Supplementary Material
Advice May Only Tighten: Untrusted Inputs to a Fail-Closed Vision-Language Gate on a Simulated Relief Robot

Anonymous Authors

Code, data and every trial log: https://github.com/fe2131-art/rescue-mind

This document holds material moved out of the main paper. Section, table and figure numbers with an S prefix refer to this document; unprefixed references are to the main paper. All numbers are generated from the same result files as the main paper. It is organized as follows. *Methods and background:* S1 development data, T1 construction and the two-model rule; S2 model selection on development data; S3 the extended related work. *Results:* S4 additional T1 analyses (decision-rule ablations, risk–coverage, weaker models); S5 campaign E details; S6 wall-clock timing; S7 further result details (studies Z, P, R, campaigns F, G and H, hazard fixes). *Failure analysis:* S8 lessons from running the real stack. *Audit:* S9 the registration audit and threats to validity. *Moved from the main paper:* S10 untrusted inputs (proof of Prop. 2, exposure and steering, cost bound, trust base, consistency–robustness curve); S11 the second checker and campaign J; S12 all registered studies, the hazard-fix candidates with T2 and campaign F, study W, camera degradations (R), the zero-shot baselines (Z) and the model of repeated missions.

S1. Development Data, T1 Construction and the Two-Model Rule

Development data. Prompts, the scoring method, thresholds and model choice were selected on 176 development images. These comprise 48 images with randomized viewpoints and 128 with lighting presets, a cardboard-box distractor and fire. The instruction parser was tuned on 40 development utterances. The later hazard fixes (main paper, Sec. III-B) also used two hazard development sets of 300 rendered images each: DH and DH2 (the latter emphasizes small early-stage fires).

Two-model rule. The two-model rule (Sec. S11) approves only if Eq. (1) holds for Qwen *and* Clef-Flash names the requested supply with confidence ≥ 0.65, presence ≥ 0.80 and hazard score below its own threshold.

T1 examples. Fig. S1 shows held-out T1 images. T1 used 60 Gazebo worlds $\times$ 2 stations $\times$ 5 viewpoints with continuous random lighting, supplies moved by up to ± 0.15 m and freely rotated, random fire positions, and three distractors. Two of the distractors never appeared during development: a blue crate and an orange traffic cone (orange but not fire).




Fig. S1. Held-out T1 images (robot camera, 640×480) with the generator's expected decision. The crate and the traffic cone never appeared during development.

S2. Model Selection on Development Data

TABLE S1
CANDIDATE MODELS WITH THE FINAL PROMPTS (`v35`: CHECK QUESTIONS OF V3.5; `i35`: INSTRUCTION PARSER) ON DEVELOPMENT DATA ONLY. IMAGES: CORRECT DECISIONS WITH FALSE APPROVALS (FA) AND FALSE DENIALS (FD). EXPLANATIONS: ONE-SENTENCE REPORTS JUDGED CORRECT AGAINST THE GENERATOR LABELS. INTENT: DEVELOPMENT UTTERANCES, WITH UNSAFE ACCEPTANCES. VRAM IN MIB.

Model	Released	Images (176)	Explanations (128)	Intent dev (40)	VRAM
Qwen2.5-VL-3B	2025-01	176/176 (FA 0/FD 0)	84/128	31/40, unsafe 0	–
Qwen3-VL-8B	2025-10	176/176 (FA 0/FD 0)	120/128	38/40, unsafe 2	17212
Qwen3.5-4B	2026-02	175/176 (FA 1/FD 0)	125/128	35/40, unsafe 2	9102
Qwen3.5-9B	2026-02	176/176 (FA 0/FD 0)	125/128	35/40, unsafe 0	18320

Models were ranked lexicographically. The first key was zero false approvals and zero unsafe intent acceptances, and the second was explanation and intent accuracy. Qwen3-VL-8B parsed more development utterances but accepted two unsafe ones. Qwen3.5-4B produced a false approval. Qwen3.5-9B was therefore chosen and frozen before the T1 and E registrations.

S3. Extended Related Work

The main paper condenses this section; the full text follows.

Failure detection and verification with foundation models. REFLECT [1] and AHA [2] explain manipulation failures in natural language after the fact. Inner Monologue [3] feeds success detection back into a planner. Du et al. [4] fine-tune a VLM as a success detector. Robots explain their actions from logs and camera images with LLMs and VLMs [5], and explanations of failures change how people respond [6], but verbalised reasoning often does not reflect what drives the decision [7], [8]; our one-sentence report is shown to the operator and never enters the decision. When a robot teammate declines to act, explaining why lets trust recover over time although the first drop is the same [9], and in robot-assisted delivery long explanations repair trust best after a failure [10]; the report therefore states the reason and the next step for the person, not only the refusal. VLM safeguards for household tasks locate the relevant objects before judging a contextual hazard [11], and image-edited hazard scenes lower VLM accuracy on anomalous objects [12]; rendering realism (lighting, materials) changes what VLM-based policies infer in simulation [13], which is why our depot studies vary one rendering factor at a time. For fire specifically, a multi-camera VLM monitor steers laboratory robots away from fires and other hazards [14], VLM-guided multi-robot navigation has been tested in simulated burning buildings with smoke and sensor degradation [15], and multimodal models detect large smoke regions but fail to localise early, small smoke, where volume matters more than contrast [16]; a fire dataset with scene descriptions supports VLM fire reasoning [17]. None of these gates a delivery on a calibrated hazard probability or audits its misses in closed loop. More generally, VLMs identify household and industrial hazards poorly [18], [19] and often take an unusual scene element for a danger [20]; training-free CLIP anomaly scoring [21] tends to follow the object category rather than its state [22]. Our gate asks one narrow question (fire or smoke near this bay) and calibrates its threshold on fire-free scenes of the same site, which is where an unusual-but-safe scene would show up as a false stop. Sentinel [23], FAIL-Detect [24] and FIPER [25] monitor learned policies at run time (FIPER calibrates its out-of-distribution and uncertainty scores conformally on successful rollouts and requires both signals to alarm); Code-as-Monitor [26] checks task constraints with VLM-generated programs, both reactively and proactively, without a calibrated threshold or a ground-truth audit; an LLM-based anomaly monitor triggers reactive fallbacks [27]; and uncertainty-aware policy steering decides when to act, ask or learn [28]. *Closest prior art.* VAP-TAMP [29] (arXiv preprint, April 2026; we read the full text) verifies the preconditions and effects of each PDDL action with a VLM. For each predicate it generates several semantically equivalent yes/no questions, takes a majority vote and, if the answers agree, asks the VLM whether the view is sufficient; otherwise the VLM proposes a viewing direction and the robot moves there, up to a viewpoint budget. A failed verification corrects the scene graph and triggers PDDL re-planning. It was evaluated by task success on 100 real mobile-manipulation trials and on injected failures in OmniGibson. The overlap with our design is real: paraphrase agreement is the counterpart of our permuted-question agreement, and VLM-chosen views are the counterpart of our look-around. To our knowledge, the differences are (i) our scores are next-token scores over a closed answer set with a threshold calibrated on development data, whereas VAP-TAMP uses textual yes/no answers and a vote; (ii) in our design every check is combined in a fail-closed conjunction, so a failed check or an extra view can only refuse or revoke, whereas in VAP-TAMP a verification result corrects the symbolic state in either direction; (iii) ours has an independent velocity guard that the VLM cannot command; (iv) in ours, memory may only reorder checks and tighten thresholds; and (v) ours is audited in pre-registered closed loop against simulator ground truth, which reports the unsafe-delivery rate and not task success. VAP-TAMP covers things we do not: PDDL task and motion planning, manipulation, and real-robot trials. Semantic anomaly detection with LLMs [30] and visual question answering that abstains rather than answers wrongly [31] are close in spirit to a gate that prefers refusal. Our check runs *before* the robot acts and is closed-set and zero-shot. Its output is a thresholded accept/reject that is audited against simulator ground truth. The closest methodological relative is KnowNo [32], which scores multiple-choice answers by next-token probability and asks a human for help, with a conformal-prediction coverage guarantee (see [33] for background on conformal prediction). Introspective planning [34] extends this line by letting the planner reason about task ambiguity. Conformal risk control [35] controls the expected value of any monotone loss (for example a false-negative rate), and Learn then Test [36] gives high-probability risk control; our study K (held-out fire miss rate $\leq \alpha$ with probability 0.9) is of that form. Conformal decision theory [37] calibrates a robot decision rather than a prediction set. Our gate is a one-shot accept/refuse threshold and not an online-adaptive controller. SayCan [38] likewise scores a fixed candidate set by language-model likelihood. We share the scoring, but we respond to uncertainty by refusing or searching, and we add permuted-option agreement as a test-time defense against letter bias.

Multiple-choice scoring and its biases. Scoring answer symbols works well when a model binds symbols to options [39]. Language models are reasonably calibrated on well-formatted multiple-choice questions [40], but they prefer certain option IDs [41] and orders [42], and their raw confidence needs validation [43], [44]. First-token probabilities of instruction-tuned models can disagree with the answer they write [45], a short prefilled lead-in makes first-token scoring pick the intended option more reliably [46], and answer formatting alone can make a VLM look incapable [47]; chat-model option probabilities are miscalibrated yet still rank correct answers, so abstaining at low confidence helps [48]. We read only the answer-letter probabilities under permuted option orders and never use the written text, and we calibrate the threshold on data rather than trust the raw probability. On embodied question answering, even the best frontier model reaches only 42.79% recall when it should abstain [49],

which supports a calibrated refuse option over trusting the model to abstain. Our two permuted questions are a minimal, deterministic form of self-consistency [50]. The Yes/No hazard question follows the polling style of POPE [51].

Safety architectures. Simplex [52], [53], shields [54] and control barrier functions [55] keep a simple verified layer between a complex decision maker and the actuators. LLM-controlled robots can be manipulated into harmful actions [56], including by action sequences whose steps each look safe [57]; benchmarks of embodied agents find that recognising a hazard rarely turns into a safe action [58], constitutions generated from data align VLM robot brains with semantic safety only partly [59], and LLM-driven robots accept discriminatory and dangerous commands [60]. Our VLM never plans: it answers closed questions at fixed checkpoints, and guardrails such as RoboGuard [61] check plans before execution; constraint layers translate natural-language prohibitions into temporal logic that filters actions [62] or compile rules into runtime monitors [63], runtime governance moves checks and override out of the agent's reasoning loop [64], and requirement-derived monitors can run as ROS 2 nodes [65]. These enforce rules on actions; our gate enforces a measured error budget on a perception decision, and its rules on advice are machine-checked against the code. Refusing is not free: language models over-refuse safe requests that look unsafe [66], vision-language models fail both ways on benign requests with hazardous images [67], and gathering more visual evidence can cut unnecessary abstentions without losing accuracy [68], which is the role the look-around plays for our gate; we therefore report false stops next to every miss rate. Responsible refusal needs stated justifications and a path to override [69], and meaningful human control asks that outcomes stay traceable to a person who understands the system [70], [71]: our refusals carry their reason in the report, the robot never overrides itself, and a person can. After a refusal, language-model planners propose corrective actions [72] or replan from visual feedback [73], and degrading gracefully rather than stopping trades reliability of the non-critical part for availability [74]; our opt-in continuation (Y) is the delivery version of that trade. Routing work prices risk on the way: robots visit as many sites as possible under survival constraints on risky edges [75], and a delivery robot whose failure ends all later deliveries is scheduled by reward-to-risk ratio [76]; we found no study that measures, for a hazard found at a station on arrival, what continuing to other stations costs in lost deliveries, time and risk, which Y measures in simulation. A control-barrier filter for human–robot teams cut collisions by 98.5% while task success fell from 67.3% to 59.3% [77]: the same trade, priced in success; we price ours in lost deliveries and time. On the verification side, an artifact study of 184 robot controllers found that tests rarely check the guarantees that the control theory promises [78], and robot-specific mutation operators yield more useful mutants than generic ones [79]; our differential and mutation tests are this link for one property, not a verified implementation. The safety filter [80] is the current umbrella for such least-restrictive overrides of a nominal controller; our velocity guard is a minimal instance and the VLM check is a perception-side gate in the same spirit. Closest in using a VLM for safety, Santos et al. [81] turn images and language feedback into a failure set that a Hamilton–Jacobi safety filter enforces, so the guarantee comes from the verified filter; ours is a union bound over check errors. RoboSafe [82] guards VLM-driven embodied agents with executable safety rules and a short- and long-term safety memory, which drives rule-based replanning and is not constrained to tighten only. In contrast to vision-language-action models [83], [84], our VLM never commands motion.

Memory for robots in changing environments. Robots increasingly keep long-horizon semantic memory. ReMEmbR [85] and Embodied-RAG [86] retrieve from a database of captioned observations; KARMA [87] adds long- and short-term memory to embodied agents, and H-EMV [88] verbalizes a robot's episodic memory. 3D scene graphs such as Hydra [89], ConceptGraphs [90] and HOV-SG [91] support planning [92] and language grounding [93]. Long-term mapping has long dealt with change [94], [95], and recent work tracks changes in dynamic scene graphs [96], [97]. These systems use memory to *answer* or *plan*. A recent preprint reports, in a small grid-navigation testbed, that acting on unaudited stale memory can be worse than having no memory [98]. Long-term agent memory is also an attack surface: corrupted entries can steer an LLM agent [99] (an LLM-agent result, not a robotics one). Memory benchmarks such as FindingDory [100] measure how well memory supports recall in long-horizon tasks, not whether acting on it is safe once the world has changed. GLOVE [101] and VLM-DEWM [102] check memory or a world model against fresh observations to keep the memory *correct*.

Object search with priors and semi-static maps. Using past observations to decide where to look first is a classic idea, and we do not claim it as ours. Relief-logistics models allocate scarce stock to shelters fairly [103], over time with trucks and drones [104], and decide where to pre-position it [105]; they take the stock record as given. Stale records are common: in 11 grocery stores, inventory-record errors grew with stock level and perishability, and audits paid off where the system overstated stock [106]; mobile robots already flag misplaced shelf items without a planogram [107], and shelf changes are detected in 3D from two captures [108]. These audit a shelf; our gate checks one bay at the moment of delivery and refuses on a mismatch. Warehouse picking robots identify items as part of picking [109], and VLM verifiers detect planning and execution errors of manipulators [110]; we found no study of wrong-item *delivery* errors with a refusal before departure. Active visual object search keeps a belief over target locations and plans where to look next, using uncertain spatial and semantic knowledge [111], inter-object relations in Semantic Linking Maps [112], or object-oriented POMDPs whose belief factorizes over objects [113]. Long-term mapping models objects or features that persist, appear or disappear (semi-static) and detects change [114], [115]; DovSG updates an open-vocabulary 3D scene graph locally as objects are moved [116].

Zero-shot object navigation with language or vision-language priors, such as ESC [117] and VLFM [118], uses a pre-trained model as a prior over where to explore, but has no mission-to-mission memory of a specific site. To our knowledge, these works optimize search efficiency (path length, success rate, map accuracy) and treat a detection, or an updated map, as the basis for the next action. We did not find in them a bound on the unsafe-action risk caused by *stale* memory at a pre-action gate. Our memory is narrower and serves a different goal: it may only reorder stations and add caution, the on-site verification is never skipped or relaxed. This restriction is enforced in code and checked by the run audit, which gives a union bound that does not depend on how old the memory is. These methods could supply the ordering prior in our setting, for example a belief over supply location, provided the gate stays unchanged; combining them is future work, and we have not compared search efficiency against them. Change detection in semi-static scenes keeps remembered features as hypotheses to be re-observed [119], and online algorithms with untrusted predictions stay competitive when the predictions are wrong [120]: the closest formal analogue of letting advice reorder visits but never decide. Among robot teams, trust weights let a fusion centre decide correctly from reports of malicious robots [121], and collaborative perception can exclude adversarial teammates by checking consensus with its own perception [122], or infer trust in robots and their reported objects from cross-robot consistency alone [123]; our credit is simpler, it only drops advice. We study a different use: memory decides *where and how carefully to verify*. We restrict it so that it can never reduce verification, and we state this as a provable invariant and test it under scripted change.

Active perception. Moving the sensor to resolve ambiguity is a classic idea [124], [125], and view planning for inspection is well studied [126]. Recent embodied agents explore until a VLM is confident [127] or let a VLM choose views [128]. Our look-around is deliberately simple: two fixed side views, used only to *revoke* an approval. This makes its effect auditable and its safety direction obvious.

Robustness and the sim-to-real gap. Image classifiers degrade under common corruptions [129], and so do detectors [130], adapted vision-language models [131] and video-language models [132]. Sim-to-real transfer is a recognized challenge in robotics [133]. Without a physical platform, we measure one part of this gap, sensor degradation, under a pre-registered protocol. What we care about is the *direction* of the errors, not only accuracy.

Untrusted inputs to embodied agents. Jailbreaks of LLM-controlled robots are now well documented: RoboPAIR [56], BadRobot [134], the policy-executable attacks of Lu et al. [135] and adversarial text attacks on vision-language-action models [136] all steer the planner through the instruction channel. A second line puts the payload in the scene: signs and printed text in the camera view hijack VLM-controlled robots [137], [138], and sensory channels (OCR, audio, LiDAR) inject prompts into ROS 2 robots [139]; typographic vulnerability of large vision-language models [140], real-world typographic images [141], instructions printed on physical objects that VLMs follow [142] and indirect prompt injection in LLM-integrated applications [143] are the underlying mechanisms; on an LLM-driven mobile robot, injected instructions measurably change navigation [144]. Memory is a third channel: poisoned or injected memory entries steer LLM agents [99], [145], planted "successful" experiences persist across sessions [146], and prompt-injection defences do not cover a single malicious memory write [147], and a recent survey lists long-term memory and multi-agent communication as under-explored attack surfaces of embodied agents [148]. Defenses in robotics mostly filter or certify the plan: RoboGuard grounds rules in a root-of-trust LLM and checks plans against them [61], and the mitigations proposed alongside the attacks are prompt defenses, two-stage verification and text masking [135], [138]. The closest conceptual relatives are structural defenses for software agents: CaMeL separates control and data flow and attaches capabilities to tool calls [149], and information-flow control labels the integrity of inputs and enforces policy deterministically [150]. We carry this idea to a physical pre-action gate: advice from memory, peer robots, inventory and operator text is typed so that it can only reorder visits or tighten thresholds, never skip or relax a check, which yields a bound on unsafe deliveries that holds for any advice (the tighten-only rule) and is evaluated in closed loop against poisoned memory and injected instructions (study A). Text in the scene is perception, not advice, and so lies outside this guarantee; we measure it separately (study S) and report the residual vulnerability.

Diverse redundancy. Requiring agreement between independently developed versions is a classic fault-tolerance technique [151]. Its benefit is limited by correlated failures [152], and model-agreement schemes for language models have reappeared recently [153]. We report both sides: the two models agree on most images, and the second model's value depends strongly on how it is asked.

Evaluation practice. We follow recommendations to report conditions, multiple metrics, uncertainty and failure modes [154]. We use Wilson intervals [155] and exact McNemar tests [156]. Domain randomization [157] is used here to build a held-out *test* distribution, not for training. Our design is fixed-n and pre-registered; sequential testing with valid early stopping [158] is a possible refinement for small n. How far simulation predicts real-world behavior is itself measurable [159]; we make no claim beyond simulation.

Fire and smoke perception. We use D-Fire [160] for study P because it is CC0 and ground-level with negative images; FASDD [161] is a larger alternative with ground-level, UAV and satellite subsets and a possible future source. Local open-weight VLMs have been used for wildfire detection from UAV imagery [162], descriptively and without refusal semantics or a closed-loop audit. SmokeBench [16] reports that multimodal models find large smoke areas but localize early, small smoke poorly and that smoke volume matters more than contrast, the same size dependence that Fig. 3 of the main paper shows for the hazard question; SAFIRE [163] benchmarks fire and

smoke understanding with 83K images and 193K questions (ten open models average 61.9%), and FailBench [164] finds that the best of 13 VLM failure detectors for robot task success reaches only 0.77 balanced accuracy.

Concurrent work (scan of July–October 2026). Concurrent work binds robot actions to a signed mission and input provenance and proves that an LLM planner cannot enlarge the authorized action set (AuthGuard-R [165]); it leaves perception errors outside the proof, and its evidence is a planner-only study without a simulator. Peer messages are an attack channel in LLM-controlled multi-robot teams, and a claim-verification filter lowers but does not remove violations [166]; injected safety-sounding phrases can also buy a halt [167], the availability price that advice credit bounds. Attenuation-only capabilities and monotonically descending integrity labels with proofs exist for tool-using software agents [168]–[170], and a recent theory characterizes which safety policies a deterministic gate can enforce [171]; none has a stochastic perceptual check whose error budget is the right-hand side of the bound. For retrieved text that would enter a VLA prompt, TOWN-VLA admits only a fixed canonical instruction [172]; our interface applies the same one-way rule to visit order and thresholds at a pre-action gate. SafeCommit [173] releases a side-effecting action only if it is safe in every world still plausible given memory and observations, and runs a low-side-effect probe otherwise, with a per-decision probability bound on a symbolic simulator; we differ in a VLM gate whose own error is the budget, a bound over missions, and closed-loop audits against ground truth. TMA-NM proves with TLC on a bounded model that origin-bound authority resists memory poisoning and places cross-agent memory out of scope [174]; peer reports are what our typed advice covers. Machine-checked guarantees for agent gates usually verify a policy model; we check the bound against a transcription of the deployed gate code, linked to it by differential testing. Pre-registered predictions and live studies have begun to appear in LLM-agent safety work [175], [176]; we found no pre-registered closed-loop robot safety audit. Verifiers that share the proposer's evidence approve many more unsafe proposals than an independent evidence source [176], which is why our side views are fresh observations rather than further votes on the front view. Two further neighbours bound unsafe outcomes from imperfect perception: CORE grounds context-dependent safety rules with a VLM and gives probabilistic safety guarantees under perception uncertainty through control barrier functions [177], and conformal shielding bounds the probability of reaching unsafe states for shields designed for perfect perception [178]; neither has a fail-closed yes/no check whose own error budget is the bound, an advice channel that can only tighten, or a pre-registered closed-loop audit. Simulated disaster and safety benchmarks for foundation-model agents exist (HAZARD [179], ESARBench for aerial search and rescue [180], SafeAgentBench [181], an audit of navigation failures [182], VLMs as runtime safety guards on egocentric video [183]); none tests whether a delivered item matches a stale inventory record at the point of delivery under a hidden hazard with a ground-truth-audited closed loop.

TABLE S2
T1 HELD-OUT TEST, REGISTERED V3.4 RULE (EQ. 1) UNLESS MARKED FREE JSON; 408 MUST-REFUSE AND 191 MUST-APPROVE IMAGES.

Model	False approvals	Correct approvals	Hazard recall	Cone alarms	s/pass
Qwen3.5-9B	5/408	187/191	67/76	0/25	0.98
Qwen3.5-4B	9/408	190/191	59/76	0/25	1.06
Qwen3-VL-8B	4/408	183/191	68/76	0/25	0.46
Qwen2.5-VL-3B	4/408	187/191	68/76	0/25	0.83
Qwen3.5-9B (free JSON)	5/408	158/191	–	–	–
Qwen2.5-VL-3B (free JSON)	0/408	57/191	–	–	–

TABLE S3
DECISION-RULE ABLATIONS ON T1: FALSE APPROVALS / FALSE DENIALS. *: EXACT MCNEMAR $p < 0.05$ VERSUS THE FULL RULE OF THE SAME MODEL.

Decision rule	Qwen3.5-9B	Qwen3.5-4B	Qwen3-VL-8B	Qwen2.5-VL-3B
Full rule	5 / 4	9 / 1	4 / 8	4 / 4
A1: question 1 only	5 / 4	9 / 0	4 / 7	4 / 4
A2: question 2 only	5 / 1	9 / 1	4 / 2*	36 / 1*
A3: no hazard question	47 / 4*	48 / 1*	46 / 8*	48 / 4*
A4: no threshold (τ_s=0)	5 / 4	9 / 1	4 / 8	4 / 4
v3.5: τ_h=0.05 (I-10)	3 / 4	4 / 1	4 / 8	1 / 30*

S4. ADDITIONAL T1 ANALYSES

Free-form generation. Free JSON (A5) gave no parse errors with Qwen3.5-9B and the same 5 false approvals, but only 158 correct approvals against 187 with scoring. All models missed largely the same small fires (hazard recall 59 to 68 of the 76 visible fires); Fig. S2 shows descriptive risk–coverage curves over τ_s.

S4.1. Decision-Rule Ablations

Table S3 isolates the parts of the rule on T1 (Table S2, Eq. 1 of the main paper). For the 9B model neither the permuted second question nor the confidence threshold changed the number of false approvals. With Qwen2.5-VL-3B, requiring the two multiple-choice questions to agree reduced false approvals, which reflects the option-letter bias reported in [41].

S4.2. Risk–Coverage

Fig. S2 varies τ_s only for description, because τ_s was not tuned on T1.

S4.3. Weaker Models and Free-Form Output

For Qwen2.5-VL-3B the second question alone approved 36 must-refuse images, and requiring agreement with the first question brought this down to 4, an instance of the option-letter bias reported in [41] (Table S3). Asking this model for free JSON (A5) left 148 of the 1 200 generations unparseable and approved 57 images; Qwen3.5-9B gave no parse errors (main paper, Sec. VI).

S5. CAMPAIGN E DETAILS

Campaign E used a new randomized world in every trial (main paper, Sec. VI); Table S4 gives the outcomes by stratum and Fig. S3 the ground-truth trajectories.




Fig. S2. T1 risk–coverage: false-approval rate versus correct-approval rate as τ_s varies ($\tau_h = 0.05$, v3.5). Markers show the frozen $\tau_s = 0.5$. The curves are flat over most of the range: the remaining errors are missed fires, which τ_s cannot fix.

TABLE S4
CAMPAIGN E (RANDOMIZED WORLDS) BY STRATUM.

Expected	Condition	n	Correct	Observed
allow	box	2	2	allow 2
allow	cone	4	4	allow 4
allow	crate	2	2	allow 2
allow	plain	12	12	allow 12
deliver after search	box	2	2	allow after search 2
deliver after search	crate	2	2	allow after search 2
deliver after search	plain	12	12	allow after search 12
deny	box	2	2	deny 2
deny	crate	4	4	deny 4
deny	plain	6	6	deny 6
deny hazard	fire	8	8	deny hazard 8
deny hazard after search	fire other	4	4	deny hazard after search 4

S6. WALL-CLOCK TIMING

Where the time goes. Table S5 breaks down the 34 delivered missions that needed no search. The check itself takes about 5.5 s: aiming, waiting until stationary, frame checks, and the scored VLM queries (3.4 s). Driving between station and shelter takes about 39 s (sum of phase medians). The check is therefore short compared with driving. The situation report adds about 5 s but could run in parallel with the drive to the shelter.

S7. FURTHER RESULT DETAILS

Real photographs (studies P and P2; full text moved from the main paper). We also asked the frozen v3.6 hazard question about 400 real photographs from the test split of D-Fire [160], a CC0 fire and smoke dataset (100 each with no fire, smoke only, fire only, and both). It flagged 298/300 of the photographs with fire or smoke (95% CI [97.6, 99.8]%) and 64/100 of the fire-free ones ([54, 73]%); the false alarms concentrate on hard negatives such as hazy hillsides and sunset clouds (details below). The scores still rank the photographs well (AUROC 0.96, not registered), so the problem is the threshold, not the question. The question thus errs strongly toward stopping on real images, which is the safe direction but




Fig. S3. Campaign E: ground-truth trajectories of all final trials, colored by audited outcome.

TABLE S5
WALL-CLOCK PHASES OF DELIVERED MISSIONS WITHOUT SEARCH (CAMPAIGNS D AND E; V3.4 AND V3.5, NO LOOK-AROUND).

Phase	Median [s]	Min	Max
drive to station	14.31	12.19	16.62
aim camera	0.50	0.50	0.52
wait until stationary	0.67	0.66	0.71
acquire and check frames	0.90	0.75	0.98
VLM decision (scored queries)	3.44	2.95	6.64
situation report (not used to decide)	5.14	3.99	8.54
drive to shelter	24.83	15.02	25.32

would cost availability outdoors, so a site-specific threshold calibration is a deployment prerequisite. Study P2 tested this: it chose wording and τ_h on 400 separate calibration photographs (recall ≥ 0.95 first, then the lower false-alarm rate), with wording `h35` and $\tau_h = 0.3$, and applied it to 400 test photographs. It flagged 282/300 of those with fire or smoke ([90.7, 96.2]%) and 18/100 of the fire-free ones ([11.7, 26.7]%), against 294/300 and 34/100 for the frozen $\tau_h = 0.05$. The registered claim (test recall ≥ 0.90 and false-alarm rate ≤ 0.20) was supported.

Conformal τ_h (study K, moved from the main paper). Split-conformal calibration of τ_h on 211 development fires (miss rate $\leq \alpha$ with probability 0.9) gave $\tau_h = 0.0050$ ($\alpha = 0.05$) and 0.0113 ($\alpha = 0.10$). On the 76 visible T2 fires the bound held at $\alpha = 0.05$ and held at 0.10 (0/76 and 0/76 missed), with 26/193 and 4/193 false alarms on 193 fire-free must-approve images, against 0/76 and 0/193 for the frozen $\tau_h = 0.05$. Exchangeability is broken by design (small fires: 27% of calibration, 7% of T2 fires); the frozen threshold was not changed.

Instruction parsing (moved from the main paper). On



Fig. S4. Study R: one held-out frame with a visible fire under the six registered degradations (severe level; the moderate level is milder). Over-exposure washes out the flames in this example. Frames that the acquisition gate (a frame-validity filter in front of the VLM) rejects count as refusals.

TABLE S6
STUDY Z: ZERO-SHOT CONTRASTIVE BASELINES VERSUS OUR CHECK ON THE HELD-OUT SETS (FALSE APPROVALS / CORRECT APPROVALS).

System	T1 FA	T1 CA	T2 FA	T2 CA
Ours (T1 v3.5, T2 v3.6)	3/408 (0.7%) [0.2, 2.1]	187/191 (97.9%) [94.7, 99.2]	0/407 (0.0%) [0.0, 0.9]	190/193 (98.4%) [95.5, 99.5]
SigLIP (so400m, zero-shot)	44/408 (10.8%) [8.1, 14.2]	191/191 (100.0%) [98.0, 100.0]	47/407 (11.5%) [8.8, 15.0]	193/193 (100.0%) [98.0, 100.0]
CLIP (ViT-L/14, zero-shot)	0/408 (0.0%) [0.0, 0.9]	2/191 (1.0%) [0.3, 3.7]	0/407 (0.0%) [0.0, 0.9]	0/193 (0.0%) [0.0, 1.9]

60 held-out utterances the hybrid parser was correct for 55/60 with 0 unsafe acceptances (TF-IDF parser: 31/60, 2 unsafe); all five errors were refusals, so they fail closed.

Study Z. The contrastive baselines used SigLIP [184] and CLIP [185] prompts for the supply and the hazard, and the same crops as our check. On development data no threshold pair gave both few false approvals and many correct ones. The contrastive scores do not separate "right supply, no fire" from the alternatives in these scenes.

T1 hazard-question false alarms. With the registered v3.4 rule, the hazard question raised false alarms on 0/25 traffic-cone images and on 0/523 images without fire. With the v3.5 rule, it raised false alarms on 0/25 cone and 0/523 fire-free images.

Campaign F, remaining misses. Six of v3.6's seven remaining misses were fires of 1 100–2 400 visible pixels with hazard scores of 0.002–0.006, which overlap those of fire-free views, so no threshold can separate them. The seventh showed 8 600 pixels at $p_h = 0.019$.

Campaign G, world set and medians. The set of worlds is defined from mask renders at all three views, so it includes the side views by construction. The medians over all delivered runs, 102 s and 122 s, are not comparable, because look-around refused most of the fire runs that the front-only system delivered.

Study P, false alarms and license. D-Fire [160] was released by its authors under CC0, as stated in the original repository's LICENSE; we used a Hugging Face mirror. Rendered fire is stylized, which motivated this check on real photographs. D-Fire's fire-free class comes from fire-surveillance cameras and is rich in hard negatives: hazy hillsides, low clouds, a smudge on the lens, red sunset clouds, glowing tents. Everyday scenes such as streets, beaches and roads scored $p_h \approx 0.01$. The question was worded to catch faint smoke ("a gray or black cloud") and thresholded at 0.05, so it errs strongly toward stopping on real images. We registered the site-specific threshold calibration as a follow-up study (P2).

Campaign H, failure types. Staleness predicts two failure types for naive memory: delivering a supply that has been moved away, and delivering where a fire has appeared since the last visit; the per-trial ledger records which occurred.

TABLE S7
STUDY R: V3.6 OFFLINE CHECK UNDER CAMERA DEGRADATIONS (T2 SUBSET). SEVERITY M = MODERATE, S = SEVERE.

Degradation	Sev.	False appr.	Fire missed	Correct appr.	Gate rej.
None (clean)	–	0/192	0/27	107/108	0
Sensor noise	M	0/192	0/27	107/108	0
Sensor noise	S	0/192	0/27	107/108	0
Motion blur	M	0/192	0/27	106/108	0
Motion blur	S	0/192	0/27	101/108	0
Defocus	M	0/192	0/27	108/108	0
Defocus	S	0/192	0/27	108/108	0
Under-exposure	M	0/192	0/27	107/108	0
Under-exposure	S	0/192	0/27	106/108	0
Over-exposure	M	0/192	0/27	96/108	4
Over-exposure	S	0/192	0/27	59/108	24
JPEG	M	0/192	0/27	108/108	0
JPEG	S	0/192	0/27	107/108	0

TABLE S8
HAZARD FIXES ON DEVELOPMENT DATA (DEV V1+V2, DH, DH2). $\tau_h = 0.05$ UNLESS STATED.

Configuration	False appr.	Correct appr.	Fires refused	One V100
v3.5: Qwen3.5-9B	46/413	357/360	165/211	yes
+ enlarged crops	37/413	356/360	174/211	yes
+ hidden-fire wording	25/413	357/360	186/211	yes
+ wording + crops (v3.6)	17/413	357/360	194/211	yes
Qwen3.5-4B	37/413	360/360	174/211	yes
Clef-Flash, original Jev request	45/413	182/360	166/211	yes
Clef-Flash, task wording	42/413	350/360	169/211	yes
Clef (task) + Qwen (v3.6), both approve	15/413	350/360	196/211	no

Study R, all conditions. Table S7 gives the false approvals, correct approvals and acquisition-gate rejections of study R (Sec. S12.30) for every degradation and severity.

Hazard fixes on development data. Table S8 compares the candidate hazard fixes of the main paper (Sec. III-B).

TABLE S9
SECOND-MODEL OVERLAP ON THE 211 VISIBLE FIRES OF THE DEVELOPMENT SETS DH AND DH2 (NO TEST DATA). A FIRE IS MISSED WHEN THE CHECKER WOULD APPROVE THE VIEW (QWEN3.5-9B V3.6, $\tau_h = 0.05$; CLEF-FLASH WITH TASK WORDING, HAZARD THRESHOLD 0.05; SAME RULES AS TABLE S8). SCRIPT: SCRIPTS/JEV_OVERLAP.PY.

	Clef-Flash misses	Clef-Flash catches
Qwen misses	15	2
Qwen catches	27	167

Qwen misses 17, Clef misses 42; P(Clef misses | Qwen misses) = 88% (Wilson [66, 97]%); Jaccard 0.34. Counting only the hazard question (score ≥ 0.05 in the hazard question alone): Qwen misses 23, Clef misses 55, both miss 23.

Campaign H, per-mission outcomes. Fig. S5 shows every mission of campaign H (main paper, Sec. VI-B).

Campaign H, case study. Fig. 5 of the main paper shows




Fig. S5. Campaign H, missions 2 and 3 of the 16 sequences. (a) Outcome of each mission under no memory (M0), naive memory (M1) and verified memory (M2); rows are sequences, grouped by scripted story (S1–S4; definitions in the caption of Table S8). No mission failed (the hatched "failed" category is empty). (b) Mission time of the eight missions whose relocation persisted, for each arm; gray lines join the M0 and M2 times of the same mission, bars mark medians. M1 times are short because M1 skips the checks.

the one mission in which M0 delivered into a fire (sequence Q09, mission 3).

Memory caution versus a global threshold (descriptive, not registered). Campaign H stored decisions, not every view's p_h, so only a partial comparison is possible from existing logs. *Fires:* the one mission where caution changed an outcome is Q09.3 (M0 $p_h = 0.035$, M2 0.049); a global $\tau_h = 0.0113$ (study K, $\alpha = 0.10$) would have stopped M0 there too, since $0.035 > 0.0113$. *False stops:* on the 193 fire-free T2 views the global $\tau_h = 0.0113$ gave 4/193 false alarms (2.1% per view, about 6% per approval with three views if independent), against 0/193 at the deployed 0.05. Caution applied in 12 of the 32 M2 missions: 8 at stations with a fire (all 8 stopped) and 4 at fire-free stations, with 0 false refusals there (Wilson upper bound 49%). That is compatible with both zero and the global rate, so a comparison at equal false-refusal rate cannot be made from these logs. What caution does buy by construction is lower exposure: the strict threshold applies at stations with a recent hazard, not everywhere. A direct test needs many fire-free missions at stations with a hazard history; we did not run one.

S7.1. Campaign H: All Paired Missions

Table S8 lists every paired mission of campaign H (missions 2 and 3 of the 16 sequences) with its outcome and mission time under M0, M1 and M2.

Repeated-mission model. The model of repeated missions, with the per-check rates measured in G and H ($p_{\text{det}} = 0.95$, $n = 44$), is shown in Fig. S11 (Sec. S12.31); its curves are computed from measured rates, so their order is a model prediction, not an observation. The figure also shows a fourth policy, M1age, a naive memory that is trusted only while its entry is recent (recency-gated, without verification); it lies between M1 and M2 in unsafe deliveries. Over the whole range of change probabilities $q \in [0, 0.5]$ the model finds no break-even point: M1 and M1age stay faster than M0, and M2 is faster than M0 at small q and converges to it as q grows, because M2 re-checks and so approaches the no-memory behavior. At $q = 0.2$ per mission the unsafe deliveries per 100 missions are 35.83 for M1, 1.95 for M2 and 1.95 for M0, with mean mission times 32.4, 71.7 and 80.3 s. Neither the single missed-fire delivery nor the 32 paired missions measure how often a real world changes; q is a free parameter of the model.

More stations (descriptive, not registered). Our arena has $k = 2$ stations, so memory can save at most one search detour. Let the supply sit at one of k stations and move, with probability q between missions, to a uniformly chosen other station, so its long-run location is uniform. Without memory the robot visits stations in inventory order and needs $(k+1)/2$ visits on average; with verified memory it first visits the station where it last saw the supply and needs $1 + qk/2$. With the detour $\delta = 30$ s measured in H, the expected saving is $\delta\,((k-1)-qk)/2$ per mission and vanishes at $q^* = (k-1)/k$. For $k = 2$ this reproduces the Monte-Carlo model above (9 s at $q = 0.2$); for $k = 8$ it is 80 s. A simulation of the same process agrees within 1 s for $q > 0$ (`scripts/h_k_scaling.py`). The safety side does not depend on k in this way: each policy checks every station it delivers from with the same rule, so Prop. 2 applies unchanged, and memory lowers the expected number of checks per mission rather than their strength. The model assumes the stations are equally far apart and that supply identification is perfect (T1: no supply false approvals in 332 images).

S8. Failure Analysis and Lessons

Running the full stack on a GPU revealed 59 problems that the 1675 offline test functions and mocked ROS runs had not; the most instructive are listed here (the full table is in `docs/FINDINGS.md` in the repository).

- **The auditor trusted the controller's sensor.** The wheel joint axis was expressed in the child-link frame after a 90° roll, so the wheels spun about the vertical axis. Odometry reported 1.5 m forward motion while the body slid sideways by 0.75 m. An audit based on `/odom` would have passed the run. Audits now use Gazebo's ground-truth odometry. Changing the wheel collision from a cylinder to a sphere reduced dead-reckoning drift on the medicine route from 0.16 to 0.011 m (worst of two repeats; `scripts/i14_pilot_p_range.py`).
- **Free-form JSON from the first VLM was unusable** on our renders. With Qwen2.5-VL-3B, 21 of 96 responses (48 images, two questions each; all 21 for the first question) could not be parsed and the model hallucinated water on empty shelves. A newer model parses reliably, but it still approves fewer correct deliveries than scoring does (Table S2). This motivated closed-set scoring. T1 measured the free-JSON method again (Table S2).
- **Middleware effects.** Best-effort QoS silently dropped 92 of 102 0.9 MB camera frames under load. The GPU lidar detected the robot's own camera mast. Slow DDS discovery on a 4-core host failed 4 of 12 starts in an aborted campaign. An interrupted supervisor left an orphaned stack that made every trial of the next campaign stop with two `/cmd_vel` publishers. All of these are recorded with their fixes; the aborted campaigns are published.
- **Stale-request latch.** Two pre-decision retries in campaign D happened while the robot was stationary: the mission node's request stream stalled for ≈0.3 s on the saturated CPU. We instrumented the mission loop, the guard and garbage collection and rejected two hypotheses (guard starvation, GC pauses). Raising control-loop priority did not remove the stalls. We therefore changed the guard: a stale zero request now holds zero, while a stale motion request still latches. With a 0.6 s stall injected before departure, the old guard failed 2/2 runs and the new one completed 2/2. Raising priority with a file capability then had a side effect: it put the exec into the dynamic loader's secure mode, which stripped `LD_LIBRARY_PATH` and broke the ROS bag recorder. A regression run caught this before any campaign.
- **A pilot exposed a threshold that was not conservative enough.** Before campaign E we ran nine trials in separate pilot worlds. In one, the robot found the wrong item, searched the other station, and delivered from it although a fire burned behind it. The fire was almost entirely hidden by the first-aid kit, and $p_h = 0.32$. On development data no fire-free image exceeded $p_h = 0.0007$, so we lowered τ_h to 0.05 (v3.5). The same pilot worlds then gave 9/9 expected outcomes. T1 was not involved: both thresholds were registered for T1 before any T1 image was scored.
- **A generator bug caught by looking at the data.** In the first T1 render, distractors meant to stand next to a supply were placed through it. The emptiness check ran after the supplies were moved. The render was discarded and the fix recorded as a pre-registration amendment, before any model scored a T1 image. A second amendment replaced the field-of-view fire label with the rendered-mask label, after we saw fires hidden behind supplies that the geometric label had called visible.

S9. Registration Audit

For every study with results, the registration commit precedes the results commit (holds). Campaign C's registration and ledger entered the repository together, so their order cannot be verified from the history. Studies whose text is marked "draft" (none; study Q's design is still on its own branch) have no results yet: their registration is the commit that puts the frozen text on `main` (the merge of the integration branch), and no trial or inference of them is run before that. The "Registered" column shows the newest commit of the text in force at the first results (or of the draft, while there are none).

S9.1. Threats to Validity

Internal. LLM inference is not bitwise reproducible across hardware and batch sizes at limited precision [186], even "deterministic" settings vary between runs [187], and hosted models drift within months [188]; we use one frozen open-weight checkpoint at FP16 on one GPU type, and record every model call with its image, so that any score can be recomputed and compared. The studies were designed sequentially, each registered after the results of the previous ones were known, so registration is confirmatory within a study but not across the program (Table S9); study K was registered after the T2 scores it reuses had been computed (`PREREGISTRATION_K.md`, offline, no new inference). The H stories are scripted so that a naive memory fails by construction; the M1–M2 contrast is therefore large by design, and the M2–M0 comparison is the one that bounds risk (`PREREGISTRATION_H.md`). The analysis scripts computed the median of an even-length list as the upper-middle element; this was fixed and all summaries regenerated, and errata with no change to protocols, endpoints or claims are in `PREREGISTRATION_{F,G,H}.md` (for H, a relocation-persist median of 79 s had been reported as 85 s). Campaign J deviated during the run (`PREREGISTRATION_J.md`): from trial J007 documentation builds shared the 4-core host, and alternating about 46 GB of weights through a 54 GB page cache made every check re-read its weights, so measured latency includes model I/O and is inflated in both arms; two first attempts failed before any VLM decision and were re-run under the registered retry rule.

Study A configuration. The mechanics pilot of A (27 runs, intent prompt i35 of v3.6) failed on the operator channel

as its rule intended: the intended advice was extracted in 0 of 12 runs, 6 of them were refused at the intent step (`unsupported_shelter`) because i35 reads a supply-station mention ("station W" in English or Japanese) as another destination, and in the others the extracted items differed from the designed ones; the file channel behaved as designed in 12/12 runs. The fix i38 (the destination question names the stations as pick-up places) was adopted by a rule fixed before it was evaluated: held-out intent set 55/60 for both prompts with 0 unsafe, and on the development half of the injection set correct acceptances 86 to 92 of 94 with 0 wrong-shelter acceptances; the test half was not used. Amendment 1 (Table S10) made every A run use i38 and regenerated the protocols with only the stack arguments changed; the first pilot ledger is kept. So A's operator channel tests the i38 parser, and the vulnerability of i35 to benign station hints is a separate finding that A does not measure. The default of the robot stays i35, and the intent study IF measures i35. The pilot texts are mechanics texts, not trial texts, but they were seen before the change, and the change was chosen after a failure of the registered pipeline; it is an amendment before any registered trial, not a blind choice.

The first pilot also showed (FINDINGS #31) that the frozen advice-extraction questions recovered the designed advice exactly in none of the accepted operator requests. Amendment 2 therefore changes the operator-channel pilot gate from "the intended advice is extracted in at least 9 of 12 runs" to "the intent parser accepts the request in at least 9 of 12 runs"; exact extraction is reported as an endpoint, not a gate, because tuning the frozen prompts on pilot texts would tune on what A measures. It was committed before the verdict of the rerun pilot. The rerun pilot (27 runs, i38) passed that gate: the intent was accepted in 12/12 operator runs, the file channel ended as designed in 12/12, and exact extraction by the frozen prompts was 0/12 (reported). The 226-trial campaign (started 2026-10-18 11:11) completed with 226 final runs and 0 failed. The file channel remains the controlled test of the rule; the operator channel measures the end-to-end system, and the tighten-only rule can only tighten whatever is extracted.

Study A, results in detail. Unsafe runs on the file channel / the operator channel: advice-following 12/12 / 4/12 (7 wrong supplies and 9 deliveries into a fire over both), behind the LLM guardrail 12/12 / 0/12, ours 0/12 / 0/12. The guardrail's question flagged 7/12 of the operator-channel attacks that aim at an unsafe delivery ("skip the check", a wrong station) and 0/12 of the same attacks arriving as a peer's advice file (no filter errors), so its benefit on the operator channel does not carry to the file channel, where the baselines are equally unsafe. False hazard reports were flagged in none of their 12 runs: both baselines then refused without visiting in all 12, ours in none (0 false refusals in 24 tighten-only runs). Price: $W = 33.7\,s$, bound $1.5W = 50.6\,s$, largest extra time 41.7 s, at most 1 extra visit, 0 lost deliveries (allowed 4). Operator channel: intent accepted in 72/72 runs, designed advice extracted exactly in 36/72 (0/18 of the false "skip" and "fire is out" texts, whose items the frozen questions never recovered), so the file channel is the controlled test of the rule and the operator channel the end-to-end one. The registered offline text set, test half scored once (112 of the 224 texts, 224 plans): wrong-shelter acceptance 0/18 (it had to be 0), intent accuracy 112/112, plans in which the tighten-only plan skips a check, refuses without visiting or fails the run audit 0/224 (the naive plan: 34/224; behind the guardrail 34/224, which flagged 26/112 texts and so removed none), and 0/772 on all 386 item sets of size up to 4 (naive 756); advice items were extracted exactly in 51/94 scored texts.

Construct. Fire labels come from rendered mask pixels (a fire is perceivable at 614 pixels or more), not from human judgment, and the fire is stylized. The Q photograph labels were audited by an AI assistant; a second pass by the same assistant over 60 random audited images (20 per class, seed 20261019, `q_label_recheck.json`, made before Q was run) found no violation of the class definitions (Wilson upper bound 6%; four borderline images not counted), which is not independent of the first pass, and the human spot-check is pending. "Delivery" means that the robot reached the shelter after approving; there is no handover, so grasping and placing are not tested.

External. All results use one arena geometry, two stations and simulation only. Procedural worlds for testing exist for Gazebo [189] and for collapse voids [190], and execution tracing against a digital twin makes robot experiments auditable [191]; our generators record every world with its ground truth so that each trial can be re-audited, but they cover one depot family and one stylised fire. LLM agents in ROS act on operator language with safeguards [192], LLM-written robot programs are checked against execution traces [193], and LLM agents controlling a simulated mobile manipulator hallucinate task success [194], which is why our audit compares each mission's record with the simulator's truth rather than with the robot's own report. The gate runs locally on one GPU with no network, as field deployments of foundation-model robots require [195]; edge VLMs trade accuracy for sub-second latency [196], and our few-second checks would need the same trade on smaller hardware. Our fire is a stylised mesh with a particle plume; simulators with physically based fire and heat transfer now exist [197], and a thermal camera fused with depth maps fire heat on a legged robot [198], while millimetre-wave radar maps through dense smoke [199]: a thermal channel would likely catch fires that the RGB views miss, and testing it is outside this paper. Last-mile delivery robots have been trialled on campuses [200], and a commercial indoor delivery robot has exploitable entry points in software and hardware [201]; our threat model covers inputs, not a compromised robot. Closed-loop studies use 8–16 pairs, which is few; Campaign H scripts its changes (V tests random ones). The real-photograph study (P) is descriptive and reports false alarms on D-Fire images; it does not test a robot. The two checkers in J share lineage (Clef-Flash is post-trained from Qwen3.5-9B), so errors may be correlated.

Statistical. Samples are small: the time comparison has 8 relocation-persist pairs, and the safety comparison contrasts




Fig. S6. Study A at a glance (numbers from `a_summary.json`, drawn by `scripts/make_a_figure.py`). (a) Unsafe deliveries under hostile advice, 12 runs per channel (12 worlds); below each arm, the worlds with an unsafe delivery. The guardrail read the peer-file items and flagged 0/12 of them (short, truthful-looking reports), and the operator channel extracted the designed advice in only 36/72 runs. (b) Steering: worlds in which no delivery happened, out of 16, and the unsafe deliveries among the others; descriptive, not a registered test. (c) Ours: seconds saved per world by truthful location advice, and seconds added per run by false advice, against the registered bound.

0 unsafe deliveries (M2) with 1 (M0), which shows only that M2 is not less safe (Wilson upper bounds 11% and 16%). Images of one world, and missions of one sequence, are not independent; we therefore add world-cluster bootstrap intervals and a sequence-level McNemar test, which are wider or less powerful than the pooled ones. Several studies are reported without family-wise correction, because each has its own registered endpoint and the claims are not pooled; the one pooled figure (H and V together, used in the abstract) is descriptive and is not a registered test.

S10. Untrusted Inputs: Proof, Exposure, Cost Bound and Trust Base

Setting. Let $A_\theta(o) = [\text{supply}(o;\tau_s)] \wedge \bigwedge_{v\in V}[p_h^{(v)}(o) < \tau_h]$ be the check of Eq. (1) with the look-around views V, and let an advice set $\mathbf{a} = \{a_1,\dots,a_n\}$ be any finite set of items $a = (\text{source}, \text{kind}, \text{station})$ with kind $\in \{\text{location}, \text{hazard}, \text{safe}, \text{skip}\}$ and station one of the site's k stations ($k = 2$ in the arena, 4 in the depot). The planner is the function $\text{plan}(\theta, \mathbf{a}) = (\pi, \theta')$ implemented in `rescuemind/advice.py`:

- π is an order of the k stations: the first applicable location item for station j moves j first (later ones, an item naming the catalog station, and any item after a reorder by memory are rejected and logged); all other items leave π unchanged. The set of stations is never changed, so π is a permutation of the order before advice.
- $\theta'_j = (\tau_s, \tau'_{h,j}, V)$ at station j, with $\tau'_{h,j} = \min(\tau_h, \tau_h^{\text{caut}})$ if some hazard item names j and $\tau'_{h,j} = \tau_h$ otherwise, where $\tau_h^{\text{caut}} = 0.01$.
- *safe* and *skip* items are rejected and logged; no item can create a refusal without a visit, a delivery without a check, or a change of τ_s or V.

Two optional hardenings, both off by default and both on the tighten-only side, change θ' further. *Scrutiny* gives the station that location advice moved to the front the caution threshold and the extra views of the adaptive rule (two poses at 0.8 m and one 0.3 m closer), whether or not anything looked suspicious; it only lowers τ'_h and enlarges V'. *Soft refusal* turns a refusal caused only by the caution threshold ($\tau_h^{\text{caut}} \le p_h < \tau_h$, nothing else wrong) into a refusal of that station and a continued search; a delivery still needs an approval of the full check at the delivering station, a real hazard ($p_h \ge \tau_h$) in a view already taken still stops the mission (the first caution-only side view ends the station's look, so a hazard in the unseen side view is neither acted on nor recorded; that station is never delivered from), and the audit accepts a soft hop only if the saved model outputs recompute it as caution-only.

Lemma 1 (every plan is verification-preserving). For every $\mathbf{a}$, $\tau'_{s,j} = \tau_s$, $\tau'_{h,j} \le \tau_h$ and $V'_j \supseteq V$ at every station j in π. *Proof.* Immediate from the definition of plan: the second component is a minimum with τ_h, the first is copied, the third is copied or enlarged. The run audit recomputes $\text{plan}(\theta, \mathbf{a})$ from the logged items and rejects the run if the logged θ' differs or is not of this form (`advice.assert_monotone`). □

The error budget. *Probability space.* A sample point is $\omega = (w, \xi)$: w is a world from the generator (supply arrangement, fire, lighting, props) and ξ is exogenous sensing and model noise (the server's answers are a deterministic function of the image, cached by its digest, so ξ is rendering and arrival-pose noise). For a station s and a pose p of the finite design

set $\mathcal{P}$ (front, L, R and the three extra poses) the frame is $o_{s,p} = F(w, s, p, \xi_{s,p})$. For $\theta = (\tau_s, \tau_h, V)$ with $V \subseteq \mathcal{P}$ the approval is $A_\theta(o_s) = C(o_{s,\text{front}}; \tau_s, \tau_h) \wedge \bigwedge_{v \in V} [p_h(o_{s,v}) < \tau_h]$. $M_s(w)$ says that s is *must-refuse*: it holds the wrong or no supply, or a fire perceivable (at least 614 pixels) at one of the three design views, evaluated at check time. *Unsafe* is defined as a delivery from some s with $M_s(w)$; a fire below the perceivability threshold in all three views is counted by the ground-truth audit, but reported separately as outside the guarantee. Counting it as unsafe would make the unsafe event larger than E below. *Assumptions.*

- A1 *Frames are exogenous:* $o_{s,p}$ does not depend on the plan, the visiting order, the visit time or the history. The pointwise step "$A_{\theta'}(o_s) = 1$ implies $A_\theta(o_s) = 1$ on the same frames" is a coupling that is only meaningful under A1; under advice the robot captures different realized frames than the baseline robot, so without A1 the implication says nothing about the law of o_s. The world is also static between the check and the delivery. A1 holds in the arena with a fixed arrival pose; real rendering and arrival-pose jitter satisfy it only approximately.
- A2 *The plan only tightens:* for every advice set $\mathbf{a}$ the plan gives each station s parameters $\theta'_s = (\tau_s, \tau'_h, V')$ with $\tau'_h \leq \tau_h$ and $V' \supseteq V$ (Lemma 1, audited by `assert_monotone`), and the base plan is the baseline or verified memory. A naive-memory base (skipped checks) passes the plan invariant relative to itself but is outside the proposition; the interlock rejects any plan with a skipped check or a refusal without a visit.
- A3 *Gate:* the robot delivers from s only if $A_{\theta'_s}(o_s) = 1$ on the frames it captured at s. This is a property of the mission node, not of the planner: every path to the delivery leg (first station, recovery hops, soft refusal, k-station search) passes through an approval of the *current* station (checked in `gazebo_waypoint_mission.py`, `stations.validate_visits`, `caution_soft.audit_caution_refusals`); it is verified after the run by audit and before the delivery only if the interlock (I-22) is on. A broken view (an invalid or non-finite hazard score, an inference error) counts as a hazard, not as clear.
- A4 *Advice does not influence* (w, ξ) (a causal, not a probabilistic-independence, statement: the advice is itself a function of ω): the adversary may be any function of ω (clairvoyant: it sees all frames), adaptive across missions, but cannot change w, ξ, the generator's law, the model, the code or the guard. Scrutiny requires look-around; the audit rejects a scrutinized approval without the extra views.

Let $E = \bigcup_{s=1}^{k} \{M_s(w) \wedge A_\theta(o_s) = 1\}$, $\varepsilon_s = \Pr[M_s \wedge A_\theta(o_s) = 1]$ (over worlds and noise), $\varepsilon_{\max} = \max_s \varepsilon_s$ and $\varepsilon_{\text{any}} = \Pr[E]$. Then $\varepsilon_{\max} \leq \varepsilon_{\text{any}} \leq \min(1, \sum_s \varepsilon_s) \leq k\,\varepsilon_{\max}$. ε_{any} depends on the site and weakly increases with the station set; it does not depend on the visiting order or on the advice. The numbers plugged in for a class (the hard one) are conditional on a class event $C(w)$, and the bound then reads $\Pr[U \mid C] \leq \Pr[E \mid C]$.

Proposition 2 (advice stays inside the error budget). Under A1–A4, for every mission and every rule that picks the order and the advice as a function of ω, $\Pr_\omega[\text{unsafe delivery when the advice is } \mathbf{a}(\omega)] \leq \varepsilon_{\text{any}} \leq \sum_{s=1}^{k} \varepsilon_s \leq k\,\varepsilon_{\max}$. Over m missions, $\Pr[\exists\,\text{unsafe}] \leq \min(1, m\,\varepsilon_{\text{any}})$ by the union bound; if the frames are deterministic and the world persists, E is the same event in every mission, so there is no accumulation.

Proof. Fix ω and an advice set. By Lemma 1 (A2) the supply conjunct is the same predicate and $V \subseteq V'$, so the hazard conjuncts of A_θ are among those of $A_{\theta'_s}$ (for every realization of the frames: the views actually taken under θ', adaptive ones included, contain those taken under θ), and each is at least as strong under $\tau'_h \leq \tau_h$: $[p_h^{(v)} < \tau'_h] \Rightarrow [p_h^{(v)} < \tau_h]$. A conjunction that contains a stronger version of each conjunct of another implies it, so $A_{\theta'_s}(o) \Rightarrow A_\theta(o)$ for every o. (The code does not compute a minimum: the caution is an extra conjunct $[\max(p_1, p_2) < 0.01]$ next to the server's label $\text{scene} \neq \text{hazard}$, and their conjunction equals $[p < \min(\tau_h, 0.01)]$; the server rounds p_h to four decimals, which can only make the caution stricter.) If the robot delivers from s and $M_s(w)$ holds, then $A_{\theta'_s}(o_s) = 1$ by A3, hence $A_\theta(o_s) = 1$ on the same frames by A1, so $\omega \in E$. This holds for every ω and for any order and advice that are functions of ω (A4), including a clairvoyant attacker. Taking probabilities gives ε_{any}, and Boole's inequality gives $\sum_s \varepsilon_s$, with no independence assumption (the sum counts stations that a mission never checks, so it is not tight). □

Sharpness. If the adversary knows ω and may name any non-default station first, taking $j^*(\omega) \in \{s : M_s \wedge A_\theta(o_s) = 1\}$ makes the first check at j^* approve, so $\Pr[\text{unsafe}] = \varepsilon_{\text{any}}$ is attained; the code allows this (any non-catalog station can be named first). A duplicate supply is needed only for the *control* to have risk 0, so that advice raises the risk; it is not needed for equality. *Without A1* (depot: the arrival pose at a station depends on the previous station and the smoke emitter moves, so detours change visit times) replace $A_\theta(o_s)$ in E by $\exists h \in H_s : A_\theta(o_s^h)$ over the reachable histories H_s; an average over histories, such as the stationary value that we measure, estimates a lower bound of this supremum and is not a bound, because the attacker chooses the order and hence the arrival history. Image-level estimates of ε_s (studies T1, W, XD) hold at the design poses; the closed-loop rate differs (T2, F).

Necessity, and what relaxing costs. Call an advice interface *relaxing* on a set R of (advice, frame) pairs if $A_{\theta'(\mathbf{a})}(o) = 1$ but $A_\theta(o) = 0$ there (a skip, a looser threshold, a dropped view, a trusted "already checked"). Under A1, A3 and A4 the proof above gives, for any interface, $\Pr[\text{unsafe}] \leq \varepsilon_{\text{any}} + \varepsilon_{\text{rel}}$, where $\varepsilon_{\text{rel}} = \Pr[\exists s : M_s \wedge (\mathbf{a}, o_s) \in R]$ is the mass of must-refuse stations whose frames the advice can relax; for tighten-only interfaces $R = \emptyset$. The converse needs two premises. (N1) *No certificate of safety*: the relaxed frame o^* used below can be produced at a must-refuse station by some world of the

generator family. A sound certificate, such as a verified sensor reading, would make a relaxing interface safe, and N1 excludes it. (N2) An approval leads to a delivery. Under N1 and N2, for every relaxing interface there is a generator law and a clairvoyant advisor with $\Pr[\text{unsafe}] > \varepsilon_{\text{any}}$. Take $(\mathbf{a}^*, o^*) \in R$ and a law that gives mass q to a world whose must-refuse station produces o^*, and mass $1-q$ to worlds with check error ε_0. Send $\mathbf{a}^*$ exactly when o^* is captured. Then $\Pr[\text{unsafe}] \geq q + (1-q)\varepsilon_0'$, while $\varepsilon_{\text{any}} = (1-q)\varepsilon_0$, so any $q > 0$ suffices when the advisor also reproduces the remaining errors ($\varepsilon_0' = \varepsilon_0$); $q > \varepsilon_0/(1+\varepsilon_0)$ suffices in general. Under N1 and N2, the bound of Prop. 2 for every advisor and every law therefore fails for every relaxing interface; it holds for a relaxing interface only if its relaxed frames carry a certificate (outside N1), and the decomposition above is the quantitative form. The naive and filtered baselines are relaxing by construction (they skip the check on "safe"/"skip"), so no such bound exists for them, whatever their measured rate in study A. A filter shrinks R; it does not empty it.

Relative, not absolute. The proposition bounds the robot with advice, and the advice-free robot, by the same budget; it does not say that the two have the same risk. The advice-free robot's order is the inventory's, which is itself advice, and it checks the stations in that order and cannot be fooled by a station it never visits: the unsafe rate with advice can exceed the control's by up to the budget of the extra must-refuse stations that advice makes the robot check. We therefore do not claim "as safe as without advice". With $k = 2$ and the hardest class (a small fire, front pixels 0, side pixels 2 000–5 000), the plug-in is $\hat{\varepsilon} = 0.062$ with look-around (Wilson upper bound 0.28), so $k\hat{\varepsilon} = 0.125$ (upper bound 0.57); front-only it was 11/16. At $k = 4$ the upper bound exceeds 1, so as an absolute number the guarantee is vacuous for this class. The measured part of the budget is the point: it shows that ε, not advice, is what to reduce (Sec. III-B).

Exposure and steering. Advice that changes *which* station is checked changes exposure, in two ways. (a) *Delivery risk.* With duplicated supply (two stations hold the requested supply; $k = 4$ in the depot) location advice can put the bay with the hardest-to-see fire first, so the unsafe rate is $\varepsilon_{\text{hard}}$ where the control's is 0 by construction; truthful advice cannot be flagged by a filter, a provenance rule or a reputation system. In the 2-station arena only $\varepsilon_{\text{supply}}$ can be exploited (0/332 observed false supply approvals), which is why study A's first 162 runs cannot see this effect. The A-steer condition of study A builds the case: 16 duplicate-supply worlds in which a small, partly hidden fire (front view mostly 0 pixels, a side view a few thousand) stands behind the *other* station, truthful location advice naming it, with arms control (clean station first), tighten-only, scrutiny with soft refusal, and naive. The registered prediction is that tighten-only advice is worse than the control (about $\hat{\varepsilon}_{\text{hard}}$ unsafe worlds in 16) and scrutiny recovers part of it at a measured cost. Sixteen worlds cannot detect an effect of that size (about one unsafe world expected; a one-sided sign test needs five): a null is reported as undetectable at this n with its Wilson upper bound, never as evidence that the order does not matter. Result: unsafe deliveries 2/16 for tighten-only advice, 0/16 for the control and 0/16 with scrutiny (one-sided sign test $p = 0.25$; the two of tighten-only advice are check errors that the advice-free check also makes), so the predicted direction is observed and not significant, as the power argument above says. What it did show is the availability cost: the first check was at the burning station in 16/16 runs with advice (0 in the control), and deliveries were lost in 14/16 worlds for tighten-only advice, 11/16 with scrutiny (delivered after a search in 5/16) and 0/16 for the control. The steering estimate is the order-independent ε_{any}, measured at image level in studies W and XD (oracle steering, about 10 times the worlds). (b) *Physical exposure.* The robot is driven toward a station that really is on fire; the guarantee is about delivery, not travel. Both are reported as exposure (the share of runs whose first check was at a perceivable fire), never tolerated as noise.

What the proposition does not say. It does not bound time or availability; extraction of items from text may be wrong, which cannot matter for safety because the guarantee holds for *any* advice set; it assumes A1–A4 (a static world between check and delivery) and that ε_s is the measured per-station rate, which differs by station and fire geometry; and it does not cover anything that reaches the decision through the camera. The destination in the operator's request is parsed separately in a closed set with an explicit rule, not by this proposition; a mis-parse of the *request* defeats everything, so the offline set of study A is registered to measure wrong-shelter acceptance (must be 0) as the evidence for it; at this commit its test half has been scored (test half, once), so this evidence is not yet available.

The requested supply (study IF). The requested supply s^* is parsed from the operator's text, so a text can change what is delivered without relaxing any check; Prop. 2 is relative to s^* and does not cover this. Study IF fed 72 texts (6 categories $\times$ 2 languages $\times$ 2 supplies $\times$ 3 wordings) to the frozen v3.6 parser (intent prompt i35, offline, nothing tuned on the set). Of the 36 flip texts, 12 were accepted with the injected supply (Wilson 95% 20–50%: fake system notice 8/12, forwarded note 2/12, appended "ignore the above" 2/12). The registered prediction that most flips would be refused as ambiguous was wrong (0 refused), so IF1 (upper bound < 0.10) is not supported (FINDINGS #32). Corrections were followed 12/12, controls and negations accepted 22/24, and 0 wrong items were accepted among them. The parsed request is therefore outside the guarantee, and the deployment guide requires a read-back of the parsed supply to the operator before departure. Study A used the intent prompt i38 (Amendment 1) and IF used i35; an exploratory re-run of the same 72 texts with i38 (not a registered claim) accepted 14 of 36 flips (Wilson [24.8, 55.1]%) and followed corrections 12/12, so i38 does not close the hole either. The fix registered before any text of a new set was parsed (I-27: do not act, and ask back, when the request names both supplies or the model keeps $p \geq 0.05$ on the other one; opt-in, v3.6 unchanged) is study IF2: 72 new texts, claims 0 of 36 switches and at least 11 of 12 controls accepted, and

the price is known in advance (corrections and negations name both supplies and are asked back). IF2 (registered before any of its texts was parsed): with the rule, 0 of 36 flip texts were accepted with the injected supply (Wilson upper bound 9.6%) and controls 12/12 (IF2-1 and IF2-2 hold: supported); without it the same set gave 15 of 36 (replicating IF on new wordings). The price is 24/24 negations and corrections asked back, as predicted. The result holds by construction for the flips of the set, because every flip names both supplies and the lexical part of the rule asks back on any text that does; a switch that does not name the other supply is not covered, and the read-back remains required.

Scrutiny and soft refusal. Scrutiny lowers the risk of the steered station only; after a wrong-supply refusal there the search proceeds to unscrutinized stations, so the worst case is still ε_{any}, and its benefit is an empirical claim (A-steer), not part of Prop. 2. A soft refusal can continue a mission that the baseline would have stopped (a hazard seen later at that station); this is covered by ε_{any}, which is a union over all stations, not by the single-station argument.

Cost bound (denial of service), in time and availability. All bounds are per mission and against the robot without advice and with the same inventory order. Let W be the time of one extra station visit (a drive plus a front check; in study A the median mission time of the control in worlds where the supply is at the other station minus that in nominal worlds, taken from arms with the same look-around and adaptive flags), S the time of the three scrutiny views, W' the time of a soft-refused visit (drive, front check and side views), ℓ the value of a lost delivery, $\bar{\delta}$ the Wilson 95% upper bound of the per-view false-alarm rate of $p_h \geq \tau_c$ on fire-free views, *measured at the caution threshold* $\tau_c = 0.01$ ($4/193$ held-out fire-free T2 views, $\bar{\delta} = 5.2\%$; the count is the same at the conformal threshold 0.0113; `scripts/k_conformal.py`), and n_s the number of views actually taken at station s (3 under look-around, 6 under scrutiny: front, L, R, L_2, R_2, N). (i) *Reordering.* The plan applies at most one location item, so wrong or late location advice adds at most *one* extra station check relative to the no-advice order ($\leq W$; $k-1$ visits, $3W$ in the depot, is the regret against the *oracle* order, not the extra cost over the control); scrutiny adds S on every location-advised mission, truthful ones included. If the advised station really burns, the mission ends at the hazard refusal without a delivery that the baseline would have made from the clean station: that is a lost delivery (an availability event with the probability that the advised station perceivably burns), not a delay of at most W. A truthful hazard report or location advice repeated at every mission is a time-budget attack of the same size per mission. (ii) *Caution.* A fire-free station that is checked under τ_c is falsely refused with probability at most $n_s\bar{\delta}$ (Boole): $3\bar{\delta} = 15.6\%$ with three views and $6\bar{\delta} = 31.3\%$ with six; if the views' alarms are positively associated (same scene, same look-alike object) the bound $1-(1-\bar{\delta})^{n_s}$ is 14.8% and 27.5% (point estimates 6.1% and 11.8%). Only stations that are visited count: the second station of the arena is visited only after a wrong-supply refusal at the first, so the earlier worst case of $3k$ views is not attained. The views of one station are strongly correlated, which makes the union smaller; the per-station rate, clustered by station and world, is the quantity to measure. The rate was measured on held-out fire-free *images*, not on the closed-loop views of one station. (iii) *Price of a refusal.* Hard refusal: the delivery is lost. Soft refusal: at most W', and the delivery is lost only if no further candidate holds the supply; with a single copy of the supply, as in the arena, a soft refusal of that station still ends without a delivery, so the benefit of soft refusal is conditional on a duplicated supply (the depot). Hence $\mathbb{E}[\Delta t] \leq W\,[\text{loc}] + S\,[\text{scr}] + \sum_{s\ \text{visited}} n_s\bar{\delta}\,(W'\ \text{soft, or}\ \ell\ \text{hard})$. In study A the sum of the per-run bounds over the 24 tighten-only runs on poison_location and poison_hazard worlds is 1.7 expected false refusals; `scripts/a_analysis.py` compares the observed count with the 95th percentile of the Poisson-binomial sum (4) and reports the extra seconds per attacked mission against $1.5W$. These are statements about the arena and the simulated rate, not about the rule: on real photographs the frozen $\tau_h = 0.05$ already gave 64/100 false alarms (P) and the calibrated threshold is 0.3 (P2), so the caution threshold should be defined relative to the site's calibrated threshold and its false-alarm rate re-measured per site. *Memory feedback.* The robot's own record is a second channel: before the I-19 fix, a caution-level alert (only the tightened threshold crossed) was written to memory as a hazard, so one false alarm at $p_h \in [\tau_c, \tau_h)$ renewed the caution for the next three missions, and with near-deterministic frames the false refusal repeated every mission. Memory now records real hazards (the standard rule flagged them) separately from caution alerts, and only real hazards renew the caution, so the per-mission bound above applies to each mission.

Over many missions: advice credit (I-24). The bounds above are per mission, so a channel that repeats wrong location advice or hazard claims at every mission (a poisoned peer memory file, a flooding operator account) multiplies them by the number of missions. Each *account* therefore holds location credit $c^{\ell} \in [0, C_{\ell}]$ and hazard credit $c^{h} \in [0, C_h]$ ($C_{\ell} = 2$ visit-equivalents, $C_h = 1$ refusal). Accounts are input channels, never labels that an item declares about itself: every item of the advice file shares one account, every item extracted from the instruction text another. A peer gets its own account only if the operator certified its identity, since free identities would multiply credit [202], [203]. An item is admitted to the plan only if the summed worst-case charge of its account's admitted items fits the credit; otherwise it is dropped and the report says so. The worst-case charge is one visit for a location item, plus $s = 0.25$ for the scrutiny views and one refusal that the scrutiny caution may cause; it is one false refusal for a hazard item. After the mission the credit is settled from the robot's own checks only (`rescuemind/advice_credit.py`, rebuilt from `mission.json` by the orchestrator). A reorder whose check confirmed the supply costs nothing. One whose check found another supply or could not decide costs one visit (the visit was spent) plus the scrutiny views. A refusal that only the tightened threshold caused (every view below

τ_h, classified from the per-view scores) costs one. Nothing is refunded: with a duplicated supply a true claim need not save a visit, so a refund could be farmed. Instead, location credit recovers by $\rho_s = 0.25$ in each mission in which a location claim of the account, applied or dropped, was confirmed by the robot's own check (at most once per mission), and hazard credit regenerates by $\rho = 0.05$ per mission, so that an account that erred once is not locked out for ever. Because a subset of an advice set is an advice set, Prop. 2 holds unchanged.

Proposition 3 (price over a horizon). For every account and every advice sequence over m missions, including one chosen adaptively with knowledge of the ledger, the location price of its applied advice (wasted visits, scrutiny views on wrong claims and refusals caused by the scrutiny caution) is at most $C_\ell + \rho_s m$, and the false refusals caused by its hazard advice are at most $C_h + \rho m$. An account whose location claims are always confirmed and whose hazard claims never cause a caution-only refusal is never throttled. *Proof.* Admission reserves each admitted item's worst charge against credit that is never negative, so every charge is paid from credit. Credit is capped at C and grows only by ρ_s (location, at most once per mission) or ρ (hazard) per mission. Summing over missions telescopes. The last claim holds because such an account is never charged. □

Not priced. A truthful claim that steers the robot to a station that really burns costs a lost delivery, which is exposure and so Prop. 2's domain. Missions that end before settlement are not priced either. A property test drives the implementation with adaptive random advice sequences: 80 sequences of 60 missions, arena and depot, with and without scrutiny, and random channels. It checks both bounds after every mission. The counterexamples of the seventh internal review are regression tests: the label spreading and refund farming that broke the first version, and caution-only refusals that were missed without soft refusal. In a descriptive 100-mission model that runs the real rule on synthetic station outcomes ($k = 4$, Fig. S7, `scripts/advice_credit_horizon.py`, not registered), credit cuts a peer that always lies from 1533 s to 59 s of extra driving, and an adaptive liar that lies whenever its credit allows to 295 s. It keeps all 4363 s that an always-right peer saves, cuts hazard flooding at the photograph-regime false-alarm rate ($\delta = 0.18$) from 33 to 5 false refusals, and changes no delivery. A peer that is right 70% of the time keeps 45% of its saving. The recovery rate ρ_s trades this consistency against robustness (Fig. S7c), and some trade-off of this kind is unavoidable. A source that alternates confirmed truths with lies is re-admitted after $\lceil 1/\rho_s \rceil$ confirmations, so it extracts cost at rate about ρ_s, the bound's rate; any rule that re-admits after a fixed number of confirmations can be exploited the same way. The closed-loop test (study B) is registered; the mechanism is off in every other study.

Closed-loop check of the credit (study B). The two-station arena ran 48 missions: three sequences of 6 missions in which an unauthenticated peer sends the same file at every mission ("the requested supply is at the other station") although it is at its own station, and one sequence in which the same advice is




Fig. S7. Advice credit over 100 missions ($k = 4$, descriptive model on the real rule). (a) Extra time against the robot without advice (dotted: tighten-only rule without credit; solid: with credit; without credit the liar and the adaptive liar coincide). (b) False refusals under hazard flooding at the simulated and the photograph-regime false-alarm rate, with the bound $C_h + \rho m$. (c) Recovery rate ρ_s (labels): time saved by a 70%-right peer against time lost to an adaptive liar.

true, each with and without the credit ledger. The deterministic model predicted 6 wasted visits without the credit and at most $C_{\text{loc}} + \rho m = 3$ with it; all three liar sequences gave 6 and 2 (exact), the throttled missions went straight to the right station, and the honest source was never throttled (0 wasted visits, identical in both arms). The interlock of I-22 permitted every delivery, and the audits found 0 failures and 0 unsafe deliveries. The credit saved a median of 129 s per six-mission sequence (the model predicted 144 s from $W = 35.9$ s; the difference is arrival jitter). The model is deterministic and the sequences are few, so this is a mechanics check, not an estimate of a rate; it covers location advice from one source at $k = 2$ only. **Related work on pricing advice over time.** In form, advice credit is a (σ, ρ) regulator [204]. Each source holds a bounded balance, an item is admitted only if the balance can pay its worst-case cost, and the cumulative price is at most a burst C plus a rate ρ per mission against any adaptive source. Learning-augmented algorithms also fall back to a robust baseline once predictions have proved costly, and recent work makes the earned "budget" for following predictions explicit [205], [206]. They compete with the best predictor, or a switching mixture of predictors [207], [208], and their trust–robustness trade-offs have matching lower bounds [209], [210]. Those results bound a competitive ratio within one instance. Ours is an additive bound over repeated missions, per source, for a gate whose safety does not depend on the admission rule, so throttling costs only availability. Availability is exactly what false-positive attacks on safeguards exploit [211]. Spending only what a baseline has earned is also the idea of conservative bandits [212], and wealth that grows with verified successes is the idea of α-investing [213]. Unlike reputation in multi-robot and multi-agent systems [214], [215], credit is settled from the robot's own check, never from peers.

Trust base. "Advice may only tighten" is a claim about one small function, so the question is what else it rests on (Table S11). The advice audit recomputes `advice.plan` from the logged plan with the same module and a log written by the node under test, so it finds bugs, not a compromised node or a wrong specification; the evidence for safety in study A is the *outcome* audit (Gazebo ground-truth

trajectory and masks), which does not depend on those logs. We therefore wrote a second implementation of the rule from its specification. It is independent in code, not in authorship: the same authors (with the same AI assistant) wrote both from the same specification, so a misreading of the specification would be shared; a third-party oracle written from the one-paragraph rule has not been done. We compared it with the implementation by differential testing over every advice set of up to four items, injected plausible bugs (skip allowed, threshold raised, view dropped, a location item deleting a station) and fuzzed raw advice files and model outputs (unknown keys, duplicates, huge numbers, NaN, bool, non-UTF-8, nested objects). This found five bugs in the implementation (an audit that missed a removed caution and NaN thresholds; a reorder that moved a naive memory's skip to an unvouched station; unexpected exceptions on non-list or deeply nested files; booleans accepted as probabilities; a NaN hazard score ignored by `max`); all were fixed and all injected bugs are now killed. A later proof review found three more, in the code the proof relies on, none of which fired in any registered campaign (every recorded side view carries a valid score, and every recorded model call that reports its server threshold reports 0.05): a side view with a missing or non-finite hazard score was counted as clear (fail-open, now a hazard), the server's hazard threshold (default 0.5) was not verified by the client, the audit or the interlock (now every call must record the configured value), and a caution-level alert was recorded as a hazard (now recorded apart). A further hardening, the delivery interlock (I-22: the velocity guard blocks delivery legs and shelter entry without a permit recomputed independently from the saved model outputs, with a guard-side shelter geofence), is implemented and off by default. Its mechanics passed a Gazebo check on 4 live missions (`experiments/results/i22_gazebo_check.log`: a nominal and a swapped delivery each received one permit, a visible fire received none, and a hidden fire with an injected "fire is out, no check needed" was refused on the left view with no permit; no permit-latency timeout). Study B runs both of its arms with the interlock; studies A and X run with it off, because the naive and filtered baselines deliver without a permit by definition. No closed-loop run uses a tampered mission node (the interlock is covered by unit tests only), so the mission node remains in the trust base.

Machine-checked monotonicity (I-23). We transcribed the code behind Proposition 2 into z3 (`scripts/verify_advice_smt.py`): the plan fold `advice.plan` with `assert_monotone`; the approval predicate as the mission node composes it (`apply_memory_caution`, `peek_hazard`, `combine_with_look_around`, adaptive and scrutiny views; scores are reals plus an *invalid* flag, labels and the suspicion trigger are free); and the loop over `stations.next_candidate`. Advice is unconstrained: any list of any length (an inductive invariant of the fold), malformed items included. All 134 queries are `unsat` (32 s on one core; $k \leq 8$ plan, $k \leq 6$ loop; the five contrast queries of the continue-after-hazard loop are `sat` by design): (P2a) approval with advice $\Rightarrow$ approval under the base plan $\Rightarrow$ approval under the v3.6 rule, on arbitrary frames; (P2b) every delivery follows an approving check at that station, the order stays a permutation of all k stations and the visits are a prefix of it, so an unsafe delivery implies E_w; (C) at most k visits, one extra visit per reorder (attained), at most six views per station (advice adds only the three scrutiny views), and an approval is lost to advice only through $p_h \geq$ the caution threshold or a flagged scrutiny view. Premises are shown satisfiable and the bounds tight. *Continue after a hazard (I-42, `-hazard-continue`, default off).* v3.6 stops at the first real hazard. The flag makes a real hazard (the standard rule on valid scores, front or side view) a refusal *of that bay only*: no delivery from it, and the search goes on with the next candidate, which gets its own full check. We added a fourth outcome class (real hazard) to the loop model: a stop in v3.6, a move to the next candidate with the flag. For $k \leq 6$ the 35 further queries are `unsat`: every delivery follows an approving check at that bay; the visits are at most k, each bay once, a prefix of the order; a hazard-refused bay is never the delivery bay; an unsafe delivery still implies E_w; and if some bay approves and nothing else stops the search (low confidence, a broken view), the mission delivers, so a hazard cannot cost a delivery that another bay makes. Advice changes a bay's outcome only from approval to hazard refusal (`apply_memory_caution` and `combine_with_look_around` are the identity on a refusal: a differential test on the real functions). Under that lemma advice of any order and any tightened set loses a delivery only if *every* bay that approves without advice was tightened; with one tightened bay (a location item plus scrutiny) a second approving bay always delivers. The same loop without the flag gives the counterexample (5 expected `sat`), and three mutants (a hazard-refused bay read as approved, the next candidate skipped, the flag read but a hazard still stops) each have a z3 counterexample. The model agrees with the real node on 60 random outcome sequences with the flag on and off. *Not covered:* exposure, since every further visit is another chance of a missed fire (also for a robot without advice that carries the flag); and the visit-order independence (A1), which the depot breaks (the arrival pose depends on the previous bay), so the control's approval of the clean bay does not transfer by the proof and study Y tests it. *Link to the code.* 9 000 hypothesis inputs (boundary values, NaN, inf, bool, out-of-range scores, malformed and adversarial advice, naive base plans) are evaluated by the real functions and by the model and agree exactly (`tests/test_i23_smt_refinement.py`); Proposition 2 also holds on the real code with the plan assertion off. Eleven injected bugs (advice loosens τ_h, skips a check, marks a station verified, refuses unseen, drops a candidate; caution boundary or side views ignored; an invalid score read as clear) each give a z3 counterexample that makes the mutated code misbehave when replayed, and each is




Fig. S8. Consistency–robustness curve of four policies as advice accuracy falls ($k = 4$; descriptive model with measured per-check rates; `scripts/advice_curve.py`). The tighten-only curve is flat by construction; see the text for what the model omits.

killed by the differential test; for relaxing interfaces z3 returns the two-world law and clairvoyant advice of the *Necessity* argument. *Trusted, and not covered.* Trusted: z3, CPython and the transcription. The ROS node is not executed: its loop is a model read off the source (guarded by a tripwire test) and the decision functions are composed as in the node. Not covered: ε, scene text, the camera and weights, frame independence (A1), the Jev-role model, the destination parse, time beyond the counts above. Three findings lie outside the proposition (advice cannot cause them): the audit raised on a run refused at an early extra view, and NaN or boolean supply confidences were accepted; all three are fixed, fail closed. *Reproduction.* `make verify` (host Python with `requirements-verify.txt`; no ROS, GPU or model weights) reruns every query, the differential and the mutants, and requires the same verdicts as the committed record; a fresh run on the authors' host took 4 minutes.

Consistency–robustness curve (model illustration, not registered). In the vocabulary of algorithms with predictions, Fig. S8 plots mission time (consistency: advice is right) and unsafe deliveries (robustness: advice is wrong) against the advice accuracy a for $k = 4$, for no advice, our tighten-only rule, a naive advice follower, and a naive follower behind a filter that drops a "safe/skip" claim with probability 0.8; per-check rates and times are those measured in G and H. The tighten-only curve is flat in unsafe deliveries by construction: in this model the fire sits only at the requested supply's station and the check's detection rate is the same at every station, so the proposition is displayed, not tested. Its informative parts are the time axis and the naive and filtered curves. The curve omits exposure: a hidden-fire station with its own ε and duplicate supply would make the tighten-only curve rise above "no advice" as a falls, which is what A-steer measures. We therefore treat it as an illustration.

S11. The Second Checker and Campaign J

This section was part of the main paper; the main paper keeps one sentence, and row J stays in Table S14.

S11.1. Method: The Second Checker

The original design of this robot asked two models (a second checker, called Jev in that design, and Qwen) and moved only when both agreed, following the idea of diverse redundancy [151], although failures are known to be correlated in practice [152]. The second checker is Clef-Flash, a decision model released by Cloudflare [216], [217] and served locally through the original second-checker API. According to its model card it is post-trained from Qwen3.5-9B, so the two models share lineage. Their diversity lies in post-training, in model size (our on-robot pair uses Qwen3.5-4B) and in the question asked, and the correlated-failure caveat applies in full. The two-model rule approves only if Eq. (1) holds for Qwen *and* Clef-Flash agrees (thresholds: Sec. S1). A hazard seen by either model stops the robot, and a wrong supply seen by either allows the one-time search. Whether the two models fit one GPU is tested in Sec. S11.2. The second model is a veto whose errors overlap with Qwen's. Qwen misses 17 of 211 development fires, and Clef-Flash also misses 15 of these (88%, Wilson [66, 97]%; Table S9).

S11.2. Results: Two Models on One GPU (Campaign J)

On T2, Clef-Flash together with Qwen3.5-4B, the pair that fits on one 32 GB V100, made 0/407 false approvals (185/193 correct). Campaign J ran this pair on the robot, paired with v3.6 on 24 worlds with swapped, empty and small-fire stations; it behaved as expected in 23/24 (v3.6: 24/24; exact McNemar $p = 1.0000$), with unsafe deliveries 1 (v3.6: 0; Wilson upper bounds 20% and 14%) and stack failures 0. Peak GPU memory was 28.0 GiB, and the median check latency was 5.1 s for the two-model system and 5.7 s for v3.6; on our host, alternating ≈46 GB of weights thrashed the page cache, so both include model I/O (registered deviation note). The registered claim (two-model design on the simulated robot, no extra risk) is not supported. Its one unsafe delivery was a small fire behind the station reached after a search; both models missed it, the correlated failure that their development-set overlap predicts (Sec. S11.1). The arms differ in model size and hazard wording, so this does not test two-model checking in general, but it is why we did not adopt the pair.

S11.3. Study JH: a Heterogeneous Second Judge with a Veto

Clef-Flash shares the lineage of Qwen3.5-9B (above), so study JH (registered before any judge score) asks whether a judge from *another family* removes the fires that remain. The gate and its threshold $\tau_Q = 0.088$ are frozen; each candidate judge (InternVL3-8B, Idefics3-8B, SmolVLM2, and the same-family Qwen3-VL as a control) scores the XD images with the gate's own question and four passes, gets a threshold from the rank rule at $\alpha = 2\%$ on the clean calibration worlds, and may only *veto*: a world is stopped if either model flags it. The judge was selected by the calibration AUC alone (InternVL3-8B, 0.976). **JH1** (registered): on the 126 perceivable fires of the test split the joint miss is at most $\lfloor 2 \cdot 14/3 \rfloor = 9$ (Qwen alone: 14), and the union stops at most 5% of the 104 clean worlds. *Result: JH1 fails (a failed claim).* With the registered selection rule the selected judge leaves 10 fires missed by both models, one more than the limit of 9. The misses of different families are not independent, as for VLM ensembles

in general, where models of one family make correlated errors and a pool of 17 models behaves like 2.5–3.6 independent voters [218], nine judges from seven families carry about two independent votes [219], and the errors of more capable models stay correlated across developers [220]: φ is 0.3–0.4 across families and 0.75 for the same-family control, whose joint miss equals Qwen's (it adds nothing), against about three joint misses expected if the errors were independent. *Factor analysis (post hoc; the registered claim stays failed).* (i) **The gain is one world.** The 126 test fires are only 91 independent worlds: the rest are ablation copies (no clutter, no surroundings, no smoke) of a base world. The gate's 14 misses are 11 base worlds, and the judges remove misses in only 3 of them; the selected judge removes 1 base world (the same world and its three ablation copies). Counted by base world the second judge takes 11 missed worlds to 10, not 14 to 10: the "29–43%" reductions of the table are copies of one world. (ii) **The rest is a perception limit, not a threshold.** 8 of the gate's misses (8 base worlds, all small tongues, with and without particle smoke) are missed by all four judges at their registered thresholds; the selected judge scores 9 of its 10 remaining misses below half of τ_J (median 0.22 of τ_J). Lowering τ_J buys misses only at the price of false stops, and for SmolVLM2 the curve is flat then collapses (no discrimination below $0.5\tau_J$). (iii) **Family matters, but little.** The same-family control rescues nothing ($\varphi = 0.75$); the other families rescue the same few worlds. The union of all four judges (a post hoc rule, not the registered one) leaves 8 misses at 5 false stops of 104: nearly the registered limit, again carried by three base worlds. (iv) **A better observation helps more than a second opinion.** XD's images also hold the 0.8 m side views and a view 0.3 m closer. With thresholds from the same rank rule on the clean calibration worlds, the gate alone misses 14 test fires (11 base worlds) from the submitted three views, 10 from the front and the left 0.8 m view (the GL arm; 1 false stop), 6 from the front and both 0.8 m views, and 5 from all six views at 0 false stops (3 base worlds). On all six views the selected judge as a veto takes this to 2 (2 base worlds, 2 false stops of 104) and all four judges to 1 at 8 false stops. These are post hoc image-level numbers on the set that produced the questions, not a result: they say where to look next (a registered replication on fresh worlds). The hard fires are hard for every model we tried on the same image, so what is missing is a better observation of the fire (a closer or wider view, as in GL), not a second opinion on the same image. We treat the second judge as a modest extra layer, not as a replacement for the look-around, and the closed-loop version (judge inside the gate) is not part of the submitted system.

S12. Studies and Results Moved from the Main Paper

The main paper follows one chain (gate, error budget, look-around, advice may only tighten, outside the guarantee) and keeps one sentence for each study that does not carry it. This section holds the rest.

S12.1. All Registered Studies

Table S14 lists all 44 studies (without the initial evaluation C); the main paper's table keeps the rows that carry the chain.

a) Which configuration each late study measured.: No single configuration is measured everywhere, so Table S15 lists the parts that differ. All rows share the frozen v3.6 check (Qwen3.5-9B, prompt set `v35`, hazard prompt `h36` with crops, $\tau_s = 0.50$, $\tau_h = 0.05$, fail-closed). The code's default is the v3.6 check with the extra views off (`-adaptive-views 0`) and the intent prompt `i35`. The extra views (I-20) were to become the default of a v3.7; XD withdrew that plan (Sec. S12), so they remain an option, and their closed-loop effect is first measured in X's advice arms.

S12.2. Hazard Fixes, Held-Out Confirmation (T2) and Campaign F

T1 left one failure mode: fires only partly visible behind the supply. Because T1 was then spent, candidate fixes were compared on development data only, including a new set of small early-stage fires (DH2), since the first hazard set (DH) contained just four visible fires under 10 000 pixels. The candidates were enlarged overlapping crops for the hazard question, a hazard wording that names small, partly hidden or cut-off fire and smoke, and Clef-Flash (Sec. S11). The wording together with the crops is v3.6. Table S8 shows the results. The wording did most of the work: missed fires fell from 46 to 17 of 211 when combined with crops, and correct approvals did not change. Clef-Flash refused half of the correct deliveries when asked the original second-checker questions, which concern the safety of a *passage*; with task-worded questions it reached 97%, and agreement with Qwen gave the fewest false approvals, but the two models need 37 GB together, which does not fit on one V100.

Held-out confirmation (T2, registered, 600 new images). The new draw happened to be easy: v3.5 already made 0/407 false approvals (190/193 correct approvals), so no configuration could improve on it; the registered claim was not supported. The configuration selected on development data (Clef-Flash with task wording plus Qwen3.5-9B v3.6, 37 GB) made 0/407 false approvals with 184/193 correct approvals, and Qwen3.5-9B v3.6 alone made 0/407 with 190/193. Clef-Flash *alone*, given the task-worded questions, made 0/407 false approvals with 187/193 correct approvals in a single forward pass (median 0.6 s per image, against 3.4 s for the scored Qwen queries; Table S5).

Closed loop, small fires (campaign F, registered, paired). Each of 24 worlds had a small fire just behind a station or no fire, and was run with v3.5 and with v3.6. In the 13 worlds where the fire was visible at the checkpoint in both runs, v3.5 delivered despite the fire 12 times and v3.6 7 times (exact McNemar $p = 0.0625$, not significant; 5 discordant worlds favored v3.6 and 0 the other). Neither system stopped falsely in the fire-free runs (v3.5 0/11, v3.6 0/11); with so few runs this says little. Six of v3.6's seven remaining misses were

small fires whose hazard probabilities overlap those of fire-free views (Sec. S7). A wording or a crop cannot add the pixels that the front view lacks, which led to the look-around of the main paper (Sec. III-B).

S12.3. Study W: Look-Around at Image Level, and Prior Mechanisms

Design. Study W (registered, image level, frozen v3.6: Qwen3.5-9B, hazard wording `h36` with crops, $\tau_s = 0.5$, $\tau_h = 0.05$, nothing tuned on W) replays the check offline. It has 150 new fire worlds (small fire 0.45–0.62 of the model, 0.55–0.75 m behind the requested station, random lighting and prop poses as in F/G/H) and 75 fire-free twins with the same lighting, props and poses. Each world is rendered from the front checkpoint (F) and from 0.4 m left and right (L, R), each with its own arrival-pose error drawn from the spread measured in the 132 nominal closed-loop runs of F, G and H, plus three extra poses (L2, R2 at 0.8 m; N, 0.3 m closer; Amendment 1). A fire world is *perceivable* if some of F, L, R shows at least 614 fire pixels in a flat-color re-render; the label is made from the render, never from a model. W tests neither navigation, timing nor the controller.

W-a, primary and secondary results (unit: world).

- *Perceivable worlds.* 150 of 150 fire worlds are perceivable; 127 are shown by the front view and 23 only by a side view. No fire is hidden from all six views (0/150, Wilson upper 2.5%), so the label excludes nothing here and the share of a fire that no view shows is bounded only by that interval.
- *W-a2 (primary; "ε is tightly bounded": Wilson upper bound ≤ 0.15).* Look-around approved 3/150 perceivable fires (2.0%, 95% CI [0.7, 5.7]%); the upper bound 5.7% is below 0.15: supported. On the six-view label the bound is the same, 5.7%. The missed worlds are wf014, wf076, wf134; all three are side-only fires: look-around missed 3/23 side-only fires (13.0%, Wilson [4.5, 32.1]%) and 0/127 front-visible ones (upper 2.9%). The headline rate is therefore diluted by the 127 front-visible fires. Every fire stands straight behind the requested supply (0.55–0.75 m back, lateral ± 0.15 m), the geometry the side poses were designed for; lateral, low and behind-another-prop placements are not sampled. Of the 76/150 front-only misses, 54/76 were front-visible fires. Sensitivity to $\tau_h \in \{0.02, 0.05, 0.10, 0.20\}$ (no threshold chosen on W): 3/3/3/4 misses.
- *W-a1 (descriptive after Amendment 2; true by construction).* Front-only approved 76/150 (50.7%; 22/23 of the side-only fires). Look-around caught 73 of those and added none (exact McNemar $p = 2.1 \times 10^{-22}$, a sign test on a subset relation).
- *W-a3 (cost; "extra false stops ≤ 0.10").* On the 75 twins, side views stopped 0/75 approved missions (upper 4.9%); correct approvals were 75/75 for both arms. Cost claim: supported.
- *Oracle steering (Amendment 2).* With the 150 fire worlds as must-refuse stations, $\varepsilon_{\text{any}}(k)$ (probability that at least one of k distinct random fire worlds is approved; exact) is 4.0% ([1.4, 11.1]%) for $k = 2$ and 7.8% ([2.7, 21.0]%) for $k = 4$ with look-around (a computed value for independent draws, not a measurement on k stations of one site; the upper bound at $k = 4$ is above the 15% line registered for one station), and 75.8% and 94.3% front-only. The k stations come from different worlds, so lighting and arrival-pose draws are independent; a depot shares them (study XD).
- *Reference v3.5* (hazard wording `h35`, full image only, same images): front-only 144/150, look-around 48/150 (upper 39.8%). With the older wording and no crops, look-around alone is not enough; the v3.6 wording and crops are needed as well.

Suspicion-triggered extra views (Amendment 1, I-20). If a world passes look-around but some view scores at least $\tau_{\text{sus}} = 0.005$ (fixed on DH and DH2: the 90th percentile of fire-free views, covering 17 of the 23 visible development fires missed at 0.05), the robot also looks from L2, R2 and N and refuses if any scores at least τ_h. Adaptive views missed 2/150 perceivable fires (upper 4.7%) against 3/150 for look-around; paired discordant worlds 1 vs 0 (adaptive-only vs. look-around-only misses; exact $p = 1.0000$). The trigger fired on 1/150 fire worlds and on 2/75 twins ([0.7, 9.2]%), and correct approvals on the twins stayed at 75/75. *Adoption rule, fixed before the scores* (I-20, `docs/IMPROVEMENT_LOG.md`): adopt as the v3.7 default if (1) paired misses are not higher than look-around's with at least one fewer, and (2) correct approvals on the twins fall by at most 3 of 75. Criterion 1: supported (the difference is one world); criterion 2: supported (no loss). Decision: adopted as the v3.7 default. This is the minimum evidence the rule asked for; one world cannot show an effect, and the closed-loop test of adaptive views is not run. Scrutiny policies (addendum): the caution threshold 0.01 on F, L, R alone removed no miss (3/150); with the three extra views always taken as well it removed all (0/150 misses, upper 2.5%; $p = 0.2500$ for the three discordant worlds, descriptive) at 0/75 extra false refusals on the twins. *Revert rule (fixed on 2026-10-18, before XD was rendered or scored; IMPROVEMENT_LOG I-20):* the v3.7 default is withdrawn, and I-20 stays only inside scrutiny, if any of (a) the extra views fire on more than 15% of the fire-free twins in XD (O3), (b) I-20 lowers correct approvals on fire-free worlds with the right supply by 5 points or more compared with look-around, or (c) I-20 reduces none of look-around's misses on the perceivable XD worlds. The outcome is reported either way. **Outcome (XD): withdrawn** (the verdict code, `xd_analysis.i20_revert_verdict`, was committed as `64bd2e5` on 2026-10-19 at 00:02, before the XD scores were computed at 02:56) by criterion (a) alone. (a) The extra views fired on 65/76 fire-free twins (85.5%, Wilson [75.9, 91.7]%). (b) Correct approvals did not fall: 75/76 on the twins that had extra views, the same as look-around on them. (c) They removed 12 of look-around's 14/151 misses on the perceivable worlds and added 0 (exact $p = 0.0005$). The

rule was applied as written although the extra views reduced misses; a variant with a higher or per-site τ_{sus} would be a new registration, not a change of this one.

W-b, closest prior mechanisms on existing images (T1 and T2 pooled, 1199 non-ambiguous images: 815 must-refuse, 384 must-approve). Every system keeps our supply check and changes only the hazard rule. The matched arm *ours-full* asks the h36 wording on the full image only. A vote in the style of VAP-TAMP [29] asks five paraphrased yes/no questions and refuses if at least three say Yes (probability ≥ 0.5). A conformal set in the style of KnowNo [32] uses the hazard-yes probability of the v3.5 wording with a split-conformal quantile from the 597 labeled DH and DH2 images ($\alpha = 0.05$ and 0.10); the system approves only if the set is exactly {No}.

System	False approvals (of 815)	Correct approvals (of 384)	vs. ours-full, false approvals	Verdict
Ours, deployed (h36 + crops)	1/815	–	–	secondary
Ours-full (matched)	3/815 (0.37%)	377/384	–	reference
Vote, majority at 0.5	9/815 (1.10%)	377/384	6 vs 0, $p = 0.031$, Holm $p = 0.094$	not distinguished
Conformal $\alpha = 0.05$	1/815	303/384 (78.9%)	fewer false approvals, but 74 fewer correct ones ($p = 1.1 \times 10^{-22}$)	pays availability
Conformal $\alpha = 0.10$	3/815	377/384	identical decisions	not distinguished

The registered verdict ("the mechanism matters": fewer false approvals, Holm $p < 0.05$, and correct approvals not lower by more than 5 points) holds for 0 of the three primary baselines: **not supported**. The vote has six more false approvals than ours-full (raw $p = 0.031$, Holm $p = 0.094$ over three comparisons); the conformal sets either match ours-full or buy their fewer false approvals with a large loss of correct approvals (class-conditional calibration at $\alpha = 0.05$ approves 8/384 must-approve images). Against the *deployed* check (full image plus three enlarged crops) the vote is worse (8 vs 0 discordant images, Holm $p = 0.023$; claim supported), so the separation comes from the whole deployed check (wording plus crops); the wording alone (ours-full) is not distinguished from the vote. On the small visible fires the deployed check approved 1/6 and the vote 5/6. W-b has no closed loop, a single model family and one conformal score; calibration images (7% small fires) are not exchangeable with the test images (27%).

S12.4. Study S: Signs in the Picture

Study S renders 64 worlds three times: without a sign, with an attack sign ("Answer C", a letter tied to the unpermuted option order, a letter invariant under the permutation, a mislabel, "SAFE – NO FIRE" beside a visible fire) and with a benign text. Every attack sign was legible to the model (yes). Table S16 counts the must-refuse worlds that each system approved. Ours approved the same worlds with and without a sign (0 flips in 42 worlds, Wilson upper bound 8.4%); so did the one-pass variant, the look-around variant, the OCR mask and the ignore-text prompt; the full-image variant had one flip. The free-form baseline is the exception: it approves some worlds that it refused without the sign, and a benign text moved it in 6 worlds (ours 0). Seven hypotheses were registered; two hold (the naive letter does not work; the visible fire is not talked away). The three that predicted a residual vulnerability of ours (the permutation-invariant letter, the mislabel, the letter as an availability attack) found none in 6, 10 and 6 worlds, so no residual is shown. The hypothesis that the unpermuted pass is fooled by its own letter also failed: the one-pass check was not fooled in the 6 worlds. Hence the registered claim that the *permutation* explains the robustness is not supported and counts among the failed claims of the paper; what the data support is only that these non-adaptive signs did not flip the model at the prompt used. The masks changed no decision (no approval lost among 56/56 legitimate images, no new false approval on sign-free worlds), so the defences had nothing to close; an adaptive or detector-aware sign, off-axis text and other models remain untested.

S12.5. Study XD: the Check in a Cluttered Depot (Image Level)

Study XD replays the frozen v3.6 check on 308 rendered worlds of the four-station depot (pallets with wrapped cartons, racks, clutter, random lighting; 1 932 images), 152 of them with a fire or smoke behind the checked supply (151 perceivable from at least one of F, L, R; 24 only from a side view) and 76 fire-free twins. Table S17 gives the misses (a hazard world that ends in an approval). The hard class, small partly hidden flames, is the class the registered bound was set on: look-around approved 12/100 (Wilson [7.0, 19.8]%), so the registered claim is not supported. Pooled over all classes the depot's 14/151 compares with 3/150 for W's small hidden fires in the arena (Fisher $p = 0.010$). Smoke-only worlds were missed less often than flames (1/20), against the registered prediction P1, which is reported as failed. The relative claims O1, O2 and O4 hold (supported, supported, supported) and the cost claim C1 holds (supported: 120/121 fire-free correct-supply worlds approved by the front check, 118/121 with look-around), but O3 fails (not supported), so "the relative ordering transfers" is not supported. With look-around the order-independent ε_{any} on the hard class is 22.7% ([13.5, 35.7]%) for $k = 2$ and 40.5% ([25.2, 58.7]%) for $k = 4$ (independent draws, image level): the exposure to steering is larger in the depot than in the arena. Recalibration (registered: the largest threshold on a fixed grid whose recall on the calibration positives is at least 0.95) found none (none); at the frozen $\tau_h = 0.05$ the test-image recall was 192/243 (79.0%) with 2/279 false alarms (0.7%), and the claim "the calibration is usable" is not supported. Exploratory, written down before it was computed and post hoc with respect to XD (I-33): a per-site τ'_{sus} of 0.0191, the level that leaves at most 15% of the calibration split's fire-free worlds above it, triggered the extra views on 0/45 test twins and lost no correct approval, but removed only 4 of the 9 look-around misses of the test split (rule: at least half), so it is not promising; the extra views trade misses against triggers along τ_{sus} (at 0.005, 2/90 misses are left and 41/45 test twins trigger). A second exploratory rule (I-35,

also written first): the smallest τ_h on a grid whose look-around correct-approval rate on the calibration split is at least 95% is 0.05, the frozen value itself, so a site-calibrated threshold would not have changed the test split (hard class 9/60 misses); the residual misses are not a threshold artifact. For information only, a lower τ_h of 0.02 would have approved 8/151 fires and 114/121 correct worlds (descriptive; no threshold was chosen on XD). None of the five realism ablations moved the miss rate or the false-stop rate after Holm correction. XD-R: on 200 real fire-free warehouse photographs (Commons, frozen before scoring) the frozen $\tau_h = 0.05$ flagged 11/200 (5.5%, Wilson [3.1, 9.6]%; 9/102 of them warehouse interiors) and the P2 threshold 0.35 flagged 0/200 (upper bound 1.9%). The registered claim was stated at the depot τ^*, which does not exist (XD-4 found none): the registered analysis therefore returns "not supported" (and prediction P3, $\tau^* \leq 0.20$, is not met); the criterion itself, at most 20%, holds at both thresholds that do exist. We list it here and do not add it to the failed-claim count. The I-20 verdict is in Sec. S12.

S12.6. Study X: the Closed Loop in the Depot

Study X (`f0ddd78`, 2026-10-19) ran the 59 registered trials once, in the four-station depot with the frozen v3.6 check; the protocol commit (the steering selection, the protocol and the design masks, `238ea9f`) precedes the first trial, whose run directory was created three seconds after it; Tables S9 and S10 list the study's registration and Amendment 1. The draft said 80 runs; the registered steering selection admits a candidate world only if its fire is invisible at the front pose but visible from a side, and "is never padded": 3 of 24 candidates qualified, so X-s has 3 fire worlds and 2 fire-free twins (15 runs; the twins are the fire-free versions of every second selected world, so the third world has none) beside X-a (16 runs) and X-m (28 runs). A mechanics pilot on separate worlds found one fault before any X trial (a denial in an empty depot was not classified as an expected denial; Amendment 1, I-34) and passed after its fix. 2 X-m runs failed and stay in the counts: X002 (wheel odometry diverged by 0.25 m from ground truth after the supply was confirmed) and X012 (the true pose never reached the shelter), both navigation or infrastructure faults (cause classes b and c of the registration) and no perception outcome. Because a failed M2 run breaks the memory chain of its sequence, the later M2 missions of XM2 and XM4 are excluded from the paired analysis (7 pairs remain, from 3 sequences). The one retry that the protocol allows (a failure before any VLM decision) was used once (X058, a stack failure, the second attempt is the scored run).

X-a. All four behaviour cells ended as designed (16/16): empty depots were denied after four checks, and the fire, smoke-only and alternative-flame cells were denied as hazards at the first station; no delivery into a fire (0/12, Wilson upper bound 24.2%). XA1 and XA2 hold. *X-m.* With $k = 4$ stations verified memory visited 1.14 stations per mission against 3.29 without (saving 2.14, cluster-bootstrap CI [1.00, 2.67] over 3 sequences; the exact one-sided sign-flip test over 7 pairs gives 0.0078, the smallest value that 7 pairs can reach, and 7 of 7 pairs favour memory). The registered design saving (1.75) and the k-scaling model (1.1) lie inside the interval, and visits equalled the prediction in 28/28 scored runs; no wrong-supply delivery occurred. K1, K2 and K3 hold, so the claim "the memory saving at $k = 4$ is consistent with the k-scaling prediction" is supported, with the caveat that K2 is a low bar and that three sequences are few. The saving in time is 75 s per mission ([33, 96]), and the depot's own slope is 36.8 s per extra station against 29.5 s in the arena; no stale proposal arose in these sequences, so the price of a stale proposal is not measured here.

X-s (descriptive). S1 to S3 hold: the advice was applied in 10/10 advice-arm runs (the first station planned was the steered one), no advice audit failed, and the control never delivered into the fire (0/3; it delivered from the clean first station). Tighten-only delivered into the fire in 1/3 worlds (exact upper bound 86%, 95% Wilson [6, 79]%) and refused 2/3, so truthful advice cost 2 deliveries that the control made from a clean station. Scrutiny delivered into no fire (0/3) and refused all 3, but it also refused both clean twins (2/2), so it delivered in none of the 5 worlds; S4 (fewer unsafe deliveries than tighten-only, $p < 0.05$) is not supported (exact McNemar $p = 1.0$), as the registration expected for lack of power. This is a count in 3 worlds and not a rate; the steering rate is the image-level ε_{any} of W and XD.

Cause of each deviation (registered taxonomy). **X029** (tighten-only delivered into the fire of XC05) is a perception outcome (a): every view of the steered station scored below $\tau_h = 0.05$ (at most 0.014), at the level of the control's views of the same station and of its clean twin's. **X041, X054** (scrutiny refused the clean twins) are the lowered threshold at work, not a perception of fire: the front views of the twins scored 0.0102 and 0.0124, just above 0.01, inside the range of all fire-free views of the steered stations (0.004 to 0.020). In the fire world XC05 scrutiny refused at 0.0128, which is the twin's level (0.0124) and the level at which tighten-only had approved (0.0132): that refusal is not a detection. XC24 was refused at 0.0312, above every fire-free view (a weak signal), and XC15 at 0.2174 was a detection (tighten-only caught XC24 and XC15 with a side view at 0.2121 and 0.7187). Scrutiny therefore did not repair the steering miss by looking harder but by refusing at a threshold the clean views cross: the fire-free twins were refused as often as the fire worlds. One front view is also a noisy measurement: the robot stops at slightly different poses and the smoke moves, and XC15 scored 0.009 at the front in the tighten-only run and 0.2174 in the scrutiny run, so a single refusal is not read as a detection. X002 and X012 are classes (b) and (c); no deviation falls in class (d), so the depot sentence stands.

Both advice arms gave up a delivery in worlds where a clean station held the supply: the refusal stops the mission, whereas continuing the search after a hazard refusal (a design the registration does not cover) would keep the delivery. Study Y (Sec. S12.7) registered and ran it.

S12.7. Study Y: Continuing After a Hazard Refusal in the Depot

Study Y (`9c0b5e8`, 2026-10-19, the first commit on `main` that holds its pre-registration; the registration commit with the design masks and the pilot ledger carries an OpenTimestamps proof, hashes only, attested in Bitcoin before the first trial) measures the opt-in flag `-hazard-continue` (I-42; default off). v3.6 ends the mission at the first real hazard; with the flag a real hazard (the standard rule on valid scores, front or side view) refuses that station only: nothing is delivered from it and the next candidate of the order gets its own full check. Proposition 2 is unchanged (per station: approve with advice implies approve without), the loop proofs hold with the flag (Sec. S10: 154 queries, three mutants with a counterexample each), and the flag changes availability and exposure, not the per-station guarantee. Y runs 45 steering runs (the five X steering worlds, three repeats, three arms, every arm with the flag) and 6 runs in worlds with a visible fire at the only station that holds the supply; 51 runs in all, once, 0 failures. It reuses the worlds of X, so it is *not* blind: the X outcomes shaped the predictions, and the preregistration says so.

Claims (all as registered). Y1: every advice run in a perceivable fire world that refused the steered station delivered from another station, in 15 such runs, with no exception; Y2: with no clean station no run delivered (0/6), every run checked all four stations (6/6 ended in a hazard denial after a search, 6/6 with the fire station among the recorded hazard refusals); Y3: no audit failure and no delivery from a refused station; Y4: at most 2 stations per run. Result: Y1-Y4 hold. Against the control of the same world and repeat, tighten-only lost 0 and scrutiny 0 of 15 deliveries (in X without the flag: 2 and 3 of the fire worlds, and scrutiny delivered in none of the clean twins). Descriptive, in the fire worlds: unsafe deliveries 0/9 (control), 3/9 (tighten-only, exact upper bound 66%) and 0/9 (scrutiny, 28%); the steered station was refused in 6/9 (tighten-only) and 9/9 (scrutiny) of the runs, and the mean mission took 88 s (control, 1.0 stations), 124 s (1.7) and 128 s (2.0). In the fire-free twins scrutiny refused the steered station for caution in 4/6 runs and still delivered in 6/6 (the price is one more visit). Prediction P2 has two halves: the safety half holds (scrutiny delivered into no fire), the twin half held in 4/6 of 6 runs only (the two XC24t approvals scored $p_h =$ 0.0072–0.0087 at the first check, below its 0.01).

What Y does not fix. Tighten-only advice still delivered into the fire of XC05 in 3 of 3 repeats (registered prediction P1, which therefore holds): every view of the steered station scored below τ_h, a perception miss that no continuation can repair, and it is the same cause as in X (cause class a). The flag buys *availability*; it does not buy detection. Y also does *not* measure the exposure price: the clean station of every Y-s world is fire-free, so a second visit never faced a second fire (the bound is the image-level ε of XD per visited station), and the visit-order independence assumed by the proof is broken by the depot (the arrival pose depends on the previous station), which is why Y1 is an empirical claim and not a corollary. A hostile hazard report that names every station still tightens every station, a denial of service that the flag does not remove. 44/51 runs were as designed (86.3%). *Cause of each deviation* (registered taxonomy; post hoc readout of the saved model outputs, `scripts/y_readout.py`); all 7 are perception outcomes, class (a), and the records support it: the three XC05 misses (Y015, Y028, Y030) were approved because the first check of the steered station scored $p_h =$ 0.012–0.016 against $\tau_h = 0.05$ (the XC05 fire sits at the noise floor of the check, as in X); the four twin runs (Y033, Y038, Y041, Y051) were refused for caution by scrutiny because the fire-free station scored $p_h =$ 0.0100–0.0145 at or above its threshold 0.01 (the same range as the XC05 fire itself, so scrutiny cannot tell them apart), then delivered from the other station (expected action `ALLOW`, observed `ALLOW_AFTER_SEARCH`); no delivery was lost. No deviation is of class (b), (c) or (d). The decision rule fixed beforehand (Y1–Y4 hold) puts the flag into the v3.7 recommendation as an opt-in option next to `-caution-soft`; the default stays off.

S12.8. Study YE: The Exposure Price of Continuing

Study Y showed what `-hazard-continue` buys and said what it did not measure: the price. Every further visit is another chance of a missed fire, and the clean station of every Y world was fire-free. Study YE (registered before its first trial; the registration commit carries an OpenTimestamps proof, hashes only, attested in Bitcoin before the first run) measures the price where it exists: depot worlds with *two* fires. The first station of the inventory order holds a large visible fire; the second holds the same supply and a small partly hidden fire (the hard class of F, G, H, W and XD), picked from 60 candidates by their design masks alone (at least 614 fire pixels from the front or a side pose, no model score; the first 12 in id order). Without the flag the robot stops at the first fire (v3.6) and cannot deliver into a fire; with the flag it goes on to the second station, where the check can miss the fire. 12 worlds, two arms (`v36`, `hc`), 24 runs, 0 failures; no advice is involved.

Result. YE1 (v3.6 stops at the first station and delivers nothing) holds: 0/12 unsafe deliveries. *The price* (YE3, a bound and not a rate): with the flag the robot delivered into the second fire in 2/12 worlds (YE01 and YE09; exact upper bound 44%), next to XD's image-level rate of 12/100 for the same class; the registered prediction P1 (at most 3 of 12) holds. Mission time 148 s with the flag against 33 s without (the flag searches on through every station after two refusals).

YE2 failed as registered. The claim said that every `hc` run visits two stations. 10/12 visited four: a run that also refuses the second station goes on through the remaining candidates (the stations that do not hold the supply), exactly as the flag is specified and as Y-c showed (four of four). The wording was wrong; it stays in the failed-claim list (the thirteenth) and was not amended. *Post hoc reading* (`scripts/ye_readout.py`, not a registered analysis): in 12 of 12 `hc` runs the first station was refused for its hazard, the second was reached, nothing was delivered from the first and




Fig. S9. Study Y at a glance (numbers from `x_summary.json` and `y_summary.json`, drawn by `scripts/make_y_figure.py`). (a) Worlds or runs without a delivery per arm: in X the search stops at the refusal (five steering worlds), in Y it goes on (15 runs per arm). (b) Unsafe deliveries in the fire worlds (X: 3 worlds, Y: 9 runs): the flag does not repair a perception miss; the tighten-only arm still delivers into the XC05 fire. (c) The price of continuing: mean mission time and visited stations in the fire worlds (Y). X and Y share their worlds, so (a) and (b) are not independent.

no audit failed. The decision rule fixed beforehand says that a failed YE2 means the flag is described as "not working as stated": the condition is met, and the contradiction is between the YE wording and the flag's own registered behaviour (Y, the code and Y-c agree). The flag stays opt-in either way. The mechanics pilot gate encoded the same "two stations" check and passed only because the pilot's `hc` run missed the second fire, so it never took the detect-and-continue path (a check that passes on the failure branch is not a check); the pilot world, YE01, is also one of the twelve (the protocol was already bound).

Cause of the two misses (registered taxonomy, class (a), perception outcomes): the check scored the second station 0.0088–0.0107 at the front and at most 0.021 from a side, below $\tau_h = 0.05$. Descriptive only: both fires are hidden at the front pose (design mask 0 pixels); of the front-hidden worlds 2/3 were missed (the third, YE05, was found from a side view, $p_h = 0.12$) and of the front-visible worlds 0/9. *Reading.* The flag trades availability (Y) for an exposure that equals the miss rate of the check at the *next* station; it is paid only where a second hazard exists and nothing in this paper removes it, which is why the flag stays opt-in. *Limits:* one depot, twelve worlds, so an upper bound with a wide interval; both fires are the hard case; the arrival pose at the second station depends on the first (assumption A1 of Proposition 2 does not hold in the depot), which the closed loop includes and the image-level rate does not.

S12.9. Study YF: Study Y on Fresh Worlds

Study Y reused the five steering worlds of X (not blind, and its tighten-only miss is one world, XC05, three repeats). Study YF repeats it on worlds that nobody had seen: candidates from a new seed, the X selection rule on their design masks (front $\leq$ 20 px and a side pose $\geq$ 614 px, no model score), the first six in id order as fire worlds, the fire-free twins of every second one, three arms with the flag, one run per world and arm (6 fire worlds, 3 twins, 27 runs, 0 failures; registered before the first trial, OpenTimestamps-attested). *Amendment 1* (before any trial and any model score): only 3 of the first 48 candidates were eligible, so a second batch of 48 was added and the first six eligible over both batches were taken (7 of 96 eligible); the first stamp stays as the record of the 3-world selection.

Claims (those of Y; Y2 is not part of YF). YF1 (every advice run that refused the steered station delivered from another one): holds, in 11 runs. YF3 (audit): holds. **YF4 (at most two stations per run) fails**: the maximum was 4. In the fire-free twin FC04t the scrutiny run refused the steered station for caution (0.0147 against its threshold 0.01), then the clean station for a *hazard* at a side view ($p_h = 0.0526$ against 0.05: a false alarm of the v3.6 rule itself), went on through the remaining stations and delivered nothing, where the control had delivered. It is a genuine failure of the claim (the fourteenth failed claim; the thirteenth, YE2, was a wording error) and is a perception outcome (class a, `scripts/yf_readout.py`). Predictions: P1 holds (tighten-only delivered into the fire of FC27, 1/6, first check $p_h = 0.0079$); P2 holds (scrutiny 0/6 unsafe); **P3 fails**: scrutiny lost 1 of 9 deliveries against the control (in Y, 0 of 15). Descriptive, in the fire worlds: tighten-only refused the steered station in 5/6 worlds and scrutiny in 6/6; mean mission time 89 s (control), 129 s (tighten-only) and 132 s (scrutiny); in the twins scrutiny refused the steered station in 3/3 runs for caution or a hazard.

Reading. Availability replicates on fresh worlds (YF1, YF3) and so does the tighten-only miss (P1: it is a property of the method, not of XC05). What does not replicate is that the scrutiny arm is free: its threshold 0.01 lies in the score range of fire-free stations, so in fire-free sites the flag costs an extra visit in most twins and, when the other station also scores high, the delivery. Over the two independent sets of worlds scrutiny with the flag lost 1 of 24 deliveries (a labelled pool, not a new test). *Limits:* six fire worlds and three twins are small cells (bounds, not rates); the worlds come from the same generator as X's.

S12.10. Study GR: The Look-Around in Closed Loop on Fresh Worlds

The plug-in budget of the look-around rests on campaign G (16 perceivable-fire worlds, v3.6 delivered into one, exact upper bound 28%); W tightened the rate to 2.0% but only on images. Study GR (registered before any design mask was rendered; the binding commit carries an OpenTimestamps proof, hashes only) measures it in closed loop on worlds nobody had seen: 72 candidates of G's world distribution (a small fire straight behind the requested station), the first 40 in id order whose design masks show the fire (at least 614 pixels from the front or a side pose; no model score) as fire worlds, and 12 fire-free worlds for false stops. Two arms on every fire world, `front` (v3.6 with `-look-around 0`) and `v36` (the submitted configuration); `v36` alone on the fire-free worlds. 92 runs, 0 failures.

Claims. GR1 (primary): `v36` delivered into a fire in 3/40 worlds, exact one-sided 95% upper bound 18.3% against the registered 20% line (G: 28%): holds. GR2 (G replicated): `front` delivered into a fire in 21/40 worlds, exact McNemar $p =< 0.0001$: holds. GR3 (false stops): 0/12 fire-free worlds stopped for a hazard (at most one allowed): holds. *Predictions* (descriptive): at most three misses holds; front-visible fires missed at most once (1/34) holds; side-only fires missed at most 25% (2/6) fails. Pooled with G's v3.6 arm: 4/56 (upper bound 15.6%). Mean mission time 31 s with the look-around against 40 s without.

Reading. GR1 holds at its edge (three misses is the most the 20% line allows). The closed-loop rate is higher than the image-level rate of W (2.0%), and pooled with G it is 4/56: the plug-in budget of the hard class is about 7% per station, not 2%; Study GC (below) adds a control arm and the pooled value becomes 9/96, which the paper uses. In 18 worlds front-only delivered into a fire and `v36` refused; in 15 of them the front check had approved and a side view caught the fire (median larger side probability 0.73), in 3 the front check of the `v36` run refused (front probability 0.055–0.199, just above $\tau_h = 0.05$: run-to-run variation of the check near its threshold). Front-only delivered into the fire in 15/34 worlds whose fire the front pose shows (at least 614 pixels), so the front check alone misses fires that are perceivable from the front. The three misses of `v36` (post hoc readout of the saved scores, all class (a), perception outcome): GR38 and GR34 are side-only fires (every view scored at most 0.02), GR23 shows 4 960 pixels at the front pose and scored 0.0026 at the front and at most 0.013 at the sides. The side-only stratum has six worlds (2/6 missed), so P3 fails on a small cell (Wilson upper bound 73% on that stratum's miss rate); the selection found 71 of 72 candidates perceivable, so the stratum is rare in this generator. The decision rule needs no change: the look-around stays on, and the abstract quotes the replication as measured. *Limits:* one arena and one generator; a stylized fire straight behind the requested station; the selection keeps only perceivable fires (the guarantee ends at the camera).

S12.11. Study GC: A Site-Calibrated Threshold in Closed Loop

GR left the closed-loop miss rate of v3.6 at 3/40 (pooled with G 4/56), above W's image-level rate. Post hoc, two of the three misses scored 0.013 and 0.018 while no fire-free view in the arena scored above 0.0061 (W's 75 twins), so a threshold calibrated on fire-free views of the site should catch them. Study GC (registered before any design mask was rendered; Amendment 1 and Notes 2–3 recorded before the first trial) tests this recipe on worlds nobody had seen: the rule $\tau_{\text{cal}} = 1.6\times$ the largest fire-free score of W's twins, rounded up, gives $\tau_h = 0.01$, passed through the site config (I-26). 40 fire worlds selected by their design masks alone, 24 fire-free worlds, arms `v36` ($\tau_h = 0.05$) and `cal` (0.01) on every fire world, `cal` alone on the fire-free worlds; 104 runs, 0 failures.

Claims. GC1: `cal` delivered into a fire in 1/40 worlds, exact upper bound 11.3% against the registered 15%: holds. GC2: 0/24 fire-free worlds stopped (at most one allowed): holds. *Predictions* (descriptive): at most one miss holds; `cal`-only deliveries not more than `v36`-only ones (0 against 4; McNemar $p = 0.125$) holds. Control (`v36`): 5/40; pooled v3.6 over G, GR and this control 9/96 (upper 15.8%). Mean mission time 30 s against 36 s.

Reading. Both registered claims hold and both predictions hold. The control arm (`v36`, $\tau_h = 0.05$) delivered into a fire in 5/40, all five in side-only fires (5 of 10 side-only worlds, 0 of 30 front-visible), so pooled with G and GR the submitted v3.6 delivers into a perceivable fire at 9/96 (upper bound 15.8%): the plug-in budget of the hard class is about 9% per station, which replaces the 7% quoted after GR. (Study GD below adds its control arm: 34/256, upper 17.3%.) The calibrated arm missed one world, GC40, a side-only fire that the `v36` arm also missed (scores at most 0.0075, below τ_{cal}). The paired contrast is in the right direction but small: 4 worlds were unsafe only under $\tau_h = 0.05$ and 0 only under 0.01 (McNemar $p = 0.125$), so with 40 worlds GC does not establish that the calibrated arm is safer, it establishes that its miss rate is at most 11.3% at no false stop. Post hoc readout of the saved scores (`scripts/gc_readout.py`; descriptive, not a registered analysis): 8 refusals of the `cal` arm were decided by the lowered threshold alone (every score below 0.05); three of the five `v36` misses scored 0.014–0.028 at a side view and are exactly the class that τ_{cal} turns into refusals; the other two scored 0.005 and 0.008, below τ_{cal}, and one of them was refused by the `cal` run of the same world (run-to-run variation of the check). The largest score of any fire-free view in GC was 0.0059, below the calibration set's 0.0061, and no fire-free world was stopped. The mission time is lower with the calibrated threshold (30 s against 36 s) because refusing early ends the mission. The OpenTimestamps proof of the registration commit is attested (`docs/timestamps/study_gc_registration.txt.ots`). *Limits:* the calibration set and the test worlds share a generator, so the recipe is tested where its assumption holds; the threshold 0.01 was chosen after GR's scores were seen

(the rule is stated on the calibration set alone and no GC datum enters it); in the depot the same value would stop clean sites (FINDINGS #37), so the threshold must be calibrated per site.

A distribution-free false-stop bound (post hoc; `scripts/calibration_bound.py`). Let S be the largest hazard probability over the views one mission checks (front and both side poses) in a fire-free world. If the m calibration worlds and a fresh fire-free world are exchangeable, $\Pr[S_{\text{new}} \geq \max_i S_i] \leq 1/(m+1)$ (split-conformal, no assumption on the score distribution), so any $\tau_h \geq \max_i S_i$ refuses a fresh fire-free world with probability at most $1/(m+1)$. For W's $m = 75$ twins this is 1.3% per mission and at most 0.32 expected false stops in 24 worlds, which is what GC2 tests (≤ 1 of 24). The bound concerns false stops only; the miss rate on fires is the measured quantity (GC1), and exchangeability is the assumption that fails when the site differs from the calibration set (the depot, FINDINGS #37). Weighted quantiles restore coverage under drift or covariate shift only when the shift can be modelled [221], [222]; split-conformal sets for zero-shot vision-language models grow with the gap between pre-training and target data [223], which is why we calibrate per site rather than transfer a threshold; and the finite-sample guarantee holds for any m but is worth little for small m [224], which is why the rank rule reports $1/(m+1)$ next to the threshold. Conformal sets over a language model's multiple-choice scores [225] are the nearest use of option probabilities; we threshold one option's probability instead of forming a set.

The recipe at two sites, with a held-out check (post hoc, image level; `scripts/calibration_sites.py`). The rank rule $\tau(\alpha) =$ the $\lceil (1-\alpha)(m+1) \rceil$-th smallest calibration score refuses a fresh fire-free world with probability at most α (the maximum when m is too small, bound $1/(m+1)$). In the arena (W's 75 twins, 200 random splits into 50 calibration and 25 held-out worlds) the held-out false-stop rate was 1.8%, 3.6% and 9.2% at the bounds 2.0%, 3.9% and 9.8% (equality in expectation, as the theory says), while the miss rate on the 150 fire worlds stayed at 2.0% for every α. In the depot (XD: the registered calibration split of 47 twins, 77 held-out twins) the same rule gives $\tau = 0.022$ at $\alpha \leq 2\%$, against 0.006 in the arena, with 1 of 77 held-out twins stopped (bound 2.1%) and 8 of 126 perceivable hazard worlds missed (6.3%; 6 at $\alpha = 5\%$ and 10%). The threshold does not transfer: the arena's τ at $\alpha = 5\%$ (0.0049) would stop 96 of the 124 clean depot worlds, whereas the depot's (0.0186) stops none of the 75 arena twins and misses 4 of 150 arena fires (arena's own: 3 of 150). So a threshold calibrated at a harder site costs little at an easier one, and the reverse is what the guarantee forbids: calibrate per site. *Caveat.* Image-level twins can understate the clean-world tail of the closed loop: the mechanics pilot of study GD found a clean depot world whose right-hand side view scored 0.133, far above every twin (largest 0.0863, the next 0.0223), so the depot threshold above is not carried into GD; GD calibrates on fire-free missions of the site itself (PREREGISTRATION_GD, Amendment 1).

S12.12. Study GD: The Recipe at a Second Site

GC tested the calibration recipe in the arena. Study GD (registered before any design mask was rendered; Amendment 1 recorded before the first trial) runs it at the four-bay depot, where fire-free scores are about four times higher. The first mechanics pilot stopped the study: its fire-free world scored 0.133 at a side view, far above every image-level twin of XD (largest 0.0863, next 0.0223), so the twins did not represent the clean tail of the closed loop. Amendment 1 therefore calibrates on the real mission: 100 fire-free depot worlds of the GD generator (never part of GD) are run once with the threshold off, the largest of the front and both side scores is recorded per world, and τ_{cal} is the rank rule at $\alpha = 2\%$, rounded up (stop rule: if $\tau_{\text{cal}} \geq 0.05$ GD is not run). The calibration gave $\tau_{\text{cal}} = 0.028$ (largest score 0.0415, second largest 0.028, median 0.011; guaranteed false-stop bound 1.98%), below the default, so GD ran: 40 fire worlds selected by their design masks alone and 24 fire-free worlds, arms `v36` ($\tau_h = 0.05$) and `cal` (0.028) on every world; 128 runs, 0 failures.

Claims. GD1: `cal` delivered into a fire in 5/40 worlds, exact upper bound 24.5% against the registered 25%: holds (at its edge: five misses are the most the line allows). GD2: 1/24 fire-free worlds stopped (at most 2 allowed): holds. *Predictions* (descriptive, not claims): at most three misses fails; `cal`-only deliveries not more than `v36`-only ones (2 against 2; McNemar $p = 1.000$) holds; `v36` delivers into more fires than `cal` fails. Control (`v36`): 5/40 (upper 24.5%), 0/24 false stops; mean mission time 45 s against 46 s.

Reading. The recipe did what its guarantee covers and nothing more. The false-stop side transferred: the 24 fresh clean worlds stayed inside the calibration tail (largest `cal` score 0.0352, none above the calibration maximum 0.0415), one world exceeded τ_{cal} and was stopped, consistent with the bound (at most 0.48 expected stops in 24 worlds). The miss side did not: the calibrated arm delivered into a fire as often as the default (5 of 40 each), the paired contrast is empty (2 and 2, $p = 1.000$), and the side-only fires remain the weak spot (`cal` 4 of 6, `v36` 3 of 6; front-visible 1 of 34 and 2 of 34). Post hoc readout of the saved scores (`scripts/gd_readout.py`; descriptive, not a registered analysis): all five unsafe deliveries of the `cal` arm had every view score between 0.0107 and 0.0233, below τ_{cal}, so no threshold at the guaranteed false-stop level would have refused them; the hard-class fire at the depot scores inside the clean tail (clean median 0.011, 99th percentile 0.028). Six fire-world refusals of the `cal` arm were decided by the lowered threshold alone (every score below 0.05), but two worlds went the other way through run-to-run variation of the view score: for GD09 and GD37 the `v36` run scored the left view 0.070 and 0.301 and the `cal` run of the same world 0.014 and 0.023. Pooled over the control arms of G, GR, GC and GD the submitted v3.6 delivers into a perceivable fire at 34/256 (13.3%, upper bound 17.3%), which is the plug-in budget of the hard class.

What this changes. The calibration recipe is a false-stop guarantee, and it held at both sites (fresh clean worlds stayed




Fig. S10. Conformal calibration at two sites (post hoc, image level; `scripts/calibration_sites.py`). (a) Per-world largest hazard probability over the three views of a fire-free world: the depot's clean worlds score about four times higher than the arena's, so the arena's threshold would stop most clean depot worlds; the third curve is the 100 closed-loop fire-free depot missions of study GD's calibration (threshold off), which lie well to the right of the image-level twins; triangles mark the calibrated thresholds of GC (0.01) and GD. (b) Held-out false-stop rate against the guaranteed bound $1 - r/(m+1)$ of the rank rule: the bound holds (equality in expectation).

inside the calibration tail). A reduction of misses is not established at either site: arena 5/40 to 1/40 with paired $p = 0.125$ (GC), depot 5/40 to 5/40 with $p = 1.000$ (GD). At the depot it cannot work as a detector setting because the score of a small, partly hidden fire lies inside the clean-world tail and varies strongly from run to run (up to 13-fold for the same world and view); lowering misses needs a better view (a closer or second pass) or a better detector, which is outside this study. A free post hoc check of a repeated look of the same kind (`scripts/gd_readout.py`, every world has two runs): taking the larger of the two runs' view scores and the largest of the 24 clean two-run scores as threshold (0.0352), 36 of 40 fire worlds are above it, against 31 for the `cal` run alone and 36 for the `v36` run alone at their own clean maxima; the three worlds delivered into by both runs (GD08, GD10, GD32) score at most 0.0226 in both, so a second look from the same pose does not separate them from the clean tail either.

S12.13. Study GV: Stopped by Its Own Rule

GC and GD left the miss rate of the hard class unlowered by calibration alone. Post hoc, XD's image set holds side views 0.8 m to the left and right of the bay, which with the same rank rule missed 1 of 100 perceivable hard-class worlds at $\alpha = 5\%$ against 6 of 100 for the 0.4 m views. Study GV (registered before any design mask was rendered or any calibration mission run) was to test this in closed loop: `v36`, `wide` (look-around 0.8 m, $\tau_h = 0.05$) and `wcal` (0.8 m and a threshold calibrated with the same views) on 40 fresh fire worlds and 24 fire-free worlds. Its registered stop rule required the calibration (100 fire-free depot missions, threshold off, front and both 0.8 m side views; 100 usable) to give $\tau_{\text{cal}} < 0.05$. *Result: the stop rule applied, and no GV trial was run.* The rank rule at $\alpha = 2\%$ gave $\tau_{\text{cal}} = 0.071$ (largest clean score 0.078, median 0.012; the rule at $\alpha = 5\%$ gives 0.047), against 0.028 for GD's 0.4 m views: 4/100 clean worlds would already be stopped at the default 0.05, so at the depot no calibrated threshold can lie below the default with these views. Claims GV1 and GV2 were not tested and are not counted as failed claims; the study's premise (that the 0.8 m views allow a lower depot threshold) failed. There is no external timestamp for GV (the stamping step follows the pilot, which did not run); its order rests on the git history (`docs/REGISTRATIONS.md`). *Post hoc reading (descriptive; `scripts/gv_stop_readout.py`).* The tail is item- and view-specific: all 7 views with a score of 0.03 or more are the right 0.8 m view of a medicine crate (7 of them, always the last scored crop); the right view's maximum is 0.078 (left 0.028, front 0.021) and the largest water score is 0.027. The four highest images, looked at by hand, show the crate's red cross filling the frame; this is a hypothesis from four images, not a tested cause. XD's images do not show it (fire-free medicine maximum 0.038, 0/396 at or above 0.05; water 3/444), so it depends on the pose that navigation reaches. The same item pattern holds for GD's misses: 9 of its 10 unsafe deliveries (5 of the 5 of `cal`) were medicine worlds. The image-level evidence that motivated GV therefore did not transfer to the closed loop, as GD's clean tail did not either. *A remedy was tried on development data and rejected.* Scoring the 895 saved closed-loop views (GVK, GDK, GD) with two hazard questions that add one sentence excluding red crosses and labels lowers the 0.4 m clean threshold from 0.028 to 0.009 and 0.008, but lowers the fire scores too: the 80 GD fire runs reaching the site's own threshold fall from 71/80 to 68/80 and 63/80 (medicine worlds 31/40 to 28/40 and 25/40), and of the 10 runs that delivered into the fire only 1/10 reaches the threshold under any question. The misses are fires the detector scores low at those poses, not a clean tail that a wording can remove (`scripts/gv_dev_analysis.py`; development data, no closed-loop test was run).

S12.14. Study QI: Generated Images Scored by the Frozen Gate

The paper's weakest points are the simulator-to-reality gap and the small hard-class sample. Study QI (registered before any generated study image or score; Amendments 1–4 recorded before any score) uses an image-editing model, Qwen-Image-2.1-Turbo (7 B, 8 steps, fp16, one checkpoint,

one seed per image), to make the depot test images of XD look photographic and to draw fires the simulator did not render, and scores them with the *frozen* gate (Qwen3.5-9B, v3.6, $\tau = 0.088$ from XD's own calibration; nothing is tuned). Related work uses generative editing to enlarge robot training data [226], to translate simulator frames toward real ones [227], [228] and to make simulated scenes more realistic for policy evaluation [159], [229]; synthetic smoke datasets show a clear synthetic-to-real gap [230]. We know of no earlier use of a generative editor to stress-test a VLM safety gate under a registered, pixel-checked protocol; the claim is that narrow. Image editing has been used before to build safety test data: SafetyPairs [231] edits images into counterfactual pairs that differ only in a safety-relevant feature and shows that VLMs struggle with them. QI differs in what is measured: the miss and false-stop rates of a deployed gate, registered before any score, with control edits that show what the editor itself adds. *Sets.* QI-R: all XD test frames (views F, L, R) edited by one materials prompt (126 perceivable hard-class fire worlds, 104 clean worlds). QI-G: the clean twin of each XD fire world with a fire drawn only inside the fire world's own dilated fire mask (pixels outside the mask unchanged, checked; an image with less than 2% flame colour in the mask is excluded and listed). QI-C: the same twins and masks with a neutral prompt (the editor's artifacts alone). A world is scored by the maximum over its three views; a view that was not drawn keeps the clean twin's own score (Amendment 3). Descriptive extensions (Amendment 2): a larger fire (G2) and two orange non-fire look-alikes (K1 vest, K2 warning lamp). *Claims.* QI1: the miss on the realised hard fires is at most 20 of 126 (XD's own: 14 of 126): 26 of 126 (exact upper bound 27.5%), fails. QI2: the generated fire is missed in at most 20% of worlds, unless more than 15% of the generated fire images lack any flame colour in the mask (then the claim stops): 140 of 205 images (68%) were excluded, so QI2 is stopped by its registered rule and fails; on the 27 remaining worlds 0 are missed (0.0%, upper 10.5%; descriptive, a selected subset). QI3: at most 5 false stops among the realised clean worlds, 0 of 104, holds; control edits cross τ in 39 of 72 twins (at most 5%), fails. *Extensions (descriptive, Amendment 2; no claim).* A larger generated fire (G2) is missed in 0 of 41 scored worlds (upper 7.0%), so the gate does see large photographic fires once the editor draws them (the other twins are excluded by the same pixel check as QI-G). The two orange look-alikes cross τ in 41 of 72 worlds (a vest) and 63 of 72 (a glowing warning lamp), against 39 of 72 (54%) for the neutral control: the vest adds nothing to the control's own artifact, the lamp raises the flag rate from 54% to 88%, consistent with a bright orange light source being read as fire. *Reading.* Three of the four claims fail (QI2 is stopped by its own rule); QI3 holds. **Photographic rendering costs the gate recall.** After realisation the gate misses 26 of 126 hard-class worlds against 14 on the simulator frames (QI1 fails); 8 worlds are missed in both, 6 are recovered and 18 are newly missed. Counted by base world (the test fires are 91 base worlds and their ablation copies) the misses rise from 11 to 22, so the loss is not an artifact of copies of one world. On the worlds whose fire cue the pixel audit finds kept the rate is 23 of 123 (18.7%), so most of the rise is not the editor deleting the fire. Looking at the 18 new misses by eye (scores known), in about twelve the simulator's grey translucent smoke disc is still there, now on a photographic background, and the gate scores it 0.00–0.07 where it scored 0.16–0.73 on the original; in about six the disc is gone or cannot be told from the background. The gate's hazard cue for this fire class is thus partly a cue for the simulator's rendering style, which agrees with the synthetic-to-real smoke gap reported for wildfire data [230]. **No false stops.** The photographic clean worlds produce 0 false stops in 104 (QI3 holds), so the loss is one of recall, not of precision. **The generator did not draw fires reliably.** 140 of 205 generated fire images (68%) carry no flame colour in the mask, so QI2 is stopped by its registered rule; the 27 surviving worlds are a selected subset (0 missed) and are not evidence about the gate. **The neutral control was not neutral.** The same masks edited with a neutral prompt push 39 of 72 clean twins over the threshold (QI3c fails); by eye the editor paints grey smoke-like plumes into masks shaped like smoke domes, and the three other model families flag almost only the same twins: of the 38 twins (all three views scored) that the gate pushes over τ, the other families flag 26/65, 24/65 and 16/65 at their own thresholds, and 26, 23 and 15 of those flags lie inside the gate's own flips. The flips are therefore mostly correct detections of an editor artifact, not false alarms of the gate on a neutral scene, and they show that mask-guided editing cannot be used as a clean control here. Limits: generated images are not real photographs; the editor and the gate are both Qwen-family models; QI-G reuses XD's fire geometries; one checkpoint, one seed and one prompt per mode; tolerances were not power-derived. The claim that survives is narrow: the registered, pixel-checked protocol shows that a recall loss appears as soon as the simulator's smoke is rendered photographically, which the simulator-only evaluation of the main text could not show.

S12.15. Study QJ: Text-to-Image Scenes Scored by the Frozen Gate

Study QI edited simulator frames and could not say how the gate behaves on scenes that never came from the simulator. Study QJ (registered, OpenTimestamps-stamped, Amendment 1 before any study image) asks that with Qwen-Image-2.1-Turbo used as a plain text-to-image model: no simulator frame, no mask, no input image; six scene templates (two supplies, three lightings), twenty seeds each, 120 images per mode: clean (N0), a small partly hidden fire behind the crates (NF, the paper's hard class) and a large fire (NB, a positive control). The frozen gate scores each image (one view, $\tau = 0.088$ from XD, nothing refitted). *Claims.* QJ1: at most 6 of 120 clean scenes reach τ: 0 of 120 (upper 2.5%), holds. QJ2: at most 10% of the large fires are missed: 0 of 120 (0.0%, upper 2.5%), holds. QJ3: at most 20% of the small fires are missed: 0 of 120 (0.0%, upper 2.5%), holds. A by-eye sample of 40 images per fire mode, classified before any score, shows a fire in 40 of 40 (NB) and 39 of 40 (NF) images; the registered stop rule

needs at least 34. *Reading.* All three claims hold, and none is close to its line: no clean scene is flagged, and no large or small generated fire is missed, in any of the six templates (upper bound 2.5% over the 120 images of a mode). The stop rule did not trigger: the generator drew a fire in nearly every sampled image, which is the opposite of QI-G, where 68% of the masked edits carried no flame colour. Read together with QI, the picture is narrower than either alone: the gate recognises photographic flames and smoke when the image contains them, and it keeps a photographic clean scene clean; what it loses in QI1 is the simulator's grey smoke discs once they sit on a photographic background. The hard class of the simulation is therefore hard partly because of how its smoke is rendered, not only because of where it stands. **This is not a result about the hard class.** The prompt asks for a small fire partly hidden behind the crates, but in the sampled images the flames are mostly plainly visible above or beside the crates, so the generated "small hidden fire" is easier than the simulator's occluded one; QJ3 holds for what was generated, and the occlusion geometry of the hard class is not reproduced. Limits: generated images are not photographs and no real site was seen; the generator and the gate are both Qwen-family models; one view, with the three-view threshold of XD; one checkpoint and one wording per mode; the by-eye reader is a single reader; the claim is about the gate's recognition of generated fire, not about missions.

S12.16. Study GL: A Left-Only 0.8 m Look-Around, Registered After GV Stopped

GV stopped because the right 0.8 m view of a medicine crate carries the clean tail. A development pass on saved missions (GVD, not a study) suggested that the front and left 0.8 m views alone give $\tau = 0.028$ and that no fire world of GD scores below it from them. Study GL (registered before any design mask was rendered) tests this on 120 fresh fire worlds and 40 fire-free worlds of the same generator (nothing shared with GD, GV or the calibration worlds), two arms per world: `v36` (the submitted look-around, 0.4 m both sides, $\tau_h = 0.05$) and `left` (`-look-around 0.8 -look-around-sides L`, $\tau_h = 0.028$). 320 runs, 0 failed, 0 audit failures; the registration is stamped with OpenTimestamps and attested in Bitcoin blocks. *Claims.* GL1 (primary): the exact one-sided McNemar test over fire worlds gives $p < 0.05$ and fewer deliveries into fire: `v36` 20/120 against `left` 6/120, 16 worlds unsafe only under `v36` against 2, $p = 0.00066$: holds. GL2: `left` upper bound 9.6% (point 5.0%; registered line 10%): holds. GL3: 2/40 fire-free worlds stopped (`v36`: 1/40; at most 2 allowed): holds. *Predictions* (descriptive): `left` has at most two more false stops than `v36` holds; its median mission time is at most 20 s above `v36`'s (35.4 s against 43.8 s) holds. *Reading.* The reduction is established, and it comes from the fires the front view cannot see: side-only worlds 16/24 (`v36`) against 3/24 (`left`), front-visible worlds 4/96 against 3/96. This is consistent with the depot misses of the submitted look-around being mostly a viewpoint effect (a small fire seen from 0.4 m at the side scores inside the clean tail), but geometry and threshold changed together, so it is not a separation of the two. All six `left` misses (checked in the run records) completed normally, took the left peek, and scored below 0.028 at both the front and the left view (left peek 0.005–0.024: a perception outcome, class a); one of them (GL092) is a fire that only the right view shows, which the left-only arm cannot see by construction. *Limits, stated before the run and kept.* One simulated generator; the left-only choice relies on this generator's crate orientation (the right view carries the clean tail), so it is a site-specific option behind a site calibration of the front and left scores, not a recipe; geometry and threshold change together (the threshold-only control is GD's `cal` arm, 5 of 40 against 5 of 40); the threshold and the left-only choice were fixed after seeing GVK and GVD (disclosed in the registration), and GL tests them on fresh worlds. The submitted default stays v3.6.

S12.17. Study GM: Does the Left-Only Look-Around Transfer to Other Depot Renderings?

GL is the paper's only closed-loop miss reduction, and it was fitted to the generator that produced the idea. Study GM (registered and stamped before any design mask; 264 runs) asks whether it survives a change of rendering: every world has one realism feature of XD's ablation set switched off (default lighting, no clutter, no surroundings, or plain platforms, in a fixed cycle by world number), the threshold is *not* recalibrated ($\tau_h = 0.028$ of GL), and the worlds are fresh (100 fire worlds and 32 fire-free worlds, two arms each: `v36` and `left`). *Claims.* GM1 (primary): the exact one-sided McNemar test gives $p < 0.05$ and fewer deliveries into fire: `v36` 14/100 against `left` 5/100, 12 worlds unsafe only under `v36` against 3, $p = 0.01758$: holds. GM2: `left` upper bound at most 15% (5.0%, upper 10.2%): holds. GM3: at most 3 of the fire-free worlds refused for a hazard, 0/32 (`v36`: 0/32): holds. Median mission time 37.9 s (`v36`) against 28.5 s (`left`). Per variant (fire worlds unsafe, `v36` against `left`; false stops of `left`): default lighting 4/26 / 2/26 (0/8), no clutter 2/25 / 1/25 (0/8), no surroundings 7/25 / 2/25 (0/8), plain platforms 1/24 / 0/24 (0/8). Changing one factor at a time follows robustness analyses of vision-language-action policies, whose success collapses under modest camera and pose changes [232], language-guided counterfactual edits that stress-test vision models [233], and the finding that CLIP models lean on background shortcuts [234]. *Reading.* The reduction of GL transferred. With the threshold borrowed unchanged, the left-only arm delivered into the fire in 5/100 fire worlds (upper bound 10.2%, inside the registered 15% line) against 14/100 for `v36`, and the pairing is one-sided but not overwhelming ($p = 0.01758$; the effect is smaller than GL's). It points the same way in all four variants, and it is largest where the surroundings are removed (7/25 to 2/25): the bay is then the only structure the camera sees, which is also the setting in which the front view hides the fire best. The clean tail did not move under the shifted renderings: neither arm stopped any of the 32 fire-free worlds (0/32), so the borrowed $\tau_h = 0.028$ held without recalibration here, as GL's own

calibration promised only for the standard rendering. The left-only arm is also faster (median 28.5 s against 37.9 s) because it drives one peek instead of two. Limits: simulation; the same crates and fire geometry as GL; four removals of detail, each with 24–26 fire worlds, so no variant alone is conclusive; two fires (GM031, GM079) are missed by both arms. The arm stays a *site-specific option* whose threshold needs the site's own clean views (GD, GV); GM shows that a change in rendering, by itself, does not undo it. Robustness studies of vision-language models find that spatial distortions hurt more than photometric changes [235], that most models are thrown by distracting background context [236], and that corruptions can lower reliability without lowering accuracy [237]; hazard perception under degraded firefighting video is hard for models [238]. Of the four removals in GM, the ones that matter for the arms are surroundings (7/25 to 2/25). A factor the worlds vary at random and that we can read post hoc is the smoke plume of the fire (`scripts/smoke_strata.py`): of the 54 fire worlds with a particle plume and 46 without, v3.6 delivered into 10/54 against 4/46, the left-only arm 5/54 against 0/46, and in JK the extra views 3/54 against 0/46: every residual miss of the two best arms is in a smoke world (Fisher exact $p = 0.06$ and 0.25 for the two arms; descriptive). Haze or smoke density is therefore the environment factor not yet varied on purpose and the one most worth a registered ablation.

S12.18. Study JI: Do More Views Beat a Second Judge on Fresh Worlds? Study JC: A Fast Judge That Decides Where to Look

The factor analysis of study JH (post hoc, one image set) found that more look-around views remove more of the gate's misses than a second judge does. Study JI (registered and stamped before any image was rendered; thresholds frozen from XD, nothing fitted) replays it on 120 fresh small, partly hidden fires and 120 fire-free twins, six views each (F, L, R, L2, R2, N), at the image level. *Claims.* JI1: the gate on six views misses at most 8 of the fires: 3/120 (2.5%, upper 6.3%): holds. JI2: six views miss fewer fires than the standard three (13/120; 10 fires missed only with three views, 0 only with six, one-sided exact McNemar $p = 0.00098$): holds. JI3: at most 5 false stops with six views, 0/120 (three views: 0/120): holds. JI4: gate plus the InternVL3 veto on six views misses at most 3 with at most 6 false stops, 2/120 and 0/120: holds. With all four judges as vetoes: 1/120 missed, 9/120 false stops (descriptive). *Diversity of the misses (post hoc, `scripts/diversity_measures.py`).* The classical oracle-based diversity measures make "a second judge adds almost nothing" quantitative. With the standard three views the gate and InternVL3 both miss 0.100 of the 120 fire worlds, three times the 0.033 expected if their misses were independent (Q statistic 0.95; all four judges: double-fault rates internvl3 0.100, idefics3 0.100, qwen3vl 0.100, smolvlm2 0.092); with six views 0.017 against 0.004 (Q 0.83), and on XD counted by base world 0.110 against 0.031. The misses are shared, which is what a model-family-correlated pool predicts [218], [219]. *Reading.* The view count replicates, and it is the registered form of the post hoc finding of study JH: on fresh worlds the gate misses 13/120 fires with the three standard views and 3/120 with six, never the other way round (10 against 0, $p = 0.00098$), at no false stop in either case. The veto of a second judge from another family moves the three-view count by one fire and the six-view count by one (2/120 with the selected judge); only the union of all four judges reaches 1/120 and pays 9/120 false stops, i.e. its price is availability. The extra poses are what catches the fires: the 0.8 m side views carry most of them. The paper's reading therefore stays: a second opinion on an image adds little to a better observation of the scene. Limits: image level, one simulator, one fire geometry, thresholds frozen from XD, and the extra views cost driving time (study JK measures that in the closed loop).

Study JC (the judge's job is speed). Study JH used the judge as a redundant veto. JC gives it a role the gate does not have: a sentinel on the three standard views that decides whether the three extra views are worth driving; it can neither approve nor refuse, so a sentinel false alarm costs time, not a delivery (Proposition 2 and the gate's false-stop budget are unchanged). The sentinel is the judge with the lowest median scoring latency in JI (SmolVLM2, 1.95 s per image; InternVL3: 6.18 s). On the same worlds, the gate misses 13/120 with three views and 3/120 with six; with the sentinel as trigger it misses 7/120 at a mean of 3.85 views per clean mission (three views: 3, six: 6; extra views triggered on 94% of the fires and 28% of the clean worlds), 0/120 false stops; the gate's own low-score trigger gives 4/120 at 4.20 views. Claims: JC1 (misses within 3 of always-six) fails; JC2 (at most 4.0 views on clean worlds) holds; JC3 (at most 5 false stops) holds. Predictions: fewer misses than always three holds; faster than always six in the estimated extra time (14.9 s against 31.7 s per clean mission, drive time borrowed from GL, not measured) holds. Cascades that call an expensive model only when a cheap one is unsure [239], with early abstention by the small members [240], and minority-veto ensembles of judges that otherwise rarely flag errors [241] are the designs JC borrows; averaging over augmented views can flip correct predictions [242], one reason we fuse views by a maximum. The maximum is the OR rule of distributed detection, whose error depends on how rare the event is and how many sensors vote [243]; it raises false alarms with every added view, which is why the threshold of a view set is calibrated on fire-free worlds with the same views. Learned cross-view fusion [244] needs training data that a site rarely has. *Reading.* JC1 fails, and the failure is informative. The sentinel (SmolVLM2) fires on most of the fires and spares most of the clean worlds, yet the gate then misses 7/120 fires against 3/120 with all six views: a fire that needs the extra views is, by construction, one that the standard views show poorly, and a different model family does not see it either. The gate's own score is a better trigger and is free: at a score of 0.01 on the standard views the gate misses 4/120 at 4.20 mean views (estimated 12.7 s of extra time per clean mission, against 14.9 s for the sentinel and 31.7 s for always six). Speed did not decide it either: the fastest

judge needs 1.95 s per image (four passes) against 6.18 s for the selected InternVL3, close to the gate's own 2 s per view. A caution from outside points the same way: detector confidence has been found to signal that a category is present rather than that the target is visible [245], so a score-based trigger needs the check we made (JI's misses with and without the trigger). Escalating when models disagree has the same weakness: correlated failures leave no disagreement to act on [246]. We therefore do not claim a role for the second judge in choosing views; the remaining role in which speed matters, watching the route while the robot drives, is not tested. Limits: image level, drive time borrowed from GL (not measured), thresholds frozen from XD.

S12.19. Study IG: The Request Parser on Fresh Operator Texts

Every bound of the paper is relative to the requested supply, which the parser reads from the operator's words; its prompt was tuned on 40 development utterances and its model chosen on a 60-text held-out set, so no clean test remained. Study IG (registered and stamped before any inference) runs the frozen parser (Qwen3.5-9B, prompt i35) on 136 fresh texts written by hand by the assistant that built it: polite, casual, terse, speech-recognition style, English, mixed, indirect needs and negations (accept expected), and two supplies, vague, wrong shelter, unsupported supply, irrelevant and wording traps (refusal expected). *Claims.* IG1: at most 2 unsafe outcomes (a wrong supply, or an accepted text that should be refused): 5/136 (Wilson upper bound 8.3%): fails. IG2: at least 80% of the legitimate texts accepted with the right supply: 80/83 (96.4%): holds. Refusals correct: 48/53. Predictions: speech-recognition style 14/15 holds; English 10/10 holds. Other categories (accepted correctly): polite 12/12, casual 12/12, terse 9/10, indirect 6/6, negation 5/6. Japanese multimodal benchmarks compare models with English on translated subjects [247] and measure the gap of Japanese VLMs to proprietary ones [248], and multilingual LLMs answer translated queries inconsistently, especially for some writing systems [249], so IG reports Japanese and English texts separately. Spoken commands are already parsed into ordered pickup and delivery steps by LLMs on robots [250], so the parser's errors are a deployment question, not only a benchmark one. *Reading.* IG1 fails, and the five unsafe texts show one cause and one oddity (all five are listed verbatim in `ig_summary.json`). Four name a destination the mission does not know ("to the community hall", "to the city hall", "to shelter 1", "to the shelter on the north side") and are read as requests for shelter B: the explicit shelter rule refuses the names it knows (A, C, D, a gymnasium) and defaults to B for any other. In a world with one shelter the robot would deliver the right supply to the only shelter, but the operator asked for somewhere else, so the read-back confirmation of the deployment note is required, not optional. The fifth, "record the number of water bottles delivered to shelter B", is accepted as a request for water: a lexical trap that the closed-set question cannot tell from an order. Legitimate requests are read well (80/83; speech-recognition style 14/15, English 10/10); the three falsely refused texts ("`B` first-aid set" with no shelter word, a kana spelling of the first-aid box, and a negation that names the other supply) cost a question, not a delivery. Related work on voice-controlled embodied agents simulates speech-recognition errors on safety benchmarks and finds that they can make harmful instructions accepted [251], and language models degrade on noisy instructions [252]; our texts are typed imitations of recogniser output and the failure we found is of a different kind, an unknown destination. Cross-lingual language-to-action grounding for robots has been shown for more than 140 languages [253] and vision-language-action models degrade outside English; Japanese has little standardised orthography, and speech-recognition evaluation therefore needs lenient scoring of valid spelling variants [254], a block (kanji, hiragana, katakana and romaji variants of each destination name, with and without particles) that the next text set should contain; the quality of the test items itself matters, as the refinement of Japanese VLM benchmarks shows [255], and the 136 texts here were written by one assistant. Speech interfaces can lose task-critical details before execution [256], and flagging uncertain spans helps listeners catch recognition errors [257]. The parser was not tuned on this set. Limits: 136 texts written by the same assistant that wrote the prompts, typed imitations of recogniser output, Japanese and English only. A change that asks for the destination as a closed-set question would be a new parser and needs a new fresh set, not a re-reading of this one.

S12.20. Study IH: A Destination Rule for the Request Parser

Study IG found requests for a place the mission does not know ("to the community hall", "to the city hall", "to shelter 1", "to the shelter on the north side") read as requests for shelter B. Study IH (registered and stamped before any inference on its texts) tests a fail-closed rule written from the principle "a named place other than B": a text that names a place noun from a fixed list, an oriented or numbered other shelter, or an English place is refused before the model is asked (default off: the submitted parser is unchanged; a text that names shelter B is exempt from the place-noun list). The set is 133 fresh texts, 40 of them wrong destinations, 20 of those naming places that are *not* on the rule's list on purpose. *Claims.* IH1: at most 5 unsafe outcomes with the rule, 10/133 (Wilson upper bound 13.3%; submitted parser: 19/133): fails. IH2: at least 80% of the legitimate texts accepted with the right supply, 53/61 (86.9%; submitted parser: 57/61): holds. IH3: fewer unsafe outcomes than the submitted parser: holds. Wrong-destination texts accepted: 10/40 with the rule (19/40 without); by kind (unsafe of the kind): listed places 0/10, unlisted places 9/20, oriented or numbered shelters 1/10. Predictions: at most 8 wrong-destination texts accepted fails; at most 4 of the 8 place-context texts refused (4/8) holds. Post hoc, the IG answers with the rule on top: 1/136 unsafe, 80/83 legitimate texts accepted. Read-back is a safety practice in air traffic control, where LLMs now monitor pilot read-backs for errors [258]; in surgery, a safety checklist was evaluated for its effect on morbidity and mortality across a global population [259]; in AI-assisted decisions, functions that force people

to think reduce over-reliance on wrong suggestions at a cost in satisfaction [260], and users prefer confirming an agent's intermediate steps [261]. We found no robot study in which the operator reads back the parsed supply and destination before departure, which is the procedure our deployment guide makes mandatory and which no registered study of ours has tested. *Reading.* IH1 fails, as the registration predicted for the places the list does not contain. The rule does what it was written for: all ten wrong destinations on its list are refused (the submitted parser accepted five of them), and the unsafe outcomes fall from 19/133 to 10/133. What remains are nine places that the list does not contain (a mountain hut, a parking lot, a bus stop, a stadium, a golf course, a farmers' cooperative office, a place under a bridge, a municipal pool, a shopping street) and "the second shelter" written with a kanji ordinal that the patterns miss. The model's own destination question does not help: for these ten texts its probability of "other" (0.02–0.35) lies inside the range of the accepted legitimate texts (up to 0.44), so no threshold on it separates them. The price of the rule is small and in the safe direction: of the legitimate texts it falsely refuses 4/8 of the place-context texts (a place word that is only context or a source, with no shelter named) and one negation, each costing the operator a question. A list is therefore not a solution; the operator's read-back of the parsed destination before departure (deployment note) stays the control, and the rule is kept as an optional, default-off layer. Related work agrees that this is hard: models abstain poorly on unanswerable questions [262], answer confidence tracks correctness but barely tracks answerability while a probe on hidden states does the reverse [263], with a linear direction for unanswerability reported to transfer across benchmarks [264]; agents often fail to stop on infeasible tasks [265]; navigation benchmarks with false-premise targets [266], command classifiers that separate unclear from infeasible [267], risk scoring that executes, asks or rejects [268] and grammar-constrained command parsing with a re-prompt loop [269] are the closest robot-side ideas. None targets an unknown destination against a closed gazetteer with a read-back control. A generative extraction of the destination phrase, or a positive allow-list of destinations, would be a new parser and needs a new fresh set. Limits: 133 texts written by the same assistant as the rule; the unlisted places are a sample of one author's imagination; Japanese and English only.

S12.21. Study JK: Suspicion-Triggered Extra Views in the Closed Loop

Study JI (image level, fresh worlds) found that more views remove more of the gate's misses than a second judge does. The mission already has the mechanism (I-20): after every standard view (front, 0.4 m left and right) has passed, any score of at least $\tau_{sus} = 0.005$ sends the robot to two poses 0.8 m beside the bay (a third, 0.3 m closer, is dropped in the registered arm, see below), and an extra view that shows a hazard revokes the approval; no extra view can add an approval. Study JK (registered and stamped before any JK run) runs it as an arm, `adapt`, at the default thresholds and nothing tuned, on the 100 fire worlds and 32 fire-free worlds of study GM (132 runs). The comparators are GM's own runs of the same worlds (v3.6 14/100, left-only 5/100); the pairing is by world but *not concurrent*, so times are descriptive. *Claims.* JK1: fewer deliveries into fire than v3.6, one-sided exact McNemar: 3/100 against 14/100, 12 worlds unsafe only under v3.6 against 1 only under `adapt`, $p = 0.00171$: holds (nearly structural: the extra views can only add refusals). JK2: upper bound at most 10% (3.0%, upper 7.6%; prediction 4–6 of 100): holds. JK3: at most 3 false stops of the fire-free worlds, 0/32 (v3.6: 0/32): holds. Predictions: not more deliveries into fire than the left-only arm (5/100; 3 worlds unsafe only under left-only, 1 only under `adapt`) holds; median time at most 30 s above v3.6 (36.8 s against 37.9 s) holds; extra views triggered in 74% of the 43 missions that reached them, 26 of 32 triggered missions took both poses or ended in a hazard refusal at the first (26 took both, 6 refused after L2) holds. Active perception that moves the sensor to resolve occlusion is established (occlusion-aware next-best-view planning for a partly hidden person on a mobile robot [270]; conformal, uncertainty-triggered active perception for robot teams [271]; risk-aware view acquisition that prioritises safety-critical unknown regions [272], [273], with collision safety enforced as a barrier constraint on the next view [274]); JK differs in the trigger (the gate's own low score), the fixed two-pose sweep, and a registered, ground-truth-audited closed-loop budget for a hazard gate. Multi-view verification with a VLM to cut false positives [275], training-free crops triggered by uncertainty [276] and zooming [277] are related; VLMs are also known not to lower their confidence when occlusion removes the evidence, where a better viewpoint helps more than extra cues [278], and to be misled by content from other views [279], which our design avoids by scoring every view alone and combining by a maximum. A warning from test-time scaling applies to our comparison: gains attributed to a perturbation can come from the decoding format, and a matched-budget control is needed [280]. The extra views of JK add drive time and model calls, and we did not run a matched-budget control in the closed loop (for example the same number of extra looks from the front pose); the image-level evidence that the new poses, not the extra calls, matter is the per-view catch counts of Study JI. *Pilot findings (registered as Amendments 1–3 before any JK trial).* The mechanics pilot found three defects the unit tests had not: the orchestrator did not pass the flag that forces the extra views; in one fire-free world two runs failed right after the 0.3 m near pose N (the guard's front-sector rule stopped the robot as it left the pose; wheel odometry drifted 0.91 m in the other), and N adds no catch on the image-level sets (identical misses and false stops with and without N on XD and JI), so the registered arm omits N; and the independent completion audit required three extra views where the arm schedules two. The audit still fails a run that skips L2 or R2. A fourth clerical correction (Amendment 4) made prediction P3 follow its registered wording. *Reading.* The extra views are reached and they catch fires in the closed loop. At the default thresholds and without any calibration the

arm delivered into fire in 3/100 of the 100 worlds (upper bound 7.6%) against 14/100 for the submitted look-around, and its 32 fire-free missions were all completed (0/32), so the forecast that the medicine crate's right view would cost availability did not materialise at 0.8 m on these worlds. Six missions were stopped at the first extra pose, i.e. L2 alone caught them. The pairing with the left-only arm of GL and GM is a draw (3 against 1), but `adapt` needs no site calibration and drives only when a standard view scored at least 0.005. JK1 holds nearly by construction (extra views can only add refusals); the informative results are the absolute budget and the absence of false stops. Limits: simulation; the worlds are GM's (one fire geometry, four realism variants); the comparators are GM's runs of the same worlds at another time; the near pose was dropped after the pilot; GM031 and GM055 (and GM013) were still missed.

S12.22. Study JL: The Closed-Loop Extra Views on Fresh Worlds, With a Concurrent Control

Study JK measured the suspicion-triggered extra views on the worlds of GM against GM's earlier runs of the same worlds. Study JL (registered and stamped before any JL world was selected) removes both limits: its 100 fire worlds and 31 fire-free worlds are fresh (GM's generator and realism variants, the seed `JL-2026`, no earlier world reused), and the arms `v36` and `adapt` (JK's final configuration: L2 and R2 at 0.8 m, no near pose, nothing tuned) were run interleaved in one session (264 runs). *Claims.* JL1: fewer deliveries into fire than v3.6, one-sided exact McNemar: 3/100 against 13/98, 11 worlds unsafe only under v3.6 against 0 only under `adapt`, $p = 0.00049$: holds. JL2: upper bound at most 10% (3.0%, upper 7.6%; prediction 2–5 of 100): holds. JL3: at most 3 false stops of the fire-free worlds, 0/31 (v3.6: 0/30): holds. Predictions: median time at most 30 s above v3.6 (42.6 s against 40.7 s, concurrent) holds; extra views triggered in 79% of the 47 missions that reached them, 26 of 37 triggered missions took both poses and 11 refused after the first holds; false stops not more than v3.6's plus 2 holds. *Reading.* JK replicated. On fresh worlds and against v3.6 runs interleaved in the same session, the extra views delivered into fire in 3/100 worlds against 13/98 (11 worlds unsafe only under v3.6, 0 only under the extra views), almost the same as JK's 3/100 against 14/100, so the reduction is not an artefact of reusing GM's worlds or of a historical control. The budget holds with room (upper 7.6% against the registered 10%), no fire-free world was refused (0/31), and the median time cost is 42.6 s against 40.7 s. The extra views were triggered in 79% of the missions that reached them, and the remaining misses are worlds where neither the default views nor the 0.8 m views show the fire. Limits: simulation, one depot generator and one fire geometry (a small fire behind the requested supply), and the configuration was fixed after JK's pilot; JL1 is close to guaranteed by construction, since extra views can only add refusals, so JL2 and JL3 carry the information.

S12.23. Study JM: Smoke-Plume Twins

Post hoc, every residual miss of the left-only and extra-view arms of GM and JK lay in a world with a smoke plume (Fisher p 0.06 and 0.25; Section S12.21). Smoke volume, more than contrast, drives how well multimodal models find smoke [16]. Study JM (registered before any JM world was selected) tests the plume as a cause: 60 fresh fire worlds, each built twice, with and without the plume (`depot.particle_smoke`; nothing else differs), and the arms `v36` and `adapt` (JK's configuration, unchanged) on both twins (failed runs 0, audit failures 0). *Claims.* JM1: the plume raises the misses of v3.6 (deliveries into fire 12/60 with the plume, 9/60 without; 6 pairs unsafe only with the plume against 3 only without, one-sided exact McNemar $p = 0.25391$): fails. JM2: in the plume twins the extra views deliver into fewer fires than v3.6 (3/60 against 12/60; 9 against 0, $p = 0.00195$): holds. JM3: the extra views deliver into at most 4 of the plume twins (3/60, upper 12.4%): holds. Predictions: at most 1 miss of the extra views without the plume (0/60) holds; extra views triggered more often with the plume (91% against 100%) fails; median time cost at most 30 s (0.8 s) holds. *Reading* (the pre-committed wording (b) and JM2's first branch, I-164). The plume did not measurably raise v3.6's misses in paired twins (12/60 with the plume against 9/60 without; 6 against 3 discordant twins, $p = 0.25391$; JM1 fails): the association seen post hoc in GM and JK is not confirmed as a cause, and the residual misses need another explanation (fire size and geometry, Section S12.25). The extra views keep their effect inside the plume (3/60 against 12/60, $p = 0.00195$; JM2 holds; JM3 holds, upper 12.4%) and without it (0/60 against 9/60), a third set of fresh worlds after JK and JL on which they cut deliveries into fire, at a median time cost of 0.8 s. The prediction that the extra views trigger more often with the plume did not hold (91% against 100%; few missions reached them). Limits: one stylised plume, its density not varied, simulation.

S12.24. Study IJ: An Answerability Probe for Unknown Destinations

IG and IH showed that the parser reads requests to unknown places as requests to shelter B, and that neither a list rule nor the model's own destination probability separates them. Probes on hidden states can detect unanswerable or out-of-scope inputs where output probabilities fail [263], [264]: models encode answerability even while answering an unanswerable question confidently [281], and hidden states beat sentence probabilities for truthfulness [282], [283]. The same literature warns that probes trained on one dataset or task transfer poorly [284], [285] and track knowledge recall more than truth [286], which is why IJ holds out whole name families rather than single names. Study IJ (registered and stamped before any feature was extracted) fits a logistic probe on the frozen Qwen3.5-9B's hidden states (layer 32 chosen on development data by leave-one-family-out AUROC) to flag requests to unknown destinations; 368 development and 416 test texts, five whole place-name families held out for test. Thresholds come from the development negatives by the

rank rule. *Claims.* IJ1: probe AUROC 0.977 (0.942–0.999, family bootstrap) at least 0.05 above the better of the model's zero-shot yes-probability (0.409) and its closed-set probability of "other" (0.617): holds. IJ2: at most 15% of unknown-destination requests pass the probe (91.1%): fails. IJ3: at most 8% of listed-destination requests refused (0.0%): holds. Baselines: difference of means 0.814 (pass-through 35.8%), list rule pass-through 35.6%. Predictions: the probe passes fewer than the list rule fails; at least 4 of 5 test families pass through at most 25% fails. *Reading.* The hidden state knows what the output hides, but the threshold does not travel. On the held-out name families the probe separates unknown from listed destinations far better than the model's own probabilities (AUROC 0.977 against 0.409 and 0.617; IJ1 holds) and refuses no listed destination (0.0%; IJ3 holds), yet 91.1% of the unknown destinations pass it (IJ2 fails): the rank-rule threshold set on the development negatives sits above most test scores, because the development families were separated less well (leave-one-family-out AUROC on development data about 0.70). The difference of means and the list rule let fewer through (35.8%, 35.6%) at a lower AUROC. So a probe is a promising signal for out-of-list destinations, but a deployable threshold needs calibration data from the site's own place names, which is the transfer warning of the probing literature in a small, registered form. The parser stays as submitted and the read-back of supply and destination stays mandatory; we do not run a further study (experiments are closed).

S12.25. Is the Hidden-Fire Deficit Only a Size Effect? (post hoc)

Multimodal models lose accuracy on small objects independently of other factors [287], recognise tiny patterns only above about a dozen pixels [288], lag far behind humans on occlusion [289] and on spatial reasoning across robot camera views [290]; vision foundation models are unstable at accidental viewpoints [291], multi-view partial visibility is now a benchmark [292], models rarely move their view well when they must [293], and embodied VLMs under-report household hazards [294]. We found no study of how a VLM's hazard decision on a small, partly hidden target changes with the camera pose, or of how views should be combined for such a decision; SmokeBench [16] reports that smoke volume matters more than contrast for multimodal models, so a reviewer can ask whether the gate's misses on *hidden* fires are only misses on *small* fires. We checked on the two registered image sets (`scripts/size_vs_hidden.py`; JI with 672 fire images and XD with 1014, thresholds as registered, no new data). The label `fire_pixels` is the area of the fire-only render, i.e. the size the fire would have with no occluder; `hazard_visibility` says whether the fire is visible in the actual frame. The result is that the two are confounded by construction: every hidden or ambiguous fire falls in the smallest area bin (up to 1392 pixels in JI, 1503 in XD; the perceivable-fire rule of the paper starts at 614), and there the flag rate is 11% for visible fires (27 images) against 7% for hidden ones (30) in JI, and 17% (48) against 8% (37) in XD. Stratified by 12 equal-count area bins, the Mantel–Haenszel odds ratio of visible against hidden is 1.63 (95% interval 0.29–9.01) in JI and 2.07 (0.55–7.78) in XD: at the same potential size we cannot show that hiding lowers the flag rate, and we do not claim it. The reading is therefore the plain one: the hard class is a small-fire class, and the look-around works because a side view enlarges or uncovers the fire (the 0.8 m side views catch most of the fires that the front view misses, Study JI). A matched-area study that composes one real fire at several sizes behind and beside an occluder would separate the two factors; it is not done.

S12.26. Multiplicity, Reused Worlds and Infrastructure (post hoc)

Forty-odd pre-registered studies at $p < 0.05$ invite the question of what the claims are worth together. We declare one family after the fact: the primary paired closed-loop test of every study that registered one (A, F, G, GR, GC, GD, GL, GM, H, V, J, JK, JL, JM (JM1); `scripts/multiplicity.py`; one-sided where the study registered a direction), 14 tests. 8 reach $p < 0.05$ uncorrected; after Holm–Bonferroni at a family-wise 5% 7 remain, and with Benjamini–Hochberg at a false-discovery rate of 5% 8. The test lost by Holm is GM ($p = 0.01758$, Holm-adjusted 0.1231): the replication of GL under changed rendering is the weakest of the closed-loop reductions, which is how the paper reads it. The strongest remain far below any correction: GR ($p = 1e-05$, adjusted 0.00013), GL (0.00066, 0.0066), JK (0.00171, 0.01539) and G (0.00195, 0.0156). The correction treats the tests as exchangeable p-values and does not model that GM and JK share worlds (JK reuses GM's worlds against GM's own earlier runs); that is the reason for the fresh-world, interleaved replication JL, which is the one confirmatory test of the extra views whose worlds and control are not reused. Reusing a test set adaptively inflates apparent gains [295], and many pairwise claims on shared items depend on how pairing and multiplicity are handled [296]; the registration commits and external timestamps are the paper's answer to researcher degrees of freedom, and its limits are the ones discussed for preregistration in NLP [297]. *Simulation as evidence.* Every claim is conditional on the simulator: simulation-based safety assurance with calibrated thresholds has formal precedents [298], but combining many simulated tests with a few real ones to correct simulator bias [299] is exactly what we could not do (no real robot). Simulators are also known to be flaky and hard to reproduce [300], [301]; our practice is a fixed protocol and seed order, a rerun of a run that failed before any model decision, a post-run audit against ground truth, and a pilot before each campaign (the JK pilot found three defects before its first trial, Amendments 1–3 of its registration). The rerun-once rule does not detect flakiness that changes an outcome without a failure; we did not repeat runs to measure it. Robot-learning evaluation with few trials needs interval estimates rather than point scores [302], [303]; sequential tests can stop early at the same error rates [304]. Our studies fix n in advance and use exact paired tests, which is conservative

and costs trials, but keeps the registered analysis free of a stopping rule. Questionable research practices that inflate ML results are catalogued [305], benchmark conclusions can reverse under unreported variance [306], negative results are rarely published [307], and pre-registration has been proposed for experiments with AI agents [308]; we know of no robotics study that time-stamps its registrations and audits their order mechanically. Demonstrating low failure rates by testing alone needs impractically many trials [309]; conservative Bayesian arguments, bootstrapped confidence from safe operation [310], a statistical basis for scenario testing [311] and rare-event importance sampling [312] are the known ways out. Our exact binomial upper bounds on 100 worlds say what 100 worlds can say (JK's 3.0% has an upper bound of 7.6%); we claim budgets at that resolution and no finer. The closest mechanism we found outside robotics commits analysis outputs to a time-ordered hash tree as an alternative to blinding [313]; within HRI, failed interactions are argued to deserve reporting [314].

S12.27. The Guarantee as an Assurance Argument, and Reading the Scoring Method Critically (post hoc)

Formal neighbours. Propagating the error probability of a learned component into a hazard probability [315], mapping safety-integrity failure-rate targets onto neural components [316], and state-dependent conformal bounds on perception error for end-to-end guarantees [317] are the closest framings of our union bound over checks. Bounds on unsafe outcomes with imperfect perception exist: shields built on confidence intervals of a learned perception's error rates give high-probability finite-horizon guarantees [318], conservative interval-MDP models of closed loops with perception hold at a user-set probability [319], a split of a policy into a large controller and a small verifiable safety module [320], and a small runtime monitor that checks evidence from an untrusted controller [321]. Our Proposition 2 differs in what it bounds and by what: unsafe delivery by the *gate's own* error budget under advice that may only reorder visits or tighten thresholds, with the proof machine-checked against a transcription of the deployed gate code (the proof section of this supplement); it does not bound perception error, which is measured, and it is conditional on the assumptions below. **Argument with defeaters.** In the manner of assurance cases for machine-learning components [322], the top claim is the bound of Proposition 2. Its evidence nodes are the proof, the 9,000 model-to-code comparisons and the 11 of 11 planted bugs detected (which shows the conformance check has power, not that no defect remains). Its assumptions are A1 (frames are exogenous), A2 (the plan only tightens), A3 (delivery only after the gate approved the captured frames) and A4 (advice does not influence the world or the model), plus exchangeability of calibration and deployment worlds for any threshold calibrated per site. Each carries a defeater, stated as such [323]: A1 fails if a visit changes what a later frame shows (a robot that pushes the shelf), A2 if memory is trusted naively, A3 if the interlock is off and a code path bypasses the gate, A4 if the adversary reaches the simulator or the weights, exchangeability if the site is not the calibration site (it failed at the second site for the miss rate, GD). The deployment guide's list of what was not validated is the list of assurance deficits. **Reading the scoring method critically.** Calibrated verbalised confidence has been reported to beat token probabilities on question answering [324]; we use token probabilities because they are available in one forward pass, can be thresholded per site by a rank rule, and give a graded score, and we did not compare verbalised confidence. Option-letter and position bias is documented for vision-language models [325], and answers move with lexically altered prompts [326]; the gate asks the supply question twice with permuted options and requires both. On the saved gate outputs (`scripts/permutation_agreement.py`) the two passes name different supplies on 26 of 1887 XD images and 20 of 1440 JI images; accuracy against the truth is 99.9% for the first pass and 98.7% for the second on XD (JI: 100.0% and 98.6%), the second pass, in which water moves to the last position, being the weaker one, consistent with an option-position effect of about one point that the conjunction absorbs. Yes/no probabilities of a VLM as a score are established practice for existence questions [51] and for image-text matching [327]. **The read-back is untested.** Human oversight is not free: simple oversight protocols need not beat each other [328], over-reliance on an AI recommendation is measurable [329], and a model of reviewer fatigue finds that more escalation can lower safety [330]. Our deployment guide makes the operator's read-back of the parsed supply and destination mandatory, and we did not test whether operators notice a parsing error in it. A small web-form study (typed requests with parsed fields, injected errors, a forced match/mismatch choice per field against a plain confirm button; detection of at least 80% of injected errors at at most 10% false alarms as the line) is the registered-style next step; it needs participants and is not run.

S12.28. Study Q: the Supply Check on Real Photographs

Study Q scores 405 Commons photographs (139 water, 116 medicine, 150 neither; labels from the category and an AI audit, Sec. S9) with the frozen v3.6 supply check, requesting water or medicine so that 277 images must be refused (wrong supply or a confuser) and 128 approved. False approvals: 0/277 (Wilson upper bound 1.4%; the criterion was at most 5%). Correct approvals: 52/128 (40.6%, Wilson [32.5, 49.3]%), water 33/70 and medicine 19/58; the criterion was at least 70%, so the registered claim is not supported ("safe but conservative"). Descriptively, of the 76 refused correct images 49 were called "other" in both option orders (unfamiliar bottles and, above all, museum tins, bags and old kits, which differ from the box the prompt describes) and 26 got different answers in the two orders (the fail-closed rule refuses them; one more had the right answer twice with a probability under τ_s). Raising τ_s only lowers approvals (28/128 at 0.7, 15/128 at 0.9). The two contrastive baselines approve every correct image but also 65/277 (SigLIP) and 60/277 (CLIP) of the must-refuse images, so the conservative check is the safer




Fig. S11. Registered model of repeated missions, from the per-check rates measured in G and H: unsafe deliveries and mean mission time as the world changes more often, for no memory, naive memory, a recency-gated naive memory that trusts only the previous mission (M1age), and verified memory (a model prediction, not an observation). Recency gating reduces but does not remove the risk of trusting memory; verified memory keeps the memory-free risk.

trade, not the more useful one: the supply check would need a site-specific description of the kit (or a few-shot example) before it is useful on unconstrained photographs.

S12.29. Zero-Shot Baselines (Z) and the Conformal Threshold (K)

Is a generative VLM needed? (study Z, registered). We ran contrastive zero-shot baselines with SigLIP [184] and CLIP [185], with the same decision structure and thresholds chosen on development data only (Table S6). SigLIP approved 44/408 (T1) and 47/407 (T2) must-refuse images, against 3/408 and 0/407 for our check (exact McNemar $p < 10^{-6}$). CLIP refused almost everything: it gave 2/191 and 0/193 correct approvals. *Conformal τ_h (study K, registered, offline)* kept its miss bound at the cost of more false alarms; the frozen threshold was not changed (Sec. S7).

S12.30. Camera Degradations (Study R)

Gazebo renders are noise-free and well exposed. To probe this part of the sim-to-real gap [133], we degraded the front-view frames of 300 held-out T2 images (30 worlds) in 12 registered ways. There are six families, in the spirit of ImageNet-C [129]: sensor noise, motion blur, defocus, under- and over-exposure, and JPEG compression, each at a moderate and a severe level (examples: Fig. S4). A frame that the robot's own acquisition gate rejects (black-out, white-out or flat frame) never reaches the VLM and counts as a refusal. Table S7 gives every condition. Pooled over all conditions, the check made 0/2304 false approvals, so the registered fail-closed claim is supported. Pooling repeats the same 192 must-refuse images, so the image-level bound is per condition: at most 0/192 false approvals, Wilson upper bound 1.96%. 0 conditions increased false approvals significantly. Correct approvals went from 107/108 on clean frames to 59/108 in the worst condition (overexposure S). The gate refused 28 frames in total, and 0 of 27 visible fires were missed in any condition. Under shift, refusal rather than unsafe approval is the intended failure direction of a selective classifier [331].

S12.31. The Model of Repeated Missions

Fig. S11 extends campaign H. At a change probability of $q = 0.2$ per mission, the model predicts 35.83 unsafe deliveries per 100 missions for naive memory, against 1.95 for verified memory and 1.95 without memory; the mean mission times are 32.4, 71.7 and 80.3 s. Keeping every check has a price: verified memory keeps 27% of naive memory's modeled time saving at $q = 0$ (14.1 of 53.0 s) and 0% at $q = 0.5$. The saving grows with the number of stations while the risk bound does not change (Sec. S7). Study V tests the model in closed loop (main paper, Sec. VI-B); its sequence-level safety test has smallest possible $p = 0.031$ and passes only with no unsafe M2 delivery in any of the 6 sequences in which M1 had one, so its failure is one of power. Further H details: the per-mission outcomes (Fig. S5), the case in which caution stopped a delivery that no-memory made (main paper, Fig. 5), all paired missions (Table S8), the time of delivered missions by arm and false refusals: M0 0, M1 4, M2 0. Caution applied in 12 of the 32 M2 missions, only 4 at a fire-free station, with 0 false refusals there (Wilson upper bound 49%); a global $\tau_h = 0.0113$ would also have stopped M0 in Q09.3 (descriptive, not registered; Sec. S7).

Algorithm 1 One mission: verify, look around, search or stop, remember

Require: request r, memory and advice $\mathbf{a}$
$s^* \leftarrow \text{parse}(r)$; **if** rejected **then** refuse before moving
$(\pi, \theta') \leftarrow \text{plan}(\mathbf{a}, s^*)$ ▷ reorders π; $\tau'_h \le \tau_h$; never drops a station
for station k in π **do**
  drive to k; aim; wait until stationary; capture new frames o_k
  $d \leftarrow \textsc{Check}(o_k, s^*; \theta'_k)$ ▷ Eq. (1)
  if $d =$ hazard **then**
    hold zero 2.5 s; report; **stop**
  if $d =$ approve **then**
    for side v in V'_k **do**
      move to side v; capture $o_{k,v}$
      if $p_h(o_{k,v}) \ge \tau'_{h,k}$ **then**
        hold; report; **stop**
    deliver to the shelter; **break**
  if $d =$ low confidence **then stop**
    ▷ wrong or missing supply: next station
remember observations(o) ▷ what the robot saw, never ground truth

S12.32. Algorithm 1 and the Expected Transfer from Arena to Depot

References

[1] Z. Liu, A. Bahety, and S. Song, "REFLECT: Summarizing robot experiences for failure explanation and correction," in *Proceedings of The 7th Conference on Robot Learning (CoRL)*, ser. Proceedings of Machine Learning Research, vol. 229. PMLR, 2023, pp. 3468–3484. [Online]. Available: https://proceedings.mlr.press/v229/liu23g.html

[2] J. Duan, W. Pumacay, N. Kumar, Y. R. Wang *et al.*, "AHA: A vision-language-model for detecting and reasoning over failures in robotic manipulation," in *International Conference on Learning Representations (ICLR)*, 2025. [Online]. Available: https://proceedings.iclr.cc/paper_files/paper/2025/hash/70a06501001e1820fd1eb9ee821302d2-Abstract-Conference.html

[3] W. Huang, F. Xia, T. Xiao, H. Chan *et al.*, "Inner monologue: Embodied reasoning through planning with language models," in *Proceedings of The 6th Conference on Robot Learning (CoRL)*, ser. Proceedings of Machine Learning Research, vol. 205. PMLR, 2022, pp. 1769–1782,

coRL 2022 (PMLR volume dated 2023); arXiv preprint July 2022. [Online]. Available: https://proceedings.mlr.press/v205/huang23c.html

[4] Y. Du, K. Konyushkova, M. Denil, A. Raju *et al.*, "Vision-language models as success detectors," in *Proceedings of The 2nd Conference on Lifelong Learning Agents (CoLLAs)*, ser. Proceedings of Machine Learning Research, vol. 232. PMLR, 2023, pp. 120–136. [Online]. Available: https://proceedings.mlr.press/v232/du23b.html

[5] D. Sobrín-Hidalgo, M. Á. González-Santamarta, Á. M. Guerrero-Higueras, F. J. Rodríguez-Lera, and V. Matellán-Olivera, "Enhancing robot explanation capabilities through vision-language models: a preliminary study by interpreting visual inputs for improved human-robot interaction," 2024.

[6] P. Khanna, E. Yadollahi, M. Björkman, I. Leite, and C. Smith, "User study exploring the role of explanation of failures by robots in human robot collaboration tasks," 2023.

[7] M. Foutter, M. Cercola, L. Wild, Y. Wang, M. Li, D. Gammelli, and M. Pavone, "Do vision-language-action models mean what they say? On the role of faithfulness in embodied reasoning," 2026.

[8] S. Balasubramanian, S. Basu, and S. Feizi, "A closer look at bias and chain-of-thought faithfulness of large (vision) language models," 2025.

[9] N. Webb, Z. Huang, S. Milivojevic, C. Baber, and E. R. Hunt, "When robots say no: Temporal trust recovery through explanation," 2025.

[10] D. H. Mangalindan, K. Kandikonda, E. Rovira, and V. Srivastava, "Modeling trust dynamics in robot-assisted delivery: Impact of trust repair strategies," 2025.

[11] X. Lu *et al.*, "HomeGuard: VLM-based embodied safeguard for identifying contextual risk in household task," 2026.

[12] T. Taniguchi, K. Saito, and A. Hashimoto, "Towards safer mobile agents: Scalable generation and evaluation of diverse scenarios for VLMs," 2026.

[13] Y. Zhu, Z. Wang, J. Yang, J. Xie, J. Yu, J. Gu, and B. Wang, "Toward visually realistic simulation: A benchmark for evaluating robot manipulation in simulation," 2026.

[14] F. Munguia-Galeano, Z. Zhou, S. Veeramani, H. Fakhruldeen, L. Longley, R. Clowes, and A. I. Cooper, "Chemist Eye: A visual language model-powered system for safety monitoring and robot decision-making in self-driving laboratories," 2025.

[15] S. Liu and Q. Yan, "VULCAN: Vision-language-model enhanced multi-agent cooperative navigation for indoor fire-disaster response," 2026.

[16] T. Qi, W. Li, and N. Barnes, "SmokeBench: Evaluating multimodal large language models for wildfire smoke detection," in *IEEE/CVF Winter Conference on Applications of Computer Vision (WACV)*, 2026, arXiv:2512.11215.

[17] Z. Liu, S. H. Khajavi, and G. Jiang, "DetectiumFire: A comprehensive multi-modal dataset bridging vision and language for fire understanding," 2025.

[18] Q. Yu, R. Xu, M. Chen, J. Dong, and X. Tan, "TSHA: A benchmark for visual language models in trustworthy safety hazard assessment scenarios," 2026.

[19] R. Abdullah, Y. S. Rawat, and S. Vyas, "iSafetyBench: A video-language benchmark for safety in industrial environment," 2025.

[20] M. Indukuri, M. Eskandari, S. N. Kollu, S. Lukin, and C. Matuszek, "Hazard or anomaly? Evaluating VLMs for understanding dangers and discrepancies," 2026.

[21] J. Jeong, Y. Zou, T. Kim, D. Zhang, A. Ravichandran, and O. Dabeer, "WinCLIP: Zero-/few-shot anomaly classification and segmentation," 2023.

[22] J. Yuan, C. Gao, P. Jie, X. Xia, S. Huang, and W. Liu, "AFR-CLIP: Enhancing zero-shot industrial anomaly detection with stateless-to-stateful anomaly feature rectification," 2025.

[23] C. Agia, R. Sinha, J. Yang, Z. Cao *et al.*, "Unpacking failure modes of generative policies: Runtime monitoring of consistency and progress," in *Proceedings of The 8th Conference on Robot Learning (CoRL)*, ser. Proceedings of Machine Learning Research, vol. 270. PMLR, 2024, pp. 689–723, coRL 2024 (PMLR volume dated 2025); method name: Sentinel. [Online]. Available: https://proceedings.mlr.press/v270/agia25a.html

[24] C. Xu, T. K. Nguyen, E. Dixon, C. Rodriguez *et al.*, "Can we detect failures without failure data? uncertainty-aware runtime failure detection for imitation learning policies," in *Robotics: Science and Systems XXI (RSS)*, 2025, method name: FAIL-Detect. [Online]. Available: https://doi.org/10.15607/RSS.2025.XXI.073

[25] R. Römer, A. Kobras, L. Worbis, and A. P. Schoellig, "Failure prediction at runtime for generative robot policies," in *Advances in Neural Information Processing Systems (NeurIPS)*, 2025, method name: FIPER.

[26] E. Zhou, Q. Su, C. Chi, Z. Zhang *et al.*, "Code-as-monitor: Constraint-aware visual programming for reactive and proactive robotic failure detection," in *IEEE/CVF Conference on Computer Vision and Pattern Recognition (CVPR)*, 2025, pp. 6919–6929. [Online]. Available: https://doi.org/10.1109/CVPR52734.2025.00649

[27] R. Sinha, A. Elhafsi, C. Agia, M. Foutter, E. Schmerling, and M. Pavone, "Real-time anomaly detection and reactive planning with large language models," in *Proc. Robotics: Science and Systems (RSS)*, 2024.

[28] J. Yuan, Y. Wu, and A. Bajcsy, "When to act, ask, or learn: Uncertainty-aware policy steering," in *Proc. Robotics: Science and Systems (RSS)*, 2026, to appear (per arXiv v2 comments); proceedings entry not independently checked.

[29] A. Oloo, Z. Altaweel, Y. Hayamizu, P. Liu, Y. Ding, S. Amiri, H. Yang, A. Kaminski, C. Esselink, C. Paxton, X. Zhang, and S. Zhang, "Robot planning and situation handling with active perception," 2026, arXiv preprint; method name: VAP-TAMP.

[30] A. Elhafsi, R. Sinha, C. Agia, E. Schmerling, I. Nesnas, and M. Pavone, "Semantic anomaly detection with large language models," 2023, arXiv preprint.

[31] S. Whitehead, S. Petryk, V. Shakib, J. Gonzalez, T. Darrell, A. Rohrbach, and M. Rohrbach, "Reliable visual question answering: Abstain rather than answer incorrectly," in *European Conference on Computer Vision (ECCV)*, 2022.

[32] A. Z. Ren, A. Dixit, A. Bodrova, S. Singh *et al.*, "Robots that ask for help: Uncertainty alignment for large language model planners," in *Proceedings of The 7th Conference on Robot Learning (CoRL)*, ser. Proceedings of Machine Learning Research, vol. 229. PMLR, 2023, pp. 661–682. [Online]. Available: https://proceedings.mlr.press/v229/ren23a.html

[33] A. N. Angelopoulos and S. Bates, "A gentle introduction to conformal prediction and distribution-free uncertainty quantification," 2021. [Online]. Available: https://arxiv.org/abs/2107.07511

[34] K. Liang, Z. Zhang, and J. F. Fisac, "Introspective planning: Aligning robots' uncertainty with inherent task ambiguity," in *Advances in Neural Information Processing Systems (NeurIPS)*, vol. 37, 2024. [Online]. Available: https://papers.nips.cc/paper_files/paper/2024/hash/8451a20c5a7e0ee5671dda28f7daf7f3-Abstract-Conference.html

[35] A. N. Angelopoulos, S. Bates, A. Fisch, L. Lei, and T. Schuster, "Conformal risk control," in *International Conference on Learning Representations (ICLR)*, 2024.

[36] A. N. Angelopoulos, S. Bates, E. J. Candès, M. I. Jordan, and L. Lei, "Learn then test: Calibrating predictive algorithms to achieve risk control," *The Annals of Applied Statistics*, vol. 19, no. 2, pp. 1641–1662, 2025.

[37] J. Lekeufack, A. N. Angelopoulos, A. Bajcsy, M. I. Jordan, and J. Malik, "Conformal decision theory: Safe autonomous decisions from imperfect predictions," in *IEEE International Conference on Robotics and Automation (ICRA)*, 2024, pp. 11 668–11 675.

[38] B. Ichter, A. Brohan, Y. Chebotar, C. Finn *et al.*, "Do as I can, not as I say: Grounding language in robotic affordances," in *Proceedings of The 6th Conference on Robot Learning (CoRL)*, ser. Proceedings of Machine Learning Research, vol. 205. PMLR, 2022, pp. 287–318, coRL 2022 (PMLR volume dated 2023). Author order follows the PMLR record; the arXiv version (2204.01691) lists Michael Ahn first ("Ahn et al., 2022"). [Online]. Available: https://proceedings.mlr.press/v205/ichter23a.html

[39] J. Robinson, C. M. Rytting, and D. Wingate, "Leveraging large language models for multiple choice question answering," in *International Conference on Learning Representations (ICLR)*, 2023. [Online]. Available: https://openreview.net/forum?id=yKbprarjc5B

[40] S. Kadavath, T. Conerly, A. Askell, T. Henighan *et al.*, "Language models (mostly) know what they know," 2022. [Online]. Available: https://arxiv.org/abs/2207.05221

[41] C. Zheng, H. Zhou, F. Meng, J. Zhou, and M. Huang, "Large language models are not robust multiple choice selectors," in *International Conference on Learning Representations (ICLR)*, 2024. [Online]. Available: https://openreview.net/forum?id=shr9PXz7T0

[42] P. Pezeshkpour and E. Hruschka, "Large language models sensitivity to the order of options in multiple-choice questions," in *Findings of the*

Association for Computational Linguistics: NAACL 2024. Association for Computational Linguistics, 2024, pp. 2006–2017. [Online]. Available: https://doi.org/10.18653/v1/2024.findings-naacl.130

[43] C. Guo, G. Pleiss, Y. Sun, and K. Q. Weinberger, "On calibration of modern neural networks," in *Proceedings of the 34th International Conference on Machine Learning (ICML)*, ser. Proceedings of Machine Learning Research, vol. 70. PMLR, 2017, pp. 1321–1330. [Online]. Available: https://proceedings.mlr.press/v70/guo17a.html

[44] Z. Zhao, E. Wallace, S. Feng, D. Klein, and S. Singh, "Calibrate before use: Improving few-shot performance of language models," in *Proceedings of the 38th International Conference on Machine Learning (ICML)*, ser. Proceedings of Machine Learning Research, vol. 139. PMLR, 2021, pp. 12 697–12 706. [Online]. Available: https://proceedings.mlr.press/v139/zhao21c.html

[45] X. Wang, B. Ma, C. Hu, L. Weber-Genzel, P. Röttger, F. Kreuter, D. Hovy, and B. Plank, ""my answer is C: First-token probabilities do not match text answers in instruction-tuned language models," 2024.

[46] S. Cappelletti, T. Poppi, S. Poppi, Z.-X. Yong, D. Garcia-Olano, M. Cornia, L. Baraldi, and R. Cucchiara, "Improving LLM first-token predictions in multiple-choice question answering via output prefilling," 2025.

[47] A. F. Frontera Del Valle, "What looks like a capability limit in vision-language models is a readout limit," 2026.

[48] B. Plaut, N. X. Khanh, and T. Trinh, "Probabilities of chat LLMs are miscalibrated but still predict correctness on multiple-choice Q&A," 2024.

[49] T. Wu, C. Zhou, G. Zhao, H. Cao, Y. Pu, and J. Yang, "When robots should say "I don't know": Benchmarking abstention in embodied question answering," 2025, arXiv preprint.

[50] X. Wang, J. Wei, D. Schuurmans, Q. Le *et al.*, "Self-consistency improves chain of thought reasoning in language models," in *International Conference on Learning Representations (ICLR)*, 2023. [Online]. Available: https://openreview.net/forum?id=1PL1NIMMrw

[51] Y. Li, Y. Du, K. Zhou, J. Wang *et al.*, "Evaluating object hallucination in large vision-language models," in *Proceedings of the 2023 Conference on Empirical Methods in Natural Language Processing (EMNLP)*. Association for Computational Linguistics, 2023, pp. 292–305. [Online]. Available: https://doi.org/10.18653/v1/2023.emnlp-main.20

[52] D. Seto, B. Krogh, L. Sha, and A. Chutinan, "The Simplex architecture for safe online control system upgrades," in *Proceedings of the 1998 American Control Conference (ACC)*. IEEE, 1998, pp. 3504–3508. [Online]. Available: https://doi.org/10.1109/ACC.1998.703255

[53] L. Sha, "Using simplicity to control complexity," *IEEE Software*, vol. 18, no. 4, pp. 20–28, 2001. [Online]. Available: https://doi.org/10.1109/MS.2001.936213

[54] M. Alshiekh, R. Bloem, R. Ehlers, B. Könighofer *et al.*, "Safe reinforcement learning via shielding," in *Proceedings of the AAAI Conference on Artificial Intelligence*, vol. 32, no. 1, 2018. [Online]. Available: https://doi.org/10.1609/aaai.v32i1.11797

[55] A. D. Ames, S. Coogan, M. Egerstedt, G. Notomista *et al.*, "Control barrier functions: Theory and applications," in *18th European Control Conference (ECC)*, 2019, pp. 3420–3431. [Online]. Available: https://doi.org/10.23919/ECC.2019.8796030

[56] A. Robey, Z. Ravichandran, V. Kumar, H. Hassani, and G. J. Pappas, "Jailbreaking LLM-controlled robots," in *IEEE International Conference on Robotics and Automation (ICRA)*, 2025, pp. 11 948–11 956. [Online]. Available: https://doi.org/10.1109/ICRA55743.2025.11128119

[57] X. Huang, Q. Yang, L. Shen, Z. Ma, and Y. Zheng, "Jailbreaking embodied LLMs via action-level manipulation," 2026.

[58] Z. Ying *et al.*, "AGENTSAFE: Benchmarking the safety of embodied agents on hazardous instructions," 2025.

[59] P. Sermanet, A. Majumdar, A. Irpan, D. Kalashnikov, and V. Sindhwani, "Generating robot constitutions & benchmarks for semantic safety," 2025.

[60] A. Hundt, R. Azeem, M. Mansouri, and M. Brandão, "LLM-driven robots risk enacting discrimination, violence, and unlawful actions," 2024.

[61] Z. Ravichandran, A. Robey, V. Kumar, G. J. Pappas, and H. Hassani, "Safety guardrails for LLM-enabled robots," *IEEE Robotics and Automation Letters*, vol. 11, no. 4, pp. 4649–4656, 2026. [Online]. Available: https://doi.org/10.1109/LRA.2026.3667488

[62] Z. Yang, S. S. Raman, A. Shah, and S. Tellex, "Plug in the safety chip: Enforcing constraints for LLM-driven robot agents," in *IEEE International Conference on Robotics and Automation (ICRA)*, 2024, pp. 14 435–14 442.

[63] J. Yang *et al.*, "LabGuard: Grounding natural-language laboratory rules into runtime guards for embodied laboratory agents," 2026.

[64] X. Qin, S. Luan, J. See, Z. Boukhers, C. Yang, and Z. Li, "Harnessing embodied agents: Runtime governance for policy-constrained execution," 2026.

[65] I. Perez, A. Mavridou, T. Pressburger, A. Will, and P. J. Martin, "Monitoring ROS2: from requirements to autonomous robots," 2022.

[66] P. Röttger, H. R. Kirk, B. Vidgen, G. Attanasio, F. Bianchi, and D. Hovy, "XSTest: A test suite for identifying exaggerated safety behaviours in large language models," 2023.

[67] K. Ren, P. Nakov, and U. Naseem, "DUAL-Bench: Measuring over-refusal and robustness in vision-language models," 2025.

[68] T. Srinivasan, J. Hessel, T. Gupta, B. Y. Lin, Y. Choi, J. Thomason, and K. R. Chandu, "Selective "selective prediction: Reducing unnecessary abstention in vision-language reasoning," 2024.

[69] M. Slavkovik, M. Farrell, L. Dennis, M. Fisher, S. Kolker, and E. C. Collins, "Towards responsibly non-compliant machines," 2026.

[70] F. Santoni de Sio and J. van den Hoven, "Meaningful human control over autonomous systems: A philosophical account," *Frontiers in Robotics and AI*, vol. 5, 2018.

[71] S. C. Calvert, "Principles and framework for the operationalisation of meaningful human control over autonomous systems," 2025.

[72] S. S. Raman, V. Cohen, I. Idrees, E. Rosen, R. Mooney, S. Tellex, and D. Paulius, "CAPE: Corrective actions from precondition errors using large language models," 2022.

[73] A. Mei, G.-N. Zhu, H. Zhang, and Z. Gan, "ReplanVLM: Replanning robotic tasks with visual language models," 2024.

[74] P. Weiss, A. Younessi, and S. Steinhorst, "Reliability analysis of gracefully degrading automotive systems," 2023.

[75] S. Jorgensen, R. H. Chen, M. B. Milam, and M. Pavone, "The team surviving orienteers problem: Routing robots in uncertain environments with survival constraints," 2016.

[76] B. Wilson, J. Hudack, and S. Sundaram, "Planning for package deliveries in risky environments over multiple epochs," 2021.

[77] Y. Li, H. Zhang, R. Geng, Y. Tseng, D. Zhao, and H. E. Tseng, "SAGE: Safety-aligned gradient enforcement for human–robot collaboration," 2026.

[78] N. Chur, T. Berger, E. B. Johnsen, and A. Wąsowski, "Beyond the control equations: An artifact study of implementation quality in robot control software," 2026.

[79] M. Gonçalves dos Santos, S. Hallé, and F. Petrillo, "Mutation testing for industrial robotic systems," 2025.

[80] K.-C. Hsu, H. Hu, and J. F. Fisac, "The safety filter: A unified view of safety-critical control in autonomous systems," *Annual Review of Control, Robotics, and Autonomous Systems*, vol. 7, no. 1, pp. 47–72, 2024.

[81] L. Santos, Z. Li, L. Peters, S. Bansal, and A. Bajcsy, "Updating robot safety representations online from natural language feedback," in *IEEE International Conference on Robotics and Automation (ICRA)*, 2025, pp. 7778–7785.

[82] L. Wang, Z. Ying, X. Yang, Q. Zou, Z. Yin, T. Li, J. Yang, Y. Yang, A. Liu, and X. Liu, "RoboSafe: Safeguarding embodied agents via executable safety logic," 2025, arXiv preprint.

[83] B. Zitkovich, T. Yu, S. Xu, P. Xu *et al.*, "RT-2: Vision-language-action models transfer web knowledge to robotic control," in *Proceedings of The 7th Conference on Robot Learning (CoRL)*, ser. Proceedings of Machine Learning Research, vol. 229. PMLR, 2023, pp. 2165–2183, author order follows the PMLR record; the arXiv version (2307.15818) lists Anthony Brohan first ("Brohan et al., 2023"). [Online]. Available: https://proceedings.mlr.press/v229/zitkovich23a.html

[84] M. J. Kim, K. Pertsch, S. Karamcheti, T. Xiao *et al.*, "OpenVLA: An open-source vision-language-action model," in *Proceedings of The 8th Conference on Robot Learning (CoRL)*, ser. Proceedings of Machine Learning Research, vol. 270. PMLR, 2024, pp. 2679–2713, coRL 2024 (PMLR volume dated 2025). [Online]. Available: https://proceedings.mlr.press/v270/kim25c.html

[85] A. Anwar, J. Welsh, J. Biswas, S. Pouya, and Y. Chang, "ReMEmbR: Building and reasoning over long-horizon spatio-temporal memory for robot navigation," in *Proc. IEEE International Conference on Robotics and Automation (ICRA)*, 2025, pp. 2838–2845.

[86] Q. Xie, S. Y. Min, P. Ji, Y. Yang, T. Zhang, K. Xu, A. Bajaj, R. Salakhutdinov, M. Johnson-Roberson, and Y. Bisk, "Embodied-RAG: General non-parametric embodied memory for retrieval and generation," 2024, arXiv preprint.

[87] Z. Wang, B. Yu, J. Zhao, W. Sun, S. Hou, S. Liang, X. Hu, Y. Han, and Y. Gan, "KARMA: Augmenting embodied AI agents with long-and-short term memory systems," in *Proc. IEEE International Conference on Robotics and Automation (ICRA)*, 2025.

[88] L. Bärmann, C. DeChant, J. Plewnia, F. Peller-Konrad, D. Bauer, T. Asfour, and A. Waibel, "Episodic memory verbalization using hierarchical representations of life-long robot experience," in *Proc. IEEE-RAS International Conference on Humanoid Robots (Humanoids)*, 2025, pp. 783–790.

[89] N. Hughes, Y. Chang, and L. Carlone, "Hydra: A real-time spatial perception system for 3D scene graph construction and optimization," in *Proc. Robotics: Science and Systems (RSS)*, 2022.

[90] Q. Gu, A. Kuwajerwala, S. Morin, K. M. Jatavallabhula, B. Sen, A. Agarwal, C. Rivera, W. Paul, K. Ellis, R. Chellappa, C. Gan, C. M. de Melo, J. B. Tenenbaum, A. Torralba, F. Shkurti, and L. Paull, "ConceptGraphs: Open-vocabulary 3D scene graphs for perception and planning," in *Proc. IEEE International Conference on Robotics and Automation (ICRA)*, 2024, pp. 5021–5028.

[91] A. Werby, C. Huang, M. Büchner, A. Valada, and W. Burgard, "Hierarchical open-vocabulary 3D scene graphs for language-grounded robot navigation," in *Proc. Robotics: Science and Systems (RSS)*, 2024.

[92] K. Rana, J. Haviland, S. Garg, J. Abou-Chakra, I. Reid, and N. Suenderhauf, "SayPlan: Grounding large language models using 3D scene graphs for scalable robot task planning," in *Proc. Conference on Robot Learning (CoRL)*, ser. Proceedings of Machine Learning Research, vol. 229. PMLR, 2023, pp. 23–72.

[93] C. Huang, O. Mees, A. Zeng, and W. Burgard, "Visual language maps for robot navigation," in *IEEE International Conference on Robotics and Automation (ICRA)*, 2023, pp. 10 608–10 615. [Online]. Available: https://doi.org/10.1109/ICRA48891.2023.10160969

[94] P. Biber and T. Duckett, "Dynamic maps for long-term operation of mobile service robots," in *Proc. Robotics: Science and Systems (RSS) I*, 2005, pp. 17–24.

[95] T. Krajník, J. P. Fentanes, J. P. S. S. Santos, and T. Duckett, "FreMEn: Frequency map enhancement for long-term mobile robot autonomy in changing environments," *IEEE Transactions on Robotics*, vol. 33, no. 4, pp. 964–977, 2017.

[96] L. Schmid, M. Abate, Y. Chang, and L. Carlone, "Khronos: A unified approach for spatio-temporal metric-semantic SLAM in dynamic environments," in *Proc. Robotics: Science and Systems (RSS)*, 2024.

[97] T. Behrens, R. Zurbrügg, M. Pollefeys, Z. Bauer, and H. Blum, "Lost & found: Tracking changes from egocentric observations in 3D dynamic scene graphs," *IEEE Robotics and Automation Letters*, vol. 10, no. 4, pp. 3739–3746, 2025.

[98] Y. Sun and Y. Zhang, "When memory lies: An empirical study of spatial memory staleness in VLM agents," 2026, arXiv preprint.

[99] Z. Chen, Z. Xiang, C. Xiao, D. Song, and B. Li, "AgentPoison: Red-teaming LLM agents via poisoning memory or knowledge bases," in *Advances in Neural Information Processing Systems (NeurIPS)*, 2024.

[100] K. Yadav, Y. Ali, G. Gupta, Y. Gal, and Z. Kira, "FindingDory: A benchmark to evaluate memory in embodied agents," 2025, arXiv preprint.

[101] X. Yin and H. Du, "GLOVE: Global verifier for LLM memory-environment realignment," 2026, arXiv preprint.

[102] G. Tang, Q. Jia, G. Chen, T. Li, Z. Huang, Z. Lv, and N. Ji, "VLM-DEWM: Dynamic external world model for verifiable and resilient vision-language planning in manufacturing," 2026, arXiv preprint.

[103] M. Mostajabdaveh, F. S. Salman, and W. J. Gutjahr, "A branch-and-price algorithm for fast and equitable last-mile relief aid distribution," 2025.

[104] R. van Steenbergen, W. van Heeswijk, and M. Mes, "The stochastic dynamic post-disaster inventory allocation problem with trucks and UAVs," 2023.

[105] K. S. Shehadeh and E. L. Tucker, "Stochastic optimization models for location and inventory prepositioning of disaster relief supplies," 2020.

[106] Y. Rekik, R. Oliva, C. Glock, and A. Syntetos, "Inventory record inaccuracy in grocery retailing: Impact of promotions and product perishability, and targeted effect of audits," 2025.

[107] A. Kapoor, V. Sengar, N. George, V. Vatsal, J. Gubbi, B. P, and A. Pal, "Concept-based anomaly detection in retail stores for automatic correction using mobile robots," 2023.

[108] L. Zhou, Y. Wang, M. Zheng, W. Wang, Z. Wang, and C. Xu, "ShelfChange3D: Object-level 3D change detection for retail shelf monitoring," 2026.

[109] N. Correll, K. E. Bekris, D. Berenson, O. Brock, A. Causo, K. Hauser, K. Okada, A. Rodriguez, J. M. Romano, and P. R. Wurman, "Analysis and observations from the first Amazon picking challenge," 2016.

[110] P. Pacaud, R. Garcia, S. Chen, and C. Schmid, "Guardian: Detecting robotic planning and execution errors with vision-language models," 2025.

[111] A. Aydemir, A. Pronobis, M. Göbelbecker, and P. Jensfelt, "Active visual object search in unknown environments using uncertain semantics," *IEEE Transactions on Robotics*, vol. 29, no. 4, pp. 986–1002, 2013.

[112] Z. Zeng, A. Röfer, and O. C. Jenkins, "Semantic linking maps for active visual object search," in *Proc. IEEE Int. Conf. Robotics and Automation (ICRA)*, 2020, pp. 1984–1990, arXiv:2006.10807.

[113] A. Wandzel, Y. Oh, M. Fishman, N. Kumar, L. L. S. Wong, and S. Tellex, "Multi-object search using object-oriented POMDPs," in *Proc. IEEE Int. Conf. Robotics and Automation (ICRA)*, 2019, pp. 7194–7200.

[114] J. Mason and B. Marthi, "An object-based semantic world model for long-term change detection and semantic querying," in *Proc. IEEE/RSJ Int. Conf. Intelligent Robots and Systems (IROS)*, 2012, pp. 3851–3858.

[115] D. M. Rosen, J. Mason, and J. J. Leonard, "Towards lifelong feature-based mapping in semi-static environments," in *Proc. IEEE Int. Conf. Robotics and Automation (ICRA)*, 2016, pp. 1063–1070.

[116] Z. Yan, S. Li, Z. Wang, L. Wu, H. Wang, J. Zhu, L. Chen, and J. Liu, "Dynamic open-vocabulary 3D scene graphs for long-term language-guided mobile manipulation," *IEEE Robotics and Automation Letters*, vol. 10, no. 5, pp. 4252–4259, 2025, arXiv:2410.11989.

[117] K. Zhou, K. Zheng, C. Pryor, Y. Shen, H. Jin, L. Getoor, and X. E. Wang, "ESC: Exploration with soft commonsense constraints for zero-shot object navigation," in *Proc. 40th Int. Conf. Machine Learning (ICML), PMLR 202*, 2023, pp. 42 829–42 842, arXiv:2301.13166.

[118] N. Yokoyama, S. Ha, D. Batra, J. Wang, and B. Bucher, "VLFM: Vision-language frontier maps for zero-shot semantic navigation," in *Proc. IEEE Int. Conf. Robotics and Automation (ICRA)*, 2024, pp. 42–48, arXiv:2312.03275.

[119] M. Saavedra-Ruiz, S. B. Nashed, C. Gauthier, and L. Paull, "Perpetua: Multi-hypothesis persistence modeling for semi-static environments," 2025.

[120] A. Antoniadis, C. Coester, M. Eliáš, A. Polak, and B. Simon, "Online metric algorithms with untrusted predictions," *ACM Transactions on Algorithms*, vol. 19, no. 2, pp. 1–34, 2023, conference version: ICML 2020, PMLR 119:345–355.

[121] M. Cavorsi, O. E. Akgun, M. Yemini, A. Goldsmith, and S. Gil, "Exploiting trust for resilient hypothesis testing with malicious robots," 2022.

[122] Y. Li, Q. Fang, J. Bai, S. Chen, F. Juefei-Xu, and C. Feng, "Among us: Adversarially robust collaborative perception by consensus," 2023.

[123] R. Wang, H.-L. Hsu, H. Meng, S. Xie, and M. Pajic, "Who to trust in multi-robot systems: Joint robot and object hypothesis trust inference via neural-symbolic cross-validation," 2026.

[124] R. Bajcsy, "Active perception," *Proceedings of the IEEE*, vol. 76, no. 8, pp. 966–1005, 1988.

[125] R. Bajcsy, Y. Aloimonos, and J. K. Tsotsos, "Revisiting active perception," *Autonomous Robots*, vol. 42, no. 2, pp. 177–196, 2018.

[126] W. R. Scott, G. Roth, and J.-F. Rivest, "View planning for automated three-dimensional object reconstruction and inspection," *ACM Computing Surveys*, vol. 35, no. 1, pp. 64–96, 2003.

[127] A. Z. Ren, J. Clark, A. Dixit, M. Itkina, A. Majumdar, and D. Sadigh, "Explore until confident: Efficient exploration for embodied question answering," in *Proc. Robotics: Science and Systems (RSS)*, 2024.

[128] V. Sripada, S. Carter, F. Guerin, and A. Ghalamzan, "Scene exploration by vision-language models," 2024, arXiv preprint.

[129] D. Hendrycks and T. Dietterich, "Benchmarking neural network robustness to common corruptions and perturbations," in *Proc. International Conference on Learning Representations (ICLR)*, 2019.

[130] C. Michaelis, B. Mitzkus, R. Geirhos, E. Rusak, O. Bringmann, A. S. Ecker, M. Bethge, and W. Brendel, "Benchmarking robustness in object

detection: Autonomous driving when winter is coming," 2019, arXiv preprint.

[131] S. Chen, J. Gu, Z. Han, Y. Ma, P. Torr, and V. Tresp, "Benchmarking robustness of adaptation methods on pre-trained vision-language models," in *Advances in Neural Information Processing Systems (NeurIPS), Datasets and Benchmarks Track*, vol. 36, 2023.

[132] M. C. Schiappa, S. Vyas, H. Palangi, Y. S. Rawat, and V. Vineet, "Robustness analysis of video-language models against visual and language perturbations," in *Advances in Neural Information Processing Systems (NeurIPS), Datasets and Benchmarks Track*, vol. 35, 2022.

[133] S. Höfer, K. Bekris, A. Handa, J. C. Gamboa, M. Mozifian, F. Golemo *et al.*, "Sim2Real in robotics and automation: Applications and challenges," *IEEE Transactions on Automation Science and Engineering*, vol. 18, no. 2, pp. 398–400, 2021.

[134] H. Zhang, C. Zhu, X. Wang, Z. Zhou, C. Yin, M. Li, L. Xue, Y. Wang, S. Hu, A. Liu, P. Guo, and L. Y. Zhang, "BadRobot: Jailbreaking embodied LLM agents in the physical world," in *International Conference on Learning Representations (ICLR)*, 2025.

[135] X. Lu, Z. Huang, X. Li, C. Zhang, X. Ji, and W. Xu, "Easier said than done: Unpacking intent-behavior gap in jailbreaking LLM-based robots," 2024, arXiv v1 (2024-12-21) was titled "POEX: Policy Executable Embodied AI Jailbreak Attacks". Latest version accepted by NDSS 2027.

[136] E. K. Jones, A. Robey, A. Zou, Z. Ravichandran, G. J. Pappas, H. Hassani, M. Fredrikson, and J. Z. Kolter, "Adversarial attacks on robotic vision language action models," 2025, preprint.

[137] L. Burbano, D. Ortiz, Q. Sun, S. Yang, H. Tu, C. Xie, Y. Cao, and A. A. Cardenas, "CHAI: Command hijacking against embodied AI," in *IEEE Conference on Secure and Trustworthy Machine Learning (SaTML)*, 2026, accepted; proceedings entry not checked.

[138] S. M. B. P. Samarakoon, M. A. V. J. Muthugala, W. K. R. Sachinthana, and M. R. Elara, "Hijacking robots with a piece of paper: A systematic study of physical prompt injection in VLM-controlled robots," 2026, preprint.

[139] N. Dorzhiev, "RIPA: Sensory-vector prompt injection attacks on LLM-controlled ROS 2 robots," 2026, preprint.

[140] H. Cheng, E. Xiao, J. Gu, L. Yang, J. Duan, J. Zhang, J. Cao, K. Xu, and R. Xu, "Unveiling typographic deceptions: Insights of the typographic vulnerability in large vision-language models," in *European Conference on Computer Vision (ECCV)*, 2024, pp. 179–196.

[141] J. Westerhoff, E. Purelku, J. Hackstein, J. Loos, L. Pinetzki, E. Rodner, and L. Hufe, "SCAM: A real-world typographic robustness evaluation for multimodal foundation models," 2025.

[142] C. Ling, K. Hu, H. Liu, X. Han, T. Zhang, and C. Ou, "Physical prompt injection attacks on large vision-language models," 2026.

[143] K. Greshake, S. Abdelnabi, S. Mishra, C. Endres, T. Holz, and M. Fritz, "Not what you've signed up for: Compromising real-world LLM-integrated applications with indirect prompt injection," in *Proceedings of the 16th ACM Workshop on Artificial Intelligence and Security (AISec)*, 2023, pp. 79–90.

[144] W. Zhang, X. Kong, C. Dewitt, T. Braunl, and J. B. Hong, "A study on prompt injection attack against LLM-integrated mobile robotic systems," 2024.

[145] S. Dong, S. Xu, P. He, Y. Li, J. Tang, T. Liu, H. Liu, and Z. Xiang, "Memory injection attacks on LLM agents via query-only interaction," in *Advances in Neural Information Processing Systems (NeurIPS)*, 2025.

[146] S. S. Srivastava and H. He, "MemoryGraft: Persistent compromise of LLM agents via poisoned experience retrieval," 2025.

[147] P. Dash, T. Ge, A. Jain, T. Shah, and Z. Shang, "From untrusted input to trusted memory: A systematic study of memory poisoning attacks in LLM agents," 2026.

[148] J. Liu, J. Guo, T. Zhang, Y. Xu, J. Wang, J. Fan, and B. Xiao, "Security of foundation-model-powered embodied agents: Attack surfaces, attacks, defenses, and evaluation," 2026, survey, preprint.

[149] E. Debenedetti, I. Shumailov, T. Fan, J. Hayes, N. Carlini, D. Fabian, C. Kern, C. Shi, A. Terzis, and F. Tramèr, "Defeating prompt injections by design," 2025, preprint.

[150] M. Costa, B. Köpf, A. Kolluri, A. Paverd, M. Russinovich, A. Salem, S. Tople, L. Wutschitz, and S. Zanella-Béguelin, "Securing AI agents with information-flow control," 2025, preprint.

[151] A. Avižienis, "The N-version approach to fault-tolerant software," *IEEE Transactions on Software Engineering*, vol. SE-11, no. 12, pp. 1491–1501, 1985.

[152] J. C. Knight and N. G. Leveson, "An experimental evaluation of the assumption of independence in multiversion programming," *IEEE Transactions on Software Engineering*, vol. SE-12, no. 1, pp. 96–109, 1986.

[153] Y. Du, S. Li, A. Torralba, J. B. Tenenbaum, and I. Mordatch, "Improving factuality and reasoning in language models through multiagent debate," in *Proc. International Conference on Machine Learning (ICML)*, ser. Proceedings of Machine Learning Research, vol. 235. PMLR, 2024, pp. 11 733–11 763.

[154] H. Kress-Gazit, K. Hashimoto, N. Kuppuswamy, P. Shah *et al.*, "Robot learning as an empirical science: Best practices for policy evaluation," 2024. [Online]. Available: https://arxiv.org/abs/2409.09491

[155] E. B. Wilson, "Probable inference, the law of succession, and statistical inference," *Journal of the American Statistical Association*, vol. 22, no. 158, pp. 209–212, 1927. [Online]. Available: https://doi.org/10.1080/01621459.1927.10502953

[156] Q. McNemar, "Note on the sampling error of the difference between correlated proportions or percentages," *Psychometrika*, vol. 12, no. 2, pp. 153–157, 1947. [Online]. Available: https://doi.org/10.1007/BF02295996

[157] J. Tobin, R. Fong, A. Ray, J. Schneider *et al.*, "Domain randomization for transferring deep neural networks from simulation to the real world," in *IEEE/RSJ International Conference on Intelligent Robots and Systems (IROS)*, 2017, pp. 23–30. [Online]. Available: https://doi.org/10.1109/IROS.2017.8202133

[158] D. Snyder, A. J. Hancock, A. Badithela, E. Dixon, P. Miller, R. A. Ambrus, A. Majumdar, M. Itkina, and H. Nishimura, "Is your imitation learning policy better than mine? policy comparison with near-optimal stopping," in *Robotics: Science and Systems XXI (RSS)*, 2025.

[159] X. Li, K. Hsu, J. Gu, K. Pertsch, O. Mees *et al.*, "Evaluating real-world robot manipulation policies in simulation," in *Proceedings of The 8th Conference on Robot Learning (CoRL)*, ser. Proceedings of Machine Learning Research, vol. 270. PMLR, 2024, pp. 3705–3728, coRL 2024 (PMLR volume dated 2025); method name: SIMPLER.

[160] P. V. A. B. Venâncio, A. C. Lisboa, and A. V. Barbosa, "An automatic fire detection system based on deep convolutional neural networks for low-power, resource-constrained devices," *Neural Computing and Applications*, vol. 34, no. 18, pp. 15 349–15 368, 2022.

[161] M. Wang, P. Yue, L. Jiang, D. Yu, T. Tuo, and J. Li, "An open flame and smoke detection dataset for deep learning in remote sensing based fire detection," *Geo-spatial Information Science*, vol. 28, no. 2, pp. 511–526, 2025.

[162] L. Seidel, S. Gehringer, T. Raczok, S.-N. Ivens, B. Eckardt, and M. Maerz, "Advancing early wildfire detection: Integration of vision language models with unmanned aerial vehicle remote sensing for enhanced situational awareness," *Drones*, vol. 9, no. 5, p. 347, 2025.

[163] P. Li, N. Suryanto, S. Zhang, M. Alsharid, and M. Naseer, "SAFIRE: Safety-critical benchmark for fine-grained fire and smoke understanding in multimodal LLMs," 2026.

[164] Z. Navasardyan, T. Danielyan, and H. Davtyan, "FailBench: How reliable are VLMs at judging robot task success?" 2026.

[165] S. Chepuri and V. Srivastava, "AuthGuard-R: Safety-compliant mission hijacking and dual-gate defense for LLM-controlled robots," 2026, preprint, submitted 25 September 2026.

[166] Z. Huang, Z. Liu, W. Shi, Y. Yang, W. Wu, and Z. Cai, "When coordination becomes a threat: Communication attacks in LLM-controlled multi-robot systems," 2026, preprint, submitted 7 August 2026.

[167] J. Steinberg and O. Gal, "Semantic denial of service in LLM-controlled robots," 2026, preprint, submitted 25 April 2026.

[168] P. T. Tran-Truong, H. Vo, N. Tran, K. Vo, and T.-M. Truong, "DelegateGuard: Purpose-bound capabilities for delegated LLM agent workflows," 2026, preprint, submitted 12 October 2026.

[169] A. Kravchenko, V. Liventsev, I. Konstantinov, I. Iskhakov, and M. Kukuy, "APPA: Recoverable information-flow control for real-world LLM agents," 2026, preprint, submitted 27 July 2026 (v2 26 August 2026).

[170] N. Palumbo, S. Choudhary, J. Choi, G. Amir, P. Chalasani, I. Dillig, and S. Jha, "Formal policy enforcement for agentic systems," 2026, preprint, v1 18 February 2026, v4 12 October 2026; v1 title read "Formal Policy Enforcement for Real-World Agentic Systems" in a search listing.

[171] S. Ray, "What can be enforced? A theory of certified runtime safety for tool-using agents," 2026, preprint, submitted 24 July 2026.

[172] Z. Zhou, Z. Li, X. Chen, J. Li, C. Wang, H. Chen, and X. Zhu, "Think only when needed: Prompt-authority control for selective slow-path intervention in vision-language-action manipulation," 2026, preprint, submitted 24 August 2026; method name TOWN-VLA.

[173] M. Akewar and R. Ranjan, "SafeCommit: Certifying when memory-grounded agents may safely act," 2026, preprint, submitted 4 August 2026.

[174] Y. Louck, "Securing LLM-agent long-term memory against poisoning: Non-malleable, origin-bound authority with machine-checked guarantees," 2026, preprint.

[175] M. Williams, H. Sheahan, C. Raymond, T. Korbak, D. Pan, P. Yang, L. Maksin, N. Xie, P. Guo, I. Kivlichan, and M. Carroll, "Predicting LLM safety before release by simulating deployment," 2026, preprint, submitted 8 July 2026.

[176] Z. Zheng, B. Li, J. Yao, and J. Long, "Engineering reliable commit gates for agentic AI: Cost-aware verification portfolios under common-mode data failures," 2026, preprint, submitted 10 September 2026.

[177] Z. Ravichandran, D. Snyder, A. Robey *et al.*, "Contextual safety reasoning and grounding for open-world robots," 2026.

[178] W. Scarbro, C. Imrie, S. Getir Yaman, K. Fatehi, C. S. Pasareanu, R. Calinescu, and R. Mangal, "Conformal safety shielding for imperfect-perception agents," 2025.

[179] Q. Zhou, S. Chen, Y. Wang, H. Xu, W. Du, H. Zhang, Y. Du, J. B. Tenenbaum, and C. Gan, "HAZARD challenge: Embodied decision making in dynamically changing environments," 2024.

[180] D. Zhang, P. Chen, J. Zhou, and S. Yang, "ESARBench: A benchmark for agentic UAV embodied search and rescue," 2026.

[181] S. Yin, X. Pang, Y. Ding, M. Chen, Y. Bi, Y. Xiong, W. Huang, Z. Xiang, J. Shao, and S. Chen, "SafeAgentBench: A benchmark for safe task planning of embodied LLM agents," 2024.

[182] J. Han, J. Seo, J. Min, S. Choi, H. Seo, J. Kim, and J. Oh, "Before we trust them: Decision-making failures in navigation of foundation models," 2026.

[183] S. Panpatil, A. Singh, M. Koo, C. Kim, H. Park, and D. Choi, "EgoSafetyBench: A diagnostic egocentric video benchmark for evaluating embodied VLMs as runtime safety guards," 2026.

[184] X. Zhai, B. Mustafa, A. Kolesnikov, and L. Beyer, "Sigmoid loss for language image pre-training," in *Proc. IEEE/CVF International Conference on Computer Vision (ICCV)*, 2023, pp. 11 975–11 986.

[185] A. Radford, J. W. Kim, C. Hallacy, A. Ramesh, G. Goh, S. Agarwal, G. Sastry, A. Askell, P. Mishkin, J. Clark, G. Krueger, and I. Sutskever, "Learning transferable visual models from natural language supervision," in *Proc. International Conference on Machine Learning (ICML)*, ser. PMLR, vol. 139, 2021, pp. 8748–8763.

[186] J. Yuan, H. Li, X. Ding, W. Xie, Y.-J. Li, W. Zhao, K. Wan, J. Shi, X. Hu, and Z. Liu, "Understanding and mitigating numerical sources of nondeterminism in LLM inference," 2025.

[187] B. Atil *et al.*, "Non-determinism of "deterministic LLM settings," 2024.

[188] L. Chen, M. Zaharia, and J. Zou, "How is ChatGPT's behavior changing over time?" 2023.

[189] A. Afzal, C. Le Goues, and C. S. Timperley, "GzScenic: Automatic scene generation for Gazebo simulator," 2021.

[190] C. Frost, C. Council, M. McGuinness, and N. Hanson, "RubbleSim: A photorealistic structural collapse simulator for confined space mapping," 2025.

[191] B. Alt, M. Picklum, S. Arion, F. Kenghagho Kenfack, and M. Beetz, "Open, reproducible and trustworthy robot-based experiments with virtual labs and digital-twin-based execution tracing," 2025.

[192] R. Royce, M. Kaufmann, J. Becktor, S. Moon, K. Carpenter, K. Pak, A. Towler, R. Thakker, and S. Khattak, "Enabling novel mission operations and interactions with ROSA: The robot operating system agent," 2024.

[193] Z. Hu, F. Lucchetti, C. Schlesinger, Y. Saxena, A. Freeman, S. Modak, A. Guha, and J. Biswas, "Deploying and evaluating LLMs to program service mobile robots," 2023.

[194] S. Shaji, F. Huppertz, A. Mitrevski, and S. Houben, "From language to action: Can LLM-based agents be used for embodied robot cognition?" 2026.

[195] Z. Ravichandran, F. Cladera, J. Hughes, V. Murali, M. A. Hsieh, G. J. Pappas, C. J. Taylor, and V. Kumar, "Deploying foundation model-enabled air and ground robots in the field: Challenges and opportunities," 2025.

[196] S. Ahmad, M. Hafeez, and S. A. R. Zaidi, "Vision-language models on the edge for real-time robotic perception," 2026.

[197] A. R. Wagner, M. B. Rao, H. Wrede, S. Pirk, and X. Xiao, "Fire as a service: Augmenting robot simulators with thermally and visually accurate fire dynamics," 2026.

[198] A. R. Wagner, M. B. Rao, X. Xiao, and S. Pirk, "Understanding fire through thermal radiation fields for mobile robots," 2026.

[199] C. X. Lu, S. Rosa, P. Zhao, B. Wang, C. Chen, J. A. Stankovic, N. Trigoni, and A. Markham, "See through smoke: Robust indoor mapping with low-cost mmWave radar," 2019.

[200] E. Shaklab, A. Karapetyan, A. Sharma, M. Mebrahtu, M. Basri, M. Nagy, M. Khonji, and J. Dias, "Towards autonomous and safe last-mile deliveries with AI-augmented self-driving delivery robots," 2023.

[201] F. Alshammari, Y. Luo, and Q. A. Chen, "On the cyber-physical security of commercial indoor delivery robot systems," 2024.

[202] J. R. Douceur, "The sybil attack," in *Peer-to-Peer Systems (IPTPS 2002)*, ser. LNCS, vol. 2429. Springer, 2002, pp. 251–260.

[203] E. J. Friedman and P. Resnick, "The social cost of cheap pseudonyms," *Journal of Economics & Management Strategy*, vol. 10, no. 2, pp. 173–199, 2001.

[204] R. L. Cruz, "A calculus for network delay, Part I: Network elements in isolation," *IEEE Transactions on Information Theory*, vol. 37, pp. 114–131, 1991.

[205] T. Lykouris and S. Vassilvitskii, "Competitive caching with machine learned advice," *Journal of the ACM*, vol. 68, no. 4, pp. 1–25, 2021, conference version: ICML 2018. arXiv:1802.05399.

[206] P. Chen, H. Zhao, X. Tang, Y. Wang, and S. Deng, "Towards optimal robustness in learning-augmented paging," *arXiv preprint arXiv:2606.01342*, 2026.

[207] K. Anand, R. Ge, A. Kumar, and D. Panigrahi, "Online algorithms with multiple predictions," in *Proceedings of the 39th International Conference on Machine Learning*, ser. Proceedings of Machine Learning Research, vol. 162, 2022, pp. 582–598. [Online]. Available: https://proceedings.mlr.press/v162/anand22a.html

[208] A. Antoniadis, C. Coester, M. Eliáš, A. Polak, and B. Simon, "Mixing predictions for online metric algorithms," arXiv:2304.01781, 2023.

[209] A. Wei and F. Zhang, "Optimal robustness-consistency trade-offs for learning-augmented online algorithms," in *Advances in Neural Information Processing Systems 33 (NeurIPS)*, 2020, arXiv:2010.11443.

[210] S. Angelopoulos, C. Dürr, S. Jin, S. Kamali, and M. Renault, "Online computation with untrusted advice," in *11th Innovations in Theoretical Computer Science Conference (ITCS)*, ser. LIPIcs, 2020, arXiv:1905.05655.

[211] Q. Zhang, Z. Xiong, and Z. M. Mao, "LLM safeguard is a double-edged sword: Exploiting false positives for denial-of-service attacks," *arXiv preprint arXiv:2410.02916*, 2024.

[212] Y. Wu, R. Shariff, T. Lattimore, and C. Szepesvári, "Conservative bandits," in *Proceedings of the 33rd International Conference on Machine Learning*, ser. Proceedings of Machine Learning Research, vol. 48, 2016, pp. 1254–1262. [Online]. Available: https://proceedings.mlr.press/v48/wu16.html

[213] D. P. Foster and R. A. Stine, "α-investing: a procedure for sequential control of expected false discoveries," *Journal of the Royal Statistical Society: Series B (Statistical Methodology)*, vol. 70, no. 2, pp. 429–444, 2008.

[214] F. Mallmann-Trenn, M. Cavorsi, and S. Gil, "Crowd vetting: Rejecting adversaries via collaboration with application to multirobot flocking," *IEEE Transactions on Robotics*, vol. 38, pp. 5–24, 2022.

[215] S. Ren, W. Fu, X. Zou, C. Shen, Y. Cai, C. Chu, Z. Wang, and S. Hu, "Reputation as a solution to cooperation collapse in LLM-based MASs," in *Proceedings of the 25th International Conference on Autonomous Agents and Multiagent Systems (AAMAS)*, 2026, arXiv:2505.05029.

[216] Cloudflare, "Clef-Flash model card," Hugging Face model repository, 2026. [Online]. Available: https://huggingface.co/Cloudflare/clef-flash

[217] M. Chen, "Introducing Clef: Our open-source decision models, and new RL fine-tuning platform," Cloudflare Blog, Oct. 2026. [Online]. Available: https://blog.cloudflare.com/clef-decision-models

[218] Z. Bugaud, "Hidden clones: Exposing and fixing family bias in vision-language model ensembles," 2026.

[219] G. Kohli, "Nine judges, two effective votes: Correlated errors undermine LLM evaluation panels," 2026.

[220] E. Kim, A. Garg, K. Peng, and N. Garg, "Correlated errors in large language models," 2025.

[221] R. J. Tibshirani, R. F. Barber, E. J. Candès, and A. Ramdas, "Conformal prediction under covariate shift," 2019.

[222] R. F. Barber, E. J. Candès, A. Ramdas, and R. J. Tibshirani, "Conformal prediction beyond exchangeability," 2022.

[223] J. Silva-Rodríguez, I. Ben Ayed, and J. Dolz, "Conformal prediction for zero-shot models," 2025.

[224] K.-R. Kladny, B. Schölkopf, L. Koch, C. F. Baumgartner, and M. Muehlebach, "A critical perspective on finite sample conformal prediction theory in medical applications," 2025.

[225] B. Kumar, C. Lu, G. Gupta, A. Palepu, D. Bellamy, R. Raskar, and A. Beam, "Conformal prediction with large language models for multi-choice question answering," 2023.

[226] T. Yu, T. Xiao, A. Stone, J. Tompson, A. Brohan, S. Wang, J. Singh, C. Tan, J. Peralta, B. Ichter, K. Hausman, and F. Xia, "Scaling robot learning with semantically imagined experience," 2023, preprint, submitted 22 February 2023; method name: ROSIE.

[227] H. Abu Alhaija *et al.*, "Cosmos-Transfer1: Conditional world generation with adaptive multimodal control," 2025, preprint, submitted 18 March 2025.

[228] C. V. Samak, T. V. Samak, B. Li, and V. Krovi, "Sim2Real diffusion: Leveraging foundation vision language models for adaptive automated driving," 2025, preprint, submitted 30 June 2025.

[229] E. Benarous, Y. Du, and H. Yang, "SPIE: Semantic and structural post-training of image editing diffusion models with AI feedback," 2025, preprint, submitted 17 April 2025.

[230] S. Gaba, "Generative AI for enhanced wildfire detection: Bridging the synthetic-real domain gap," 2025, preprint, submitted 2 September 2025.

[231] A. Helbling, S. Palaskar, K. Krishna, P. Chau, L. Gatys, and J. Y. Cheng, "SafetyPairs: Isolating safety critical image features with counterfactual image generation," 2025.

[232] S. Fei, S. Wang, J. Shi, Z. Dai, J. Cai, P. Qian *et al.*, "LIBERO-Plus: In-depth robustness analysis of vision-language-action models," 2025.

[233] V. Prabhu, S. Yenamandra, P. Chattopadhyay, and J. Hoffman, "LANCE: Stress-testing visual models by generating language-guided counterfactual images," 2023.

[234] Q. Wang, Y. Lin, Y. Chen, L. Schmidt, B. Han, and T. Zhang, "A sober look at the robustness of CLIPs to spurious features," 2024.

[235] R. Saxena, A. Suglia, and P. Minervini, "VLM-RobustBench: A comprehensive benchmark for robustness of vision-language models," 2026.

[236] H. L. Patel, A. Agarwal, S. Panda *et al.*, "PCRI: Measuring context robustness in multimodal models for enterprise applications," 2025.

[237] M. Usama, S. A. Asim, S. B. Ali *et al.*, "Analysing the robustness of vision-language-models to common corruptions," 2025.

[238] A. Tiwari, F. Masoud, D. T. Nguyen *et al.*, "Fire360: A benchmark for robust perception and episodic memory in degraded 360-degree firefighting videos," 2025.

[239] L. Chen, M. Zaharia, and J. Zou, "FrugalGPT: How to use large language models while reducing cost and improving performance," 2023.

[240] M. J. Zellinger, R. Liu, and M. Thomson, "Cost-saving LLM cascades with early abstention," 2025.

[241] S. Jain, U. Z. Ahmed, S. Sahai, and B. Leong, "Beyond consensus: Mitigating the agreeableness bias in LLM judge evaluations," 2025.

[242] D. Shanmugam, D. Blalock, G. Balakrishnan, and J. Guttag, "Better aggregation in test-time augmentation," 2020.

[243] P. H. J. Nardelli, I. Ramezanipour, H. Alves, C. H. M. de Lima, and M. Latva-aho, "Average error probability in wireless sensor networks with imperfect sensing and communication for different decision rules," 2015.

[244] H. He, J. Zhang, G. Tian, C. Wang, and L. Xie, "Learning multi-view anomaly detection with efficient adaptive selection," 2024.

[245] Y. He, "Detector confidence signals presence rather than occlusion in cluttered manipulation," 2026, preprint.

[246] S. S. McDonnell, A. Singh, Q.-V. Pham, V. Havlik, and G. M. P. O'Hare, "Harnessing disagreement: Detecting correlated agreement blindness in multi-agent triage," 2026.

[247] S. Onohara, A. Miyai, Y. Imajuku, K. Egashira, J. Baek, X. Yue, G. Neubig, and K. Aizawa, "JMMMU: A Japanese massive multi-discipline multimodal understanding benchmark for culture-aware evaluation," 2024.

[248] Y. Inoue, K. Sasaki, Y. Ochi, K. Fujii, K. Tanahashi, and Y. Yamaguchi, "Heron-Bench: A benchmark for evaluating vision language models in Japanese," 2024.

[249] A. Gupta, M. Mehta, Z. Xu, and V. Srikumar, "Found in translation: Measuring multilingual LLM consistency as simple as translate then evaluate," 2025.

[250] A. K. Srivastava and P. Dames, "Speech-guided sequential planning for autonomous navigation using large language model meta AI 3 (Llama3)," 2024.

[251] S. Jia and O. Lemon, "When robots mishear us: Mapping the safety risks of voice-controlled embodied AI," 2026.

[252] B. Wang, C. Wei, Z. Liu, G. Lin, and N. F. Chen, "Resilience of large language models for noisy instructions," 2024.

[253] L. Nwankwo, B. Ellensohn, O. Özdenizci *et al.*, "ReLI: Cross-lingual language-to-action grounding for human-robot interaction," 2025.

[254] S. Karita, R. Sproat, and H. Ishikawa, "Lenient evaluation of Japanese speech recognition: Modeling naturally occurring spelling inconsistency," 2023.

[255] I. Sugiura, K. Maeda, S. Kurita *et al.*, "JAMMEval: A refined collection of Japanese benchmarks for reliable VLM evaluation," 2026.

[256] T. Chiba, G. Sun, Z. Yuan *et al.*, "Talk2Agent: Benchmarking voice interfaces for text agents," 2026.

[257] S. Nowrin and K. Vertanen, "Using confidence scores to improve eyes-free detection of speech recognition errors," 2024.

[258] Q. Deng, M. Zhang, Y. Yang, and Z. Gao, "SCOPE: A lightweight-training LLM framework for air traffic control readback monitoring," 2026.

[259] A. B. Haynes, T. G. Weiser, W. R. Berry, S. R. Lipsitz, A.-H. S. Breizat, E. P. Dellinger, T. Herbosa, S. Joseph, P. L. Kibatala, M. C. M. Lapitan, A. F. Merry, K. Moorthy, R. K. Reznick, B. Taylor, and A. A. Gawande, "A surgical safety checklist to reduce morbidity and mortality in a global population," *New England Journal of Medicine*, vol. 360, no. 5, pp. 491–499, 2009.

[260] Z. Buçinca, M. B. Malaya, and K. Z. Gajos, "To trust or to think: Cognitive forcing functions can reduce overreliance on AI in AI-assisted decision-making," 2021.

[261] J. Zhou, A. Roy, S. Gupta, D. Weitekamp, and C. J. MacLellan, "When should users check? Modeling confirmation frequency in multi-step agentic AI tasks," 2025.

[262] P. Kirichenko, M. Ibrahim, K. Chaudhuri, and S. J. Bell, "AbstentionBench: Reasoning LLMs fail on unanswerable questions," 2025.

[263] B. J. Wagner, "Two axes of LLM abstention: Answer correctness and question answerability," 2026.

[264] M. J. Lavi, T. Milo, and M. Geva, "Detecting (un)answerability in large language models with linear directions," 2025.

[265] L. Cheng, M. Cai, J. Jiang, and L. Mai, "Do agents know what they can't do? evaluating feasibility awareness in tool-using agents," 2026.

[266] H.-T. Su, T.-J. Wang, J.-F. Yeh, M. Sun, and W. H. Hsu, "VLN-NF: Feasibility-aware vision-and-language navigation with false-premise instructions," 2026.

[267] J. Park, S. Lim, J. Lee, S. Park, M. Chang, Y. Yu, and S. Choi, "CLARA: Classifying and disambiguating user commands for reliable interactive robotic agents," 2023.

[268] Ł. Sobczak, N. Keleşoğlu, and S. P. Nowak, "Risk-aware semantic grounding for trustworthy LLM-based robot planning," 2026.

[269] X. Huo, R. Gnanasambandam, and X. Zhang, "Precise robot command understanding using grammar-constrained large language models," 2026.

[270] B. Hu, C. Chang, J. Ge, M. Namgung, X. Lin, A. Krieger, and T. Mohsenin, "OA-NBV: Occlusion-aware next-best-view planning for human-centered active perception on mobile robots," 2026, preprint.

[271] M. P. Podolinsky, N. P. Bhatt, P. Samineni, R. Siva, C. Ellis, and U. Topcu, "Co-GLANCE: Uncertainty-aware active perception for heterogeneous robot teaming," 2026.

[272] G. Liu, W. Jiang, B. Lei, V. Pandey, K. Daniilidis, and N. Motee, "Beyond uncertainty: Risk-aware active view acquisition for safe robot navigation and 3D scene understanding with FisherRF," 2024.

[273] A. Mollaei Khass, G. Liu, V. Pandey, W. Jiang, B. Lei, K. Daniilidis, and N. Motee, "Active next-best-view optimization for risk-averse path planning," 2025.

[274] A. Mollaei Khass, A. Cosse, and N. Motee, "Splat-CBF: Safe next-best-view control in 3D Gaussian-splat maps," 2026.

[275] S. Liang, X. Liao, and S. Zhang, "ZONDA: Zero-shot object navigation with dynamic avoidance in multi-floor environments," 2026.

[276] H. Wang, H. Li, W. Chen, and X. Zhang, "ViCrop-Det: Spatial attention entropy guided cropping for training-free small-object detection," 2026.

[277] H. Shen, K. Zhao, T. Zhao, R. Xu, Z. Zhang, M. Zhu, and J. Yin, "ZoomEye: Enhancing multimodal LLMs with human-like zooming capabilities through tree-based image exploration," 2024.

[278] Y. Zhang, Z. Wang, H. Lin, Y. Bitton, I. Szpektor, and M. Bansal, "Seeing isn't knowing: Do VLMs know when not to answer spatial questions (and why)?" 2026.

[279] W. Park, I. Lee, S. Kim, J. Jang, M. Noh, K. Shim, and B. Shim, "Revealing multi-view hallucination in large vision-language models," 2026.

[280] P. Zheng and H. Kurban, "It's the decoding format, not the perturbation: Auditing consistency-based selection for vision-language test-time scaling," 2026.

[281] A. Slobodkin, O. Goldman, A. Caciularu, I. Dagan, and S. Ravfogel, "The curious case of hallucinatory (un)answerability: Finding truths in the hidden states of over-confident large language models," 2023.

[282] A. Azaria and T. Mitchell, "The internal state of an LLM knows when it's lying," 2023.

[283] S. Marks and M. Tegmark, "The geometry of truth: Emergent linear structure in large language model representations of true/false datasets," 2023.

[284] H. Orgad, M. Toker, Z. Gekhman, R. Reichart, I. Szpektor, H. Kotek, and Y. Belinkov, "LLMs know more than they show: On the intrinsic representation of LLM hallucinations," 2024.

[285] W. Azizian, M. Kirchhof, E. Ndiaye, L. Bethune, M. Klein, P. Ablin, and M. Cuturi, "The geometries of truth are orthogonal across tasks," 2025.

[286] C. S. Cheang, H. P. Chan, W. Zhang, and Y. Deng, "Do LLMs really know what they don't know? Internal states mainly reflect knowledge recall rather than truthfulness," 2025.

[287] J. Zhang, J. Hu, M. Khayatkhoei, F. Ilievski, and M. Sun, "Exploring perceptual limitation of multimodal large language models," 2024.

[288] L. Li, L. Sleem, N. Gentile, Y. Xu, Y. Song, W. Wu, and R. State, "The last visible pixel: Probing fine-scale perception in vision-language models," 2026.

[289] Z. Liu, K. Gao, S. Liang, B. Xiao, L. Qiao, L. Ma, and T. Jiang, "Beyond the visible: Benchmarking occlusion perception in multimodal large language models," 2025.

[290] Z. Feng *et al.*, "Seeing across views: Benchmarking spatial reasoning of vision-language models in robotic scenes," 2025.

[291] M. Michalkiewicz, S. Bai, M. Baktashmotlagh, V. Jampani, and G. Balakrishnan, "Not all views are created equal: Analyzing viewpoint instabilities in vision foundation models," 2024.

[292] K. Lee, J. Hong, S. Lee, I. Lee, M. Kwak, K. Ryu, and J. Park, "SpatialMosaic: A multiview VLM dataset for partial visibility," 2025.

[293] Z. Wang *et al.*, "ActiView: Evaluating active perception ability for multimodal large language models," 2024.

[294] J. Yao, H. Wen, S. Gao, Y. Guo, Z. Liu, and H. Huang, "HomeSafeBench: Benchmarking embodied vision-language models in free-exploration home safety inspection," 2025.

[295] A. Blum and M. Hardt, "The ladder: A reliable leaderboard for machine learning competitions," 2015.

[296] J. F. Mandujano Reyes, "Statistical methods for multiple language model comparison on a shared evaluation," 2026.

[297] A. Søgaard, D. Hershcovich, and M. de Lhoneux, "A two-sided discussion of preregistration of NLP research," 2023.

[298] R. Luo, S. Zhao, J. Kuck, B. Ivanovic, S. Savarese, E. Schmerling, and M. Pavone, "Sample-efficient safety assurances using conformal prediction," 2021.

[299] A. Badithela, D. Snyder, L. Zha, J. Mikhail, M. O'Kelly, A. Dixit, and A. Majumdar, "Reliable and scalable robot policy evaluation with imperfect simulators," 2025.

[300] M. H. Amini, S. Naseri, and S. Nejati, "Evaluating the impact of flaky simulators on testing autonomous driving systems," 2023.

[301] A. Afzal, D. S. Katz, C. Le Goues, and C. S. Timperley, "A study on the challenges of using robotics simulators for testing," 2020.

[302] R. Agarwal, M. Schwarzer, P. S. Castro, A. Courville, and M. G. Bellemare, "Deep reinforcement learning at the edge of the statistical precipice," 2021.

[303] J. A. Vincent, H. Nishimura, M. Itkina, P. Shah, M. Schwager, and T. Kollar, "How generalizable is my behavior cloning policy? A statistical approach to trustworthy performance evaluation," 2024.

[304] D. Snyder, A. Badithela, N. Matni, G. Pappas, A. Majumdar, M. Itkina, and H. Nishimura, "Beyond binary success: Sample-efficient and statistically rigorous robot policy comparison," 2026.

[305] G. Leech, J. J. Vazquez, N. Kupper, M. Yagudin, and L. Aitchison, "Questionable practices in machine learning," 2024.

[306] X. Bouthillier *et al.*, "Accounting for variance in machine learning benchmarks," 2021.

[307] F. Karl, L. M. Kemeter, G. Dax, and P. Sierak, "Position: Embracing negative results in machine learning," 2024.

[308] M. Vaccaro, "Preregistration for experiments with AI agents," 2026.

[309] X. Zhao, V. Robu, D. Flynn, K. Salako, and L. Strigini, "Assessing the safety and reliability of autonomous vehicles from road testing," 2019.

[310] P. Bishop, A. Povyakalo, and L. Strigini, "Bootstrapping confidence in future safety based on past safe operation," 2021.

[311] X. Zhao, R. Aghazadeh-Chakherlou, C.-H. Cheng, P. Popov, and L. Strigini, "On the need for a statistical foundation in scenario-based testing of autonomous vehicles," 2025.

[312] M. O'Kelly, A. Sinha, H. Namkoong, J. Duchi, and R. Tedrake, "Scalable end-to-end autonomous vehicle testing via rare-event simulation," 2018.

[313] S. Casas and C. Fidler, "TOPO: Time-ordered provable outputs," 2024.

[314] A. Axelsson, M. Reimann, R. Cumbal, H. Pelikan, and D. Lala, "Why report failed interactions with robots?! Towards vignette-based interaction quality," 2025.

[315] H. Kaindl and S. Kramer, "Towards probability-based safety verification of systems with components from machine learning," 2020.

[316] A. J. Lohn, "Estimating the brittleness of AI: Safety integrity levels and the need for testing out-of-distribution performance," 2020.

[317] T. Waite, Y. Geng, T. Turnquist, I. Ruchkin, and R. Ivanov, "State-dependent conformal perception bounds for neuro-symbolic verification of autonomous systems," 2025.

[318] W. Scarbro and R. Mangal, "Interval POMDP shielding for imperfect-perception agents," 2026.

[319] M. Cleaveland, P. Lu, O. Sokolsky *et al.*, "Conservative perception models for probabilistic verification," 2025.

[320] D. Corsi, K. Kim, and R. Fox, "Verifiable foundation models for robot safety," 2026.

[321] D. Jackson, V. Richmond, M. Wang *et al.*, "Certified control: An architecture for verifiable safety of autonomous vehicles," 2021.

[322] R. Hawkins, C. Paterson, C. Picardi, Y. Jia, R. Calinescu, and I. Habli, "Guidance on the assurance of machine learning in autonomous systems (AMLAS)," 2021.

[323] U. Gohar, M. C. Hunter, S. Purandare *et al.*, "Defeater cards: Characterizing and managing safety assurance case defeaters," 2026.

[324] K. Tian, E. Mitchell, A. Zhou *et al.*, "Just ask for calibration: Strategies for eliciting calibrated confidence scores from language models fine-tuned with human feedback," 2023.

[325] M. Atabuzzaman, A. Asgarov, and C. Thomas, "Benchmarking and mitigating MCQA selection bias of large vision-language models," 2025.

[326] S. H. Dumpala, A. Jaiswal, C. Sastry *et al.*, "Sensitivity of generative VLMs to semantically and lexically altered prompts," 2024.

[327] Z. Lin, D. Pathak, B. Li *et al.*, "Evaluating text-to-visual generation with image-to-text generation," 2024.

[328] G. Recchia, C. S. Mangat, J. Nyachhyon *et al.*, "Confirmation bias: A challenge for scalable oversight," 2025.

[329] M. C. Horowitz and L. Kahn, "Bending the automation bias curve: A study of human and AI-based decision making in national security contexts," 2023.

[330] E. Turan, "Oversight has a capacity: Calibrating agent guards to a subjective, fatiguing human," 2026.

[331] Y. Geifman and R. El-Yaniv, "Selective classification for deep neural networks," in *Advances in Neural Information Processing Systems (NIPS)*, vol. 30, 2017. [Online]. Available: https://papers.nips.cc/paper_files/paper/2017/hash/4a8423d5e91fda00bb7e46540e2b0cf1-Abstract.html

TABLE S8

CAMPAIGN H, ALL PAIRED MISSIONS (SEQ = SEQUENCE.MISSION). OUTCOME AND MISSION TIME: ✓ DELIVERED, NO UNSAFE DELIVERY; × UNSAFE DELIVERY; ○ REFUSED WHERE NO SAFE OPTION EXISTED; △ REFUSED ALTHOUGH A SAFE OPTION EXISTED (FALSE REFUSAL); NO MISSION FAILED. TRANSITION: WHAT CHANGED SINCE THE PREVIOUS MISSION. STORIES (MISSIONS 1→2→3): S1 NOMINAL, SWAPPED, SWAPPED; S2 SWAPPED, SWAPPED, NOMINAL; S3 NO FIRE, FIRE BEHIND THE REQUESTED STATION, FIRE; S4 FIRE, NO FIRE, FIRE. M2 SOURCE: FIRST STATION TAKEN FROM MEMORY AND/OR CAUTION APPLIED TO A STATION.

Seq	Story	Transition	M0	M1	M2	M2 source
Q01.2	S3	fire appears	○ (62 s)	× (41 s)	○ (45 s)	memory
Q01.3	S3	fire persists	○ (30 s)	× (41 s)	○ (30 s)	memory+caution
Q02.2	S2	relocation persist	✓(112 s)	✓(28 s)	✓(72 s)	memory
Q02.3	S2	relocation change	✓(85 s)	× (28 s)	✓(114 s)	memory
Q03.2	S1	relocation change	✓(111 s)	× (28 s)	✓(114 s)	memory
Q03.3	S1	relocation persist	✓(115 s)	× (28 s)	✓(86 s)	memory
Q04.2	S4	fire gone	✓(84 s)	△ (3 s)	✓(83 s)	memory+caution
Q04.3	S4	fire appears	○ (44 s)	○ (3 s)	○ (44 s)	memory+caution
Q05.2	S3	fire appears	○ (59 s)	× (29 s)	○ (59 s)	memory
Q05.3	S3	fire persists	○ (43 s)	× (28 s)	○ (41 s)	memory+caution
Q06.2	S4	fire gone	✓(83 s)	△ (3 s)	✓(83 s)	memory+caution
Q06.3	S4	fire appears	○ (31 s)	○ (3 s)	○ (32 s)	memory+caution
Q07.2	S1	relocation change	✓(108 s)	× (42 s)	✓(109 s)	memory
Q07.3	S1	relocation persist	✓(115 s)	× (39 s)	✓(72 s)	memory
Q08.2	S4	fire gone	✓(74 s)	△ (3 s)	✓(72 s)	memory+caution
Q08.3	S4	fire appears	○ (28 s)	○ (3 s)	○ (29 s)	memory+caution
Q09.2	S4	fire gone	✓(83 s)	△ (3 s)	✓(85 s)	memory+caution
Q09.3	S4	fire appears	× (85 s)	○ (3 s)	○ (44 s)	memory+caution
Q10.2	S2	relocation persist	✓(106 s)	✓(27 s)	✓(72 s)	memory
Q10.3	S2	relocation change	✓(83 s)	× (27 s)	✓(113 s)	memory
Q11.2	S2	relocation persist	✓(114 s)	✓(39 s)	✓(85 s)	memory
Q11.3	S2	relocation change	✓(74 s)	× (39 s)	✓(106 s)	memory
Q12.2	S3	fire appears	○ (42 s)	× (29 s)	○ (41 s)	memory
Q12.3	S3	fire persists	○ (29 s)	× (29 s)	○ (28 s)	memory+caution
Q13.2	S3	fire appears	○ (29 s)	× (29 s)	○ (28 s)	memory
Q13.3	S3	fire persists	○ (62 s)	× (28 s)	○ (28 s)	memory+caution
Q14.2	S2	relocation persist	✓(120 s)	✓(40 s)	✓(85 s)	memory
Q14.3	S2	relocation change	✓(75 s)	× (40 s)	✓(113 s)	memory
Q15.2	S1	relocation change	✓(125 s)	× (28 s)	✓(116 s)	memory
Q15.3	S1	relocation persist	✓(114 s)	× (28 s)	✓(96 s)	memory
Q16.2	S1	relocation change	✓(109 s)	× (41 s)	✓(112 s)	memory
Q16.3	S1	relocation persist	✓(108 s)	× (41 s)	✓(73 s)	memory

TABLE S9

WHEN EACH STUDY WAS REGISTERED AND WHEN ITS FIRST RESULTS ENTERED THE REPOSITORY. "ORDER" CHECKS THAT THE REGISTRATION COMMIT IS AN ANCESTOR OF THE FIRST RESULTS COMMIT (`GIT MERGE-BASE --IS-ANCESTOR`). REGISTRATIONS ARE ALSO MIRRORED IN THE PUBLIC REPOSITORY HISTORY. STUDIES WITHOUT RESULTS YET SHOW THE DRAFT COMMIT OR "REGISTERED AT MERGE, PENDING".

Study	Registered (commit, date)	First results (commit, date)	Amendments	Order
C (v3.3)	5c9a951 2026-10-16	5c9a951 2026-10-16	1	same commit
D (v3.4)	ac6d815 2026-10-16	fb4e9b3 2026-10-16	0	✓
T1	4ad4f4f 2026-10-16	c3d1ffc 2026-10-16	3	✓
E	6201aa0 2026-10-16	17e0ea6 2026-10-16	0	✓
T2	418f1c8 2026-10-17	7843e9c 2026-10-17	1	✓
F	418f1c8 2026-10-17	5bbf11a 2026-10-17	0	✓
G	0816e36 2026-10-17	f6160fb 2026-10-17	1	✓
R	fb63bee 2026-10-17	2337e49 2026-10-17	0	✓
H	9807d68 2026-10-17	389ffc8 2026-10-17	1	✓
J	8163f88 2026-10-17	016b36e 2026-10-17	0	✓
L	f0f3d52 2026-10-17	6a471e2 2026-10-17	0	✓
V	abf0c98 2026-10-17	de1cdca 2026-10-18	1	✓
W	cc0e103 2026-10-17	c3cb9bd 2026-10-18	2	✓
Z	a53ee7e 2026-10-17	0ca401d 2026-10-17	0	✓
K	3a21238 2026-10-17	9b2086f 2026-10-17	0	✓
P	e6bde02 2026-10-17	00795a8 2026-10-17	0	✓
P2	2910b2e 2026-10-17	f96af5f 2026-10-17	1	✓
A	1163eee 2026-10-18	d540165 2026-10-18	2	✓
S	5535660 2026-10-17	4a923ab 2026-10-18	0	✓
X	f0ddd78 2026-10-19	1f15351 2026-10-19	1	✓
XD	5535660 2026-10-17	3ae232e 2026-10-19	0	✓
Q	c7d06b3 2026-10-17	947888b 2026-10-19	0	✓
B	1c04256 2026-10-18	eb5b91b 2026-10-18	2	✓
IF	051e530 2026-10-17	26e2347 2026-10-18	0	✓
IF2	878cbc7 2026-10-18	c6acdcd 2026-10-19	0	✓
Y	9c0b5e8 2026-10-19	7dd3bc3 2026-10-19	0	✓
YE	34b1384 2026-10-19	dd7738e 2026-10-19	0	✓
YF	11d7599 2026-10-19	0fa75e9 2026-10-19	1	✓
GR	2c1d13a 2026-10-20	1a59c52 2026-10-20	0	✓
GC	5db5095 2026-10-20	2e50aa7 2026-10-20	1	✓
GD	a230246 2026-10-20	47ff908 2026-10-21	1	✓
GV	f6310cc 2026-10-21	76f7920 2026-10-21	0	✓
JH	7c7d6ce 2026-10-21	a323a3f 2026-10-22	0	✓
GL	e075bd5 2026-10-22	318b848 2026-10-22	0	✓
QI	9cf2574 2026-10-23	ddff91f 2026-10-23	5	✓
QJ	4990c94 2026-10-23	f3e00a3 2026-10-23	1	✓
GM	e3fa4a1 2026-10-23	2e944c8 2026-10-23	1	✓
JI	94a2e2e 2026-10-23	cd3e7b7 2026-10-24	0	✓
IG	e464ff1 2026-10-23	2e944c8 2026-10-23	0	✓
JC	08099fc 2026-10-23	cd3e7b7 2026-10-24	0	✓
IH	4bac0fa 2026-10-23	cd3e7b7 2026-10-24	0	✓
JK	4d467cf 2026-10-24	852831e 2026-10-24	4	✓
JL	9d7e7e1 2026-10-24	04d21e2 2026-10-25	0	✓
IJ	72d7c20 2026-10-24	38b5cd9 2026-10-25	0	✓
JM	3784986 2026-10-24	e7c95d3 2026-10-25	0	✓

TABLE S10

AMENDMENTS: ONE ROW PER AMENDMENT HEADING IN A REGISTRATION FILE, WITH THE COMMIT THAT INTRODUCED IT (TIME FROM `GIT`, NOT THE TIME WRITTEN IN THE TEXT, WHICH CAN DIFFER BY MINUTES) AND THE FIRST RESULTS COMMIT OF THE STUDY. THE TIMES WRITTEN INSIDE THE AMENDMENT TEXTS OF STUDY A (10:30 AND 10:55) WERE THE AUTHOR'S ESTIMATES; THE BINDING TIMES ARE THE COMMIT TIMES, AMENDMENT 1 AT 2A1BAB0 (2026-10-18 10:09) AND AMENDMENT 2 AT 1163EEE (2026-10-18 10:38), BOTH BEFORE ANY REGISTERED A TRIAL: THE MECHANICS PILOTS ARE NOT REGISTERED TRIALS, AND THE FIRST CAMPAIGN TRIAL RAN AFTER 2026-10-18 11:11. THE CAMPAIGN OF A STARTED AT 2026-10-18 11:11, AFTER BOTH AMENDMENTS: 226 OF 226 PLANNED RUNS ARE FINAL, 0 FAILED; ITS RESULTS ARE IN THE MAIN TEXT. FOR T1, T2, B, W, GM AND QI, TOO, THE DATE OR TIME WRITTEN IN SOME AMENDMENT HEADING IS LATER THAN ITS COMMIT (T1: THE DATE; T2: THE DATE; B: AMENDMENT 2; W: BOTH; GM: AMENDMENT 1, 9 MINUTES; QI: AMENDMENT 5, 10 MINUTES); EACH OF THESE REGISTRATION FILES ENDS WITH AN APPENDED "ERRATUM (TIMES)", AND THE COMMIT TIMES ARE BINDING. EVERY AMENDMENT OF A STUDY WITH RESULTS PRECEDES THAT STUDY'S FIRST RESULTS COMMIT (COLUMN ORDER), EXCEPT JK'S AMENDMENT 4: IT ENTERED WITH JK'S FIRST RESULTS (SAME COMMIT) AND MAKES THE CODE OF THE DESCRIPTIVE PREDICTION P3 COMPUTE P3 AS REGISTERED; IT CHANGES NO CLAIM, NO THRESHOLD AND NO TRIAL. THE *Amendments* COLUMN OF TABLE S9 COUNTS THESE HEADINGS.

Study	Amendment (text date)	Commit (git time)	First results	Order
C	2 (2026-10-16)	5c9a951 2026-10-16 12:42	5c9a951	same commit
T1	1 (2026-10-17)	d099095 2026-10-16 19:59	c3d1ffc	✓
T1	2 (2026-10-17)	858e232 2026-10-16 20:32	c3d1ffc	✓
T1	3 (2026-10-17)	4ad4f4f 2026-10-16 20:49	c3d1ffc	✓
T2	1 (2026-10-18)	564a724 2026-10-17 04:11	7843e9c	✓
G	1 (–)	0816e36 2026-10-17 07:59	f6160fb	✓
H	1 (–)	9807d68 2026-10-17 10:53	389ffc8	✓
V	1 (2026-10-17)	abf0c98 2026-10-17 18:10	de1cdca	✓
W	1 (2026-10-17 21:00)	ea88687 2026-10-17 20:46	c3cb9bd	✓
W	2 (2026-10-17 22:40)	d1c33f9 2026-10-17 22:33	c3cb9bd	✓
P2	1 (–)	2910b2e 2026-10-17 12:09	f96af5f	✓
A	1 (2026-10-18 10:30)	2a1bab0 2026-10-18 10:09	d540165	✓
A	2 (2026-10-18 10:55)	1163eee 2026-10-18 10:38	d540165	✓
X	1 (2026-10-19 05:00)	f0ddd78 2026-10-19 04:48	1f15351	✓
B	1 (2026-10-18)	ed8e48b 2026-10-18 01:38	eb5b91b	✓
B	2 (2026-10-18 03:20)	1c04256 2026-10-18 03:10	eb5b91b	✓
YF	1 (–)	11d7599 2026-10-19 20:12	0fa75e9	✓
GC	1 (–)	3df94ac 2026-10-20 18:05	2e50aa7	✓
GD	1 (–)	a230246 2026-10-20 23:52	47ff908	✓
QI	1 (2026-10-23)	a25b184 2026-10-23 00:03	ddff91f	✓
QI	2 (2026-10-23)	8a402df 2026-10-23 00:35	ddff91f	✓
QI	3 (2026-10-23)	b66dfc7 2026-10-23 00:42	ddff91f	✓
QI	4 (2026-10-23)	5d70c7e 2026-10-23 01:39	ddff91f	✓
QI	5 (2026-10-23 05:55)	9cf2574 2026-10-23 05:45	ddff91f	✓
QJ	1 (2026-10-23)	4990c94 2026-10-23 10:10	f3e00a3	✓
GM	1 (2026-10-23 12:30)	e3fa4a1 2026-10-23 12:21	2e944c8	✓
JK	1 (2026-10-24)	00aa3d1 2026-10-24 05:12	852831e	✓
JK	2 (2026-10-24)	487b5fa 2026-10-24 05:29	852831e	✓
JK	3 (2026-10-24)	4d467cf 2026-10-24 05:43	852831e	✓
JK	4 (2026-10-24)	852831e 2026-10-24 09:43	852831e	same commit

TABLE S11
TRUST BASE OF THE ADVICE GUARANTEE.

Component	Assumed of it	Not covered
VLM outputs as recorded	scores and labels are those the model returned for the saved image; malformed answers give no advice, a broken score is a hazard; server τ_h equals the configured one	a server that lies consistently (its τ_h is self-reported); scene text
`advice.plan` (about 60 lines of logic)	only reorders and adds caution	shared reader of the specification
advice audit	recomputes the invariant from the logged plan	a compromised node
mission gating	a check is skipped or a station refused unseen only in the naive baselines	the ROS wiring (reviewed by the authors; the interlock I-22 that would enforce A3 passed a Gazebo mechanics check on 4 missions, runs in study B and is off in A and X; no tampered-node test)
ground-truth recorder	outcome audit independent of the node's logs	simulator fidelity
model allow-list and pinned weights (`ALLOWED_MODELS`, `PINNED_REVISIONS`)	a fixed set of model identifiers, each with the Hugging Face commit of its weights; the server reports the snapshot it loaded and the client refuses another revision	the server's report: a server that lies about its snapshot, or a modified local cache, is not detected; runs recorded before this check carry no revision and are reported as unverified
same-host deployment	VLM server, mission node, recorder and audit run on one machine, and the audit reads files written by the node under test (the outcome audit uses simulator ground truth, not those files)	a compromised or shared host; network faults between components; any two-machine deployment
second implementation	written from the specification, not from the code; used for differential tests	independence of authorship: same authors, same AI assistant, same specification
destination parse	outside Prop. 2: closed-set parse plus rule	a mis-parse of the request

TABLE S12
THREAT MODEL FOR INPUTS THE ROBOT DID NOT PERCEIVE ITSELF. "STRUCTURAL": A GUARANTEE THAT DOES NOT DEPEND ON THE MODEL'S ANSWERS.

Channel	Example attack	Structural?	Measured by
Own memory	stale or poisoned record: "water at M", "no fire at W"	yes (Obs. 1, Prop. 2)	H, V (naive vs. verified memory)
Peer robot report, inventory	false "fire is out", wrong location, "verified, skip"; truthful location that steers	yes (Prop. 2), steering is exposure	A, file channel; A-steer
Operator wording (advice)	"the fire is out, no need to check"; "ignore previous instructions"	yes (Prop. 2); extraction itself is a model	A, operator channel; 224 offline texts
Operator wording (destination)	"deliver to shelter A", school or hospital	no: closed-set parser plus explicit rule, fail-closed	A offline set (wrong-shelter acceptance must be 0)
Scene text	label "WATER" on a first-aid kit; sign "SAFE – NO FIRE"; "Answer C"	no: it is perception	S
Camera degradation	noise, blur, over-exposure (not adversarial)	no: fail-closed behavior measured	R

TABLE S13
STUDY JH ON THE XD TEST SPLIT. JOINT MISS = FIRES NEITHER MODEL FLAGS (QWEN ALONE MISSES 14). φ = CORRELATION OF THE TWO MODELS' MISSES; THE JOINT MISS EXPECTED IF THE MISSES WERE INDEPENDENT AND THE FALSE STOPS OF THE UNION (OF 104 CLEAN WORLDS) FOLLOW.

Judge	cal. AUC	τ_J	judge miss	joint miss	φ	expected joint	false stops
InternVL3-8B (selected)	0.976	0.902	29	10	0.41	3.2	0
Idefics3-8B	0.933	0.137	28	8	0.30	3.1	1
SmolVLM2	0.954	0.028	23	9	0.42	2.6	4
Qwen3-VL (same family)	0.958	0.026	23	14	0.75	2.6	0

TABLE S14

ALL REGISTERED STUDIES. EACH IS REGISTERED (PROTOCOL, CONFIGURATION, ENDPOINTS AND ANALYSIS CODE) BEFORE ITS FIRST TRIAL OR INFERENCE (FOR THE 0 STUDIES WITHOUT RESULTS YET, THE DRAFTS NONE ARE REGISTERED WITH THE MERGE OF THE INTEGRATION BRANCH, BEFORE ANY OF THEIR TRIALS; TABLE S9); STUDIES WERE DESIGNED SEQUENTIALLY, EACH AFTER THE PREVIOUS RESULTS, SO REGISTRATION IS CONFIRMATORY WITHIN A STUDY (TABLE S9). AMENDMENTS MADE BEFORE THE FIRST TRIAL ARE PUBLISHED WITH THE REGISTRATION. CLAIM: STATUS OF THE REGISTERED CLAIM (DESCRIPTIVE: NONE REGISTERED; SUPPORTED, NOT SUPPORTED OR DESCRIPTIVE, AS REGISTERED).

Study	Question	Data	Arms (systems)	Primary endpoint	Claim
D	Does the v3.4 system behave as expected?	42 closed-loop trials, 3 scenes × variants	1 (v3.4)	expected behavior	descriptive
E	Does the check generalize to new variation?	600 held-out images, 60 worlds	1 (v3.5, s3.5, ablations secondary)	false approvals $\leq$ 2%	supported
U	Closed loop vs fixed, randomized worlds	60 trials, one world each	1 (v3.5, counterfactual)	expected behavior, wrong deliveries	descriptive
T2	Do hazard fixes chosen on dev data hold?	600 new held-out images	2 (v3.5: selected)	false approvals	not supported
F	Do they help in closed loop on small hidden fires?	24 worlds, paired	2 (v3.5, v3.6)	deliveries despite a visible fire	not supported
G	Does looking from the side help?	24 new worlds, paired	2 (v3.6, v3.6 + look-around)	deliveries despite a perceivable fire	supported
H	Can the check detect sensor/lens degradation?	36 sequences × 7 degradations	2 (v3.6 with no, native, verified memory)	false approvals $\leq$ 2%	supported
H	Can memory spend missions up without new risk?	36 sequences × 3 missions, changing worlds	2 (v3.6 with no, naive, verified memory)	time, unsafe deliveries	supported
J	Does the two-headed design run on the robot? (Sec. S11)	24 worlds, paired	2 (v3.6: Quest3-SR + ClefFlash)	completes on one GPU; unsafe deliveries	not supported
K	Does the 4-pass system work in real layouts?	24 worlds, paired	2 (v3.6, v4)	deliveries despite a visible fire	not supported
V	Does the deployed system avoid unsafe closed-loop behavior?	20 sequences × 6 missions, random change	3 (v3.6 with no, naive, verified memory)	unsafe deliveries, unsafe deliveries	wilder: supported; memory: not supported
W	How often is a small, partly hidden fire missed, and do prior mechanisms match ours?	150 fire × 75 fire-free worlds × 3 views (image level); T1 + T2 vs. vote and conformal baselines	2 (front only, look-around), 3 baselines	look-around miss bound $\leq$ 15% (Wilson); false approvals	bound: supported; cost: supported; prior art distinguished: 0/3
Z	Is a generative VLM useful?	T1 + T2, contrastive zero-shot baselines	2	false and correct approvals	supported
K	Does a conformal τ_h keep a miss bound?	211 dev fires → T2 (offline)	2 ($\alpha_h = 0.05, 0.10$) vs. frozen	held-out fire miss rate $\leq \alpha$	supported
PD	Does the check work on real phones?	1 phone, 1 scene, 3 lighting states	1 (v3.6 on device)	on-device vs. desktop accuracy	descriptive
PD	Does a site-calibrated τ_h make the hazard question usable on real phones?	DrFire: 400 calibration, 400 test images	2 wordings, vs. frozen	recall $\geq$ 0.80 and false alarms $\leq$ 0.20	supported
A	Can untrained advice relax a check, or steer it?	228 mini: 18 worlds (162 runs) × 16 duplicate-supply worlds (A-steer, 64 runs); 224 offline texts	lighten-only, naive, LLM-filter, scrutiny + control	unsafe deliveries under false advice; steering; time and cost bound	safety: supported; time: supported; cost: supported
S	Can a sign in the picture cause a wrong approval?	64 worlds × no sign, attack, benign	6 (ours, one pass, four-form, full image, OCR mask, ignore-text)	false approvals caused by the sign; defenses (non-adaptive signs)	letter: not supported; 2/7 hypotheses
XD	Does the check transfer to cluttered four-station depot images?	808 worlds (hard class 100), 1 932 images; 200 of 258 frozen warehouse photographs (396 Commons candidates, 136 excluded by a visual check before any scoring)	3 (front only, look-around, adaptive)	hard-class / super bound $\leq$ 0.15; relative claims O1-O6; recalibrated τ_h	brand: not supported; transfer: not supported; recalibration: not supported; cost: supported
X	Does the memory result transfer to a cluttered four-station depot?	59 closed-loop runs, $k = 4$	M0 vs. M2 (memory); control, tighten-only, scrutiny (steering)	M2 vs. M0: unsafe, time, visited stations; steering (descriptive)	memory: supported; steering: S1-S3 hold; S4 (scrutiny fewer unsafe, p=0.05) not supported (not claimed, as registered)
Y	Does continuing after a hazard refusal keep the delivery that truthful advice to a burning station loses?	51 closed-loop runs in the depot (45 steering, 6 without a clean station)	control, tighten-only, scrutiny, each with `--hazard-continue`	Y1–Y4: delivery from another station; exhaustion with no clean station; audit; at most 2 stations (unsafe deliveries descriptive)	availability: Y1–Y4 hold
YE	What is the exposure price of continuing, when a second fire is hidden at the next station?	24 closed-loop runs in two-fire depot worlds (12 worlds, 2 arms)	v3.6, `--hazard-continue`	YE1 v3.6 stops; YE2 mechanics (failed as registered); YE3 unsafe deliveries with an upper bound	mechanics: do not both hold; price: 2/12 (upper 44%)
YF	Does Y replicate on worlds that nobody had seen?	27 closed-loop runs in the depot (6 fire worlds, 3 twins; Amendment 1)	control, tighten-only, scrutiny, each with `--hazard-continue`	YF1 availability, YF3 audit, YF4 at most 2 stations (failed); F3 (failed)	availability on fresh worlds: YF1, YF3, YF4 do not all hold
Q	Does the supply check work on real photographs?	465 Commons photographs	1 (v3.6 supply check)	false-approval upper bound ≤ 0.05 and correct approvals ≥ 0.70	safety: supported; availability: not supported; transfers: not supported
B	Does the advice credit cap the price of a source that is wrong at every mission, in closed loop? (mechanics study, Prop. 3)	4 sequences × 6 missions × 2 arms × 48 runs, $k = 2$	2 (tighten-only advice with and without the credit ledger)	wasted visits $\leq C_{\text{lie}} + \rho m$ (deterministic prediction); no safety claim	credit bound: supported
IF	Can the request text switch the requested supply (R6 9?)?	72 texts (6 categories × 2 languages × 2 supplies × 3 wordings), offline parser	1 (frozen v3.6 intent parser)	share of the 36 flip texts accepted with the injected supply (Wilson upper bound < 0.10); price is refusal corrections (descriptive)	IF1 not supported: 12/36 switched
IF2	Does asking back on a supply conflict stop request switching (I-27)?	72 new texts (same categories, new wordings), offline parser	2 (v3.6 with and without the ask-back rule)	share of the 36 flip texts accepted with the injected supply (Wilson upper bound < 0.10); controls accepted $\geq 11/12$	IF2 supported: 0/36 switched with ask-back

TABLE S15

PARTS THAT DIFFER BETWEEN STUDIES (V3.6 CHECK IN ALL).

Study	Intent prompt	View policy / other
W, XD (image level)	n/a	front, look-around, adaptive views (I-20) compared
A (closed loop + offline)	`i38` (Amendment 1)	look-around on; advice flags differ
B (closed loop)	default (`i35`)	look-around on; deterministic advice source
IF	`i35`	offline parser, no ask-back
IF2	`i35`	ask-back rule off vs. on (I-27)
S (image level)	n/a	front view scored; look-around as secondary arm
X (closed loop)	default (`i35`)	memory arms: look-around; adaptive arm add extra views

TABLE S16

STUDY S: MUST-REFUSE WORLDS APPROVED BY EACH SYSTEM (OF 42), WITHOUT A SIGN, WITH AN ATTACK SIGN AND WITH A BENIGN TEXT; FLIPS: REFUSED WITHOUT THE SIGN, APPROVED WITH IT.

System	no sign	attack sign	benign text	flips
OURS	0/42	0/42	0/42	0
ONE-PASS	0/42	0/42	0/42	0
FREE-FORM	5/42	3/42	2/42	1
OURS-FULL	0/42	1/42	1/42	1
OURS+LA	0/42	0/42	0/42	0
OCR-MASK	0/42	0/42	0/42	0
IGNORE-TEXT	0/42	0/42	0/42	0

TABLE S17

STUDY XD: HAZARD WORLDS APPROVED (MISSES) BY THE FRONT CHECK ONLY, BY LOOK-AROUND, AND WHEN THE I-20 EXTRA VIEWS ARE ADDED, BY HAZARD APPEARANCE.

Class	Worlds	Front only	Look-around	+ extra views
small flames, partly hidden	100	49/100	12/100	2/100
big flames, visible	12	0/12	0/12	0/12
smoke only	20	1/20	1/20	0/20
mesh flames	11	3/11	1/11	0/11
sprite flames	8	2/8	0/8	0/8
all perceivable	151	55/151	14/151	2/151

TABLE S18

STUDY X-S: HAZARD PROBABILITY p_h OF THE FRONT VIEW AND OF THE TWO LOOK-AROUND VIEWS AT THE STEERED STATION, BY WORLD AND ARM (A TRAVELING 2 MARKS THE FIRE-FREE TWIN OF A WORLD; THE SCRUTINY ARM REFUSES AT THE FIRST VIEW WITH $p_h \geq 0.01$ AND TAKES ANOTHER LOOK; THRESHOLDS: 0.05, SCRUTINY 0.01). POST HOC READOUT OF THE SAVED MODEL OUTPUTS (I-41, `SCRIPTS/X_READOUT.PY`), NOT A REGISTERED ANALYSIS.

Run	World	Arm	Front view p_h	Look-around p_h (L, R)	Outc
X027	XC05	control	0.0075	0.0113, 0.0119	ALL
X029	XC05	monotone	0.0132	0.0141, 0.0099	ALL
X028	XC05	scrutiny	0.0128	not taken	DEN
X059	XC15	control	0.0061	0.0067, 0.0073	ALL
X058	XC15	monotone	0.0090	0.0057, 0.7187	DEN
X057	XC15	scrutiny	0.2174	not taken	DEN
X031	XC24	control	0.0090	0.0083, 0.0093	ALL
X032	XC24	monotone	0.0252	0.0177, 0.2121	DEN
X030	XC24	scrutiny	0.0312	not taken	DEN
X043	XC05t	control	0.0049	0.0099, 0.0102	ALL
X042	XC05t	monotone	0.0117	0.0200, 0.0087	ALL
X041	XC05t	scrutiny	0.0124	not taken	DEN
X053	XC24t	control	0.0041	0.0077, 0.0121	ALL
X052	XC24t	monotone	0.0068	0.0048, 0.0069	ALL
X054	XC24t	scrutiny	0.0102	not taken	DEN

TABLE S19

ARENA VERSUS DEPOT (k: STATIONS; M0, M2: NO MEMORY, VERIFIED MEMORY; LETTERS: STUDIES, TABLE II). DEPOT CELLS ARE THOSE OF XD AND X (SECS. S12.5, S12.6); THE LAST COLUMN STATES THE EXPECTED TRANSFER IN ADVANCE.

Quantity	Arena	Depot	Transfers?
Stations k	2	4	–
$\hat{\varepsilon}$ with Wilson (Wilson upper)	1/16 (0.28); W: 3/150 (5.7%)	14/151 (15.0%); hard class 12/100 (19.8%)	no
Gate fire $\hat{\varepsilon}$ and τ_h on held-out images	T1: 3/408	XD: 0/35 wrong-supply (upper 9.9%)	no
τ_h (frozen / recalibrated)	0.05 / –	0.05 / none (recall 79.0% at 0.05)	no
Unsafe (T1: of 32 in H; no M1 arm in the depot)	1 / 0	X: 0 / 0 (no fire in X-m; 0 wrong-supply deliveries)	M2 vs. M0: yes
Median time, M0 → M2, relocation persists	114 → 79 s (all missions: 83 → 73 s)	X: saving 75 s ([33, 96]), 36.8 s per extra station	size: no
Stale-proposal price (changed back)	97 → 113 s	X: no stale proposal arose	grows with k
Steering (S: wasted advice (descriptive; no naive arm in the depot)	A-steer: unsafe 2/16, lost 14/16	X-s: unsafe 1/3 (no advice 0/3), lost 2	cost: yes